

FUNCTIONAL SERVICING AND PRELIMINARY STORMWATER MANAGEMENT REPORT

RESIDENTIAL SUBDIVISION
537086 MAIN STREET, HORNING'S MILLS
TOWN OF MELANCTHON



PEARSON
ENGINEERING

PEARSONENG.COM

March 2024

23008



TABLE OF CONTENTS

1. INTRODUCTION	1
1.1. TERMS OF REFERENCE	1
2. SUPPORTING DOCUMENTS	1
3. WATER DESIGN.....	2
3.1. INDIVIDUAL WELL DESIGN	2
4. SANITARY DESIGN	2
4.1. INDIVIDUAL SEPTIC BED DESIGN	2
5. STORMWATER MANAGEMENT	2
5.1. OVERVIEW	2
5.2. ANALYSIS METHODOLOGY	3
5.3. EXISTING DRAINAGE CONDITIONS	3
5.4. HORNING'S MILLS CREEK.....	3
5.5. PROPOSED DRAINAGE CONDITIONS	4
5.6. STORMWATER QUANTITY CONTROL	4
5.7. LOW IMPACT DEVELOPMENT	5
5.8. QUALITY CONTROL	6
5.8.1. PERMANENT QUALITY CONTROL	6
5.8.2. QUALITY CONTROL DURING CONSTRUCTION	6
6. PHOSPHORUS BUDGET	6
7. WATER BALANCE.....	7
8. GRADING.....	7
9. SECONDARY UTILITIES	7
10. CONCLUSIONS	8



APPENDICES

- Appendix A** – Sanitary Flow Calculations
- Appendix B** – Stormwater Management Calculations
- Appendix C** – Pre-Development OTTHYMO Results
- Appendix D** – Post-Development OTTHYMO Results
- Appendix E** – Phosphorous Budget Calculations
- Appendix F** – Water Balance Calculations
- Appendix G** – Geotechnical Investigation Report, Cambium Inc., March 11th, 2024
- Appendix H** – Pearson Engineering Drawings

LIST OF FIGURES & DRAWINGS

- Figure 1** - Site Location Plan
- Dwg SGS 1** - Preliminary Site Servicing and Grading Plan
- Dwg STM 1** - Pre-Development Storm Catchment Plan
- Dwg STM 2** - Post-Development Storm Catchment Plan
- Dwg PND 1** - Stormwater Management Pond



FUNCTIONAL SERVICING AND PRELIMINARY STORMWATER MANAGEMENT REPORT CARNEVALE'S, 537086 MAIN ST, HORNING'S MILLS

1. INTRODUCTION

PEARSON Engineering Ltd. has been retained by the Carnevale's (Client) to prepare a Functional Servicing Report (FSR) in support of the proposed residential subdivision (Project) located at 537086 Main Street, in the Township of Melancthon (Town).

The subject property is approximately 10.2 ha in size and is located in Horning's Mills in the Township of Melancthon (Township), County of Dufferin (County). The site is bound by Dufferin County Road 124 to the west, existing agricultural lands to the north and south and Main Street to the east. The Project site is currently agricultural lands, and the majority of the site drains west to east towards Main Street. The location of the site can be seen on Figure 1.

This FSR assesses the onsite Stormwater Management (SWM) facilities and internal services required to service the proposed Project. The report also includes preliminary design calculations and a brief outline of the proposed internal services, as well as comments regarding the ability of the various secondary utilities to service the site.

1.1. TERMS OF REFERENCE


- Identify the existing site characteristics including any external drainage conditions.
- Illustrate the design of the stormwater conveyance and detention system, capable of accommodating both minor and major storm flows from the site;
- Incorporate the appropriate Best Management Practices for controlling on-site erosion and sedimentation during construction while ultimately ensuring that the pos-development release of stormwater is of adequate quality; and
- Summarize this design in a technically comprehensive and concise manner.

2. SUPPORTING DOCUMENTS

The following documents have been referenced in the preparation of this report:

- Ministry of the Environment, Design Guidelines for Sewage Works, 2008
- Ministry of the Environment, Design Guidelines for Drinking Water Systems, 2008
- Ministry of the Environment, Stormwater Management Planning and Design Manual, March 2003
- Nottawasaga Vally Conservation Authority Technical Guidelines for Stormwater Management Submissions, September 2016

C:\Users\mparmar\AppData\Local\Temp\AcPublish_30156\23008 - BASE - SITE LAYOUT.dwg Layout:FIG-1 Plotted Feb 29, 2024 @ 11:09am by mparmar © PEARSON ENGINEERING LTD.



CARNEVALE'S
537086 MAIN ST., HORNING'S MILL
TOWNSHIP OF MELANCTHON

SITE LOCATION PLAN



PEARSON
ENGINEERING
PEARSONENG.COM PH. 705.719.4785

DESIGNED BY	AMC/IR	HORIZ SCALE	N/A	PROJECT #	23008
DRAWN BY	NP/IR	VERT SCALE	N/A	DRAWING #	FIG-1
CHECKED BY	MWD	DATE	APRIL 2023	REVISION #	0



3. WATER DESIGN

3.1. INDIVIDUAL WELL DESIGN

There is no municipal watermain adjacent to the project site, and therefore the subdivision will be serviced by private wells. Individual well supply will be implemented by an authorized well driller. The location and detailed well design for individual wells will be developed through a detailed plot plan and building permit application process. The preliminary location of individual wells is shown on the Preliminary Site Servicing and Grading drawing SSG-1.

4. SANITARY DESIGN

4.1. INDIVIDUAL SEPTIC BED DESIGN

There are no municipal services fronting the Project site. As such, the subdivision will be serviced with individual septic beds for each individual lot. Residential septic bed design with daily sanitary sewage flows less than 10,000 L/day are governed by part 8 of the Ontario Building Code (2016).

Preliminary filter bed size calculations have been completed and were based on a T-time of 30 min/cm, which is the highest T-time noted in the Geotechnical Investigation completed by Cambium Inc., dated March 11, 2024 (refer to appendix G). The T-time of 30 min/cm is considered to be conservative for the development as the range provided is between 10-30 min/cm with most of the samples being less than 20. Once T-time is confirmed for each lot by installer, the septic bed sizes will be reduced accordingly.

Based on a 4 bedroom home of 320 m², the area required for the filter bed with a t-time of 30 will be approximately 400 m². Preliminary bed and house locations for each lot can be seen on the Preliminary Site Servicing and Grading Drawing SSG-1.

5. STORMWATER MANAGEMENT

5.1. OVERVIEW

A key component of the development is the need to address environmental and related SWM issues. These are examined in a framework aimed at meeting the Township of Melancthon, Nottawasaga Valley Conservation Authority (NVCA), and the Ministry of the Environment, Conservation, and Parks (MECP) requirements. This report focuses on the necessary measures to satisfy the MECP's SWM requirements.

It is understood the objectives of the SWM plan are to:

- Protect life and property from flooding and erosion.
- Maintain water quality for ecological integrity, recreational opportunities etc.
- Protect and maintain groundwater flow regime(s).
- Protect aquatic and fishery communities and habitats.
- Maintain and protect significant natural features.
- Incorporate Low Impact Development (LID) practices to promote infiltration and reduce phosphorus levels to downstream watercourses.



5.2. ANALYSIS METHODOLOGY

The design of the SWM Facilities for this site has been conducted in accordance with:

- The Ministry of the Environment Stormwater Management Planning and Design Manual, March 2003.
- Nottawasaga Valley Conservation Authority (NVCA) Stormwater Technical Guide, December 2013.

In order to design the facilities to meet these requirements, it is essential to select the appropriate modeling methodology for the storm system design. Given the size of the site, the hydrologic modeling software visual OTTHYMO, is appropriate for the design for the SWM system.

5.3. EXISTING DRAINAGE CONDITIONS

The project site currently consists of vacant farmland with a small treed area along the north property lines. The majority of the site drains east at a slope of 1% - 5% towards the roadside ditch adjacent to Main Street while the eastern portion of the site drains east towards the Horning's Mills Creek. A portion of the northwestern corner of the site drains northerly, and an existing residential lot southwest of the site drains through the project site. Details of the existing storm drainage conditions are shown on Drawing STM-1.

The Cambium geotechnical investigation revealed that the site is composed of a surficial topsoil layer containing organics underlain by silty sand, predominately containing organics. The silty sand containing organics extended to a depth of about 0.8 m below ground surface and contained trace amount of gravel and clay. As the proposed site will be comprised of estate lots serviced with individual wells and septic systems, additional groundwater monitoring and water quality tests will be required. Throughout the four boreholes and three monitoring wells completed by Cambium, groundwater was only encountered within monitoring well (#BH104-23) at a depth of 4.3 m below existing ground surface. Refer to Appendix G for more information.

The Visual OTTHYMO hydrologic modelling software was used to determine the pre-development peak flows for the site for 2-year storm up to the 100-year storm and Regional Storm and are shown in Table 1. The Visual OTTHYMO Parameter calculations can be found in Appendix B, and pre-development OTTHYMO modelling output results can be found in Appendix C.

Table 1: Pre-Development Peak Flows

	2 Year Storm	5 Year Storm	10 Year Storm	25 Year Storm	50 Year Storm	100 Year Storm	Regional Storm
4-Hour Chicago Storm (m ³ /s)	0.16	0.31	0.43	0.60	0.73	0.88	-
24-Hour SCS Storm (m ³ /s)	0.30	0.55	0.75	1.01	1.21	1.42	0.96

5.4. HORNING'S MILLS CREEK

Based on NVCA regulation mapping, the proposed subdivision is located adjacent to the Horning's Mills Creek. The Generic Regulations Floodplain model was obtained from NVCA, which is based on their digital elevation model (DEM) which are accurate to ± 1.0 m. By comparing the elevations in the model to the site's topographic survey, a surface adjustment factor of 0.60 m was calculated.



The proposed SWM pond lies between cross sections 629.5018 and 708.895 to the west of the Horning's Mills Creek. The model data provided by NVCA shows that cross section 629.5018 has a floodline elevation of 458.37 and 708.895 has a floodline elevation of 458.41. Therefore, the existing floodline was increased by the adjustment factor of 0.60 m and calculated to be 458.97 m at cross section 629.5018 and 459.01 at cross section 708.895. A summary of floodline elevations can be seen in Table 2 below.

Table 2: Horning's Mills Creek Floodline Elevations

HEC-RAS Cross Section Station (m)	Regulation NVCA Model Floodline Elevation (m)	Adjusted Floodline Elevation (m)
629.5018	458.97	458.97
708.895	459.01	459.01

5.5. PROPOSED DRAINAGE CONDITIONS

The post-development storm drainage for the project will generally follow pre-development conditions. The proposed development consists of 26 residential estate lots with 0.77 ha of parkland, and a SWM pond block. The majority of the proposed drainage from the project will be conveyed easterly via roadside ditches to a dry pond located at the northeast corner of the site. The south portion of the site will flow southerly uncontrolled towards Horning's Mills Creek. Peak flows will be released from the SWM pond with the use of a hickenbottom complete with orifice tube to reduce post-development peak flows to at or below pre-development values. Peak Flow released from the dry pond will be conveyed through an Oil Grit Separator (OGS) unit to provide quality control prior to discharge into the existing roadside ditch on Main Street.

As per Azimuth's Environmental Impact Study (2024), the wetland area located to the northeast corner of the project site will be maintained and a 5.0 m buffer has been applied to it. The proposed SWM pond outlet will bypass the wetland and drain into the existing roadside ditch on Main Street.

The Project's drainage ditches will be sized to convey all storms up to and including the 100-year storm event. Driveway culverts have been sized using the 10-year storm event flows. The proposed culverts across Street 'A', Street 'B' and SWM pond access road have been designed to convey the 10-year storm event without overtopping the road surface.

Lots 1-14 as well as lots 24-26 will be split drainage. A rear yard swale along the north property is proposed which will convey flows from the rear portion of the lots to the proposed SWM pond. The proposed ditch located within the parkland area conveys flows from Street 'B', Lots 22 to lot 26 and Lot 21 to Lot 24 which will convey stormwater to the proposed roadside ditch on Street 'A' and ultimately to the SWM pond. Refer to drawing STM-2 for proposed drainage patterns.

5.6. STORMWATER QUANTITY CONTROL

The proposed development will increase the imperviousness of the site and as such, the post-development peak flows will increase. The majority of the proposed drainage from the project will be conveyed easterly to a dry pond located in the northeast corner of the development, which has been designed to provide quantity control by retaining flows and releasing them at or below pre-development values. The outlet control structure for the SWM pond will consist of an orifice tube located within a hickenbottom structure and an overflow weir which will reduce post-development peak flows to allowable values for all storm events. The proposed dry pond has been designed with a 4:1 side slopes as per MECP guidelines. 2,266 m³ of quantity control storage volume in the dry pond is required to reduce post development peak flows for the 2-year to 100-year storm events. The dry pond has a storage volume of 2395 m³ at an elevation of 462.15, providing approximately 0.30 m of freeboard to the top of berm. Rip-rap will be placed at the inlet and at the emergency overflow weir location to prevent erosion. Based on the Site Evaluation Report by Azimuth



Environmental Consulting, Inc., Horning's Mills Creek is a coldwater system. Temperature mitigation measures such as a cooling trench will be investigated further at the detailed stage of the project based on recommendations in the environmental report.

Table 3 summarizes post-development peak flows and storage volume requirements for the SWM pond.

Table 3: SWM Pond Outflow and Storage

	2 Year Storm	5 Year Storm	10 Year Storm	25 Year Storm	50 Year Storm	100 Year Storm	Regional Storm
4 Hour Chicago Storm Events							
Peak Flows (m ³ /s)	0.12	0.26	0.34	0.48	0.57	0.72	-
Storage Volume (m ³)	630	842	1,008	1,249	1,407	1,625	-
24 Hour SCS Storm Events							
Peak Flows (m ³ /s)	0.20	0.39	0.56	0.73	1.01	1.17	0.73
Storage Volume (m ³)	773	1,134	1,372	1,719	1,990	2,266	1,728

Table 4 below summarizes the post-development peak flows for the site and demonstrates that the total site peak flow is at or below pre-development flows.

Table 4: Post-Development Peak Flows

	2 Year Storm	5 Year Storm	10 Year Storm	25 Year Storm	50 Year Storm	100 Year Storm	Regional Storm
4-Hour Chicago Storm (m ³ /s)	0.12	0.28	0.38	0.53	0.64	0.81	-
24-Hour SCS Storm (m ³ /s)	0.22	0.44	0.64	0.83	1.13	1.31	0.81

5.7. LOW IMPACT DEVELOPMENT

Current SWM practices have evolved over recent years, with Low Impact Development (LID) techniques being widely used as the preferred method of Stormwater Management. As such, it is proposed that LID techniques be implemented throughout the development to meet Township and NVCA requirements.

The estate lot nature of the proposed development will help minimize the degradation of storm runoff when compared to higher density developments. Stormwater runoff from the rooftop will be directed to roadside ditch through side yard swales which will convey stormwater to a proposed SWM pond. Low Impact Development (LID) controls will be implemented where available to improve storm runoff quality and will be reviewed in greater detail at the detailed design stage of the project.



5.8. QUALITY CONTROL

The MECP issued a “Stormwater Management Planning and Design Manual” in March 2003. This manual has been adopted by a variety of agencies including the Township of Melancthon. The development’s Stormwater Quality Control objective is to provide Enhanced Protection quality control as stated in the MECP manual. To achieve enhanced protection, permanent and temporary control of erosion and sediment transport are proposed and are discussed in the following sections.

5.8.1. PERMANENT QUALITY CONTROL

The development’s active roadways pose a risk to stormwater quality through the collection of grit, salt, sand, and oils on the paved surfaces. The majority of the development’s stormwater will drain into the SWM pond. An oil/grit separator (OGS) unit is proposed at the outlet of the SWM Pond which will treat stormwater prior to outletting to the existing ditch on Main Street. The MECP standard stipulates a Total Suspended Solids (TSS) removal of at least 80%. The OGS unit will treat the post development flows to the required MECP quality standard with a minimum TSS removal rate of 80%. The OGS sizing and model information will be provided at the detailed design stage.

5.8.2. QUALITY CONTROL DURING CONSTRUCTION

During construction, earth grading and excavation will create the potential for soil erosion and sedimentation. It is imperative that effective environmental and sedimentation controls are in place and maintained throughout the duration of construction activities to ensure the stormwater runoff’s quality. Therefore, the following recommendations shall be implemented and maintained during construction to achieve acceptable stormwater runoff quality:

Installation of filter strips, silt fences and rock check dams or other similar facilities throughout the site, and specifically during all construction activities, in order to reduce stormwater drainage velocities and trap sediment on-site; and,

- Restoration of exposed surfaces with vegetative and non-vegetative material as soon as construction schedules permit; the duration in which surfaces are disturbed/exposed shall not exceed 30 days.
- Provision of a mud-mat where applicable at the construction entrances in order to control the tracking of sediment and debris onto municipal streets.
- Reduce stormwater drainage velocities where possible.
- Minimize the amount of existing vegetation removed.

6. PHOSPHORUS BUDGET

Local conservation authorities have determined the importance of reducing phosphorus levels in water courses. Best efforts are proposed in order to reduce phosphorus levels to pre-development levels or better.

The existing site consists of cultivated land and a small treed area and generates approximately 0.79 kg of phosphorus annually. The development of the project will increase the amount of phosphorus contributed from the site to 3.20 kg annually if uncontrolled. To minimize the site’s phosphorous discharge, a treatment train approach will be implemented. Stormwater from the rooftop area will drain to soakaway pits for infiltration. Stormwater that doesn’t infiltrate will overflow to the surface and drain to the roadside drainage ditch conveyance system and ultimately to the proposed SWM Pond. Stormwater will then be conveyed through an OGS treatment unit prior to outlet to the roadside ditch on Main Street.



According to the NVCA Phosphorus Loading Tool, a reduction of 10% is provided for dry detention ponds, 20% for OGS units, and 100% for infiltration. As per water balance calculations, the soakaway pits have been sized to infiltrate 71% of annual rainfall, therefore a phosphorous reduction of 71% was utilized. Table 5 below details the anticipated phosphorus loading for pre- and post-development conditions for the total site based on the above noted treatment train approach. Detailed phosphorus loading calculations derived from NVCA Phosphorus Loading Tool for the project can be found in Appendix E.

Table 5: Phosphorus Loadings

	Total P (kg)
Pre-Development	0.79
Uncontrolled Post-Development	3.20
Controlled Post-Development	1.78

7. WATER BALANCE

Since the post-development state will increase the imperviousness of the site, considerations were taken in regard to groundwater recharge. A water budget was completed as per NVCA guidelines. Calculations were completed comparing the current condition infiltration volumes to post-development infiltration volumes. In the pre-development conditions, the site provides 25,911 m³ of infiltration annually. In the post development condition, the site provides 20,821 m³ of infiltration volume resulting in a deficit of 5,090 m³ annually.

In order to infiltrate an additional 5,090 m³ annually, a yearly rainfall depth of 611.8 mm from the rooftop is required to be infiltrated. This percentage of annual rainfall occurs for rain events of 10 mm or less resulting in a total storage volume of 83 m³. As per the Geotechnical Investigation completed by Cambium, the groundwater was encountered at 4.3 m below existing surface within monitoring well located to the northeast portion of the site.

A total of twenty-six 4.00 m x 1.90 m soakaway pits are proposed in the front yard of all the lots, which will infiltrate 98.8 m³ from the rooftop area which is more than the required storage volume. Detailed water balance and soakaway pits calculations can be found in Appendix F.

8. GRADING

A preliminary grading design has been completed for the project and has been designed to generally drain storm runoff to the northeast corner of the property at an average grade of 2.0% to 5.0% allowing the majority of the site to be conveyed to the proposed SWM pond. A small portion to the northeast corner of the site will drain uncontrolled to Main Street. Majority of the parkland area will drain uncontrolled to the Horning's Mills Creek. A split drainage is provided for Lots to the north of Street 'A' have split drainage, lots to the south of Street 'A' and west of Street 'B' have rear to front drainage and lots to the east of Street 'B' have front to rear drainage and are self contained where possible. Refer to drawing SGS-1 for details of the preliminary grading design.

9. SECONDARY UTILITIES

Although there are no municipal services adjacent to the Project site, it is anticipated that secondary utilities (hydro, cable, phone and gas) will be readily available to service the site. Due to the rural nature of the development site, letters will be sent to utilities to confirm the location of existing utilities at the detailed design stage.



10. CONCLUSIONS

The proposed development will require septic beds and wells to service individual houses.

Quantity control for the development will be provided through the use of a proposed dry SWM pond controlling post-development flows to pre-development levels.

Quality control is provided by an OGS treatment unit and SWM pond.

To reduce phosphorus levels leaving the site, a treatment train approach will be implemented consisting of rooftop infiltration, dry SWM Pond and OGS treatment unit.

The analysis and designs outlined in this report demonstrates that servicing of the site is feasible.

All of which is respectfully submitted,

PEARSON ENGINEERING LTD.

Taylor Arkell, P. Eng.
Senior Project Manager

Mike Dejean, P.Eng.
Partner, Manager of Engineering Services





APPENDIX A

SANITARY FLOW CALCULATIONS

GSP Group Inc., Horning's Mills
Sanitary Flow Calculations

CLIENT: GSP Group Inc.
PROJECT: 537086 Main Street, Horning's Mills
FILE: 23008

Date: 22-Mar-24
Designer: NP

Property Information

DESCRIPTION	Total Floor Area	Total Flow
Residential Subdivision	320.0 sq.m	3200 L/day (Table 8.2.1.3.B)
Q = 3200 L/day T = 30 min/cm (Based on Geotechnical Report) Level of Pre-Treatment = Primary		
FILTER BED (OBC 8.7.5.)		
$A_{stone} = Q/75$ (if $Q < 3000$)		
$A_{stone} = Q/50$ (if $Q > 3000$)	$A_{stone} =$	64.0 sq.m
$A_{stone} = Q/100$ (if Tertiary treatment is being used)		
where		
A = total area of sand layer in metres squared		
Q = the total daily design sanitary sewage flow in litres		
$A_{sand} = Q \cdot T / 850$	$A_{sand} =$	112.9 sq.m
where		
A = the area of contact in meters squared between the soil base of the filter medium and the underlying soil		
Q = the total daily design sanitary sewage flow in litres		
T = the design percolation time in minutes		
$A_{mantle} = Q / L_R$	$A_{mantle} =$	400.0 sq.m *
where		
A = the area of the mantle in meters squared		
L_R = Loading Rates (8L/m² for 20 < T ≤ 35 min as per OBC Table 8.7.4.1)		
TYPE A DISPERSAL (OBC 8.7.7.)		
$A_{sand} = Q \cdot T / 850$ (if $T < 15$ min/cm)		
$A_{sand} = Q \cdot T / 400$ (if $T > 15$ min/cm)	$A_{sand} =$	240.0 sq.m
where		
A = total area of sand layer in metres squared		
Q = the total daily design sanitary sewage flow in litres		
T = the design percolation time in minutes		
(OBC 8.7.7.)		
$A_{stone} = Q/B$ (where $B = 50$ if $Q > 3000L$)		
$A_{stone} = Q/B$ (where $B = 75$ if $Q < 3000L$)	$A_{stone} =$	64.0 sq.m
where		
A = total area of stone layer in metres squared		
Q = the total daily design sanitary sewage flow in litres		
Note: * indicates the area of septic bed drawn in the drawings		

GSP Group Inc., Horning's Mills

DESCRIPTION	Total Floor Area	Base Flow
4 Bedroom Dwelling	320.0	2000 L/day

Fixture		Fixture Count	Fixture Load	TOTAL Hydraulic Load / Fixture Units
Drinking Fountain	Domestic	1	1.5	1.5
	Commercial		3	0
			0.5	0
			1.5	0
Fish Tank or Tray				
Floor Drain				
Garbage Grinder (commercial)	2" Trap	1	2	2
	3" Trap		3	0
			3	0
			1	0
Icebox				
Laundry Tray	Single/Double	1	1.5	1.5
	3 Compartment		2	0
Lavatory				
Potatoe Peeler	Barber or beauty parlor		1.5	0
	Dental Lavatory		1	0
	Domestic type single w/ 1.25" Trap		1	0
	Domestic type single w/ 1.5" Trap		1.5	0
	multiple or industrial type		3	0
			3	0
Shower Drain				
Sink	from 1 head		1.5	0
	from 2 or 3 heads		3	0
	from 4 to 6 heads		6	0
	Domestic and other small type without garbage grinders	1	1.5	1.5
	other sinks			
	1.5" Trap		1.5	0
	2" Trap		2	0
	3" Trap		3	0
Total		9		32.0

Total Flow 3200 L/day



APPENDIX B

STORMWATER MANAGEMENT CALCULATIONS

GSP Inc., Horning's Mill
Pre-Development OTTHYMO Parameters

Drainage ID	=	100	
Cultivated	=	10.24	ha.
Woods Area	=	1.01	ha.
Impervious area	=	0.10	
Total Area	=	11.35	ha.

Based on soils revealed in Cambium Inc.'s Geotechnical Investigation and Borehole Logs, the following Soil Group was assumed:

Hydrologic Soils Group:	=	B	
CN Value is as follows:			
CN	=	74	(Cultivated as per NVCA Guidelines)
CN	=	60	(Woods as per NVCA Guidelines)
CN	=	100	(Impervious as per NVCA Guidelines)
CN	=	$\frac{74 \times 2.91 + 60 \times 0.08 + 100 \times 0.10}{11.35}$	
CN	=	73	
IA Value is as follows:			
IA	=	7	(Cultivated as per NVCA Guidelines)
IA	=	10	(Woods as per NVCA Guidelines)
IA	=	2	(Impervious as per NVCA Guidelines)
IA	=	$\frac{7 \times 2.91 + 10 \times 0.04 + 2 \times 0.10}{11.35}$	
IA	=	7.2	
Runoff Coefficient Value is as follows:			
C	=	0.35	(Cultivated as per NVCA Guidelines)
C	=	0.25	(Woods as per NVCA Guidelines)
C	=	0.95	(Impervious as per NVCA Guidelines)
C	=	$\frac{0.34 \times 2.91 + 0.25 \times 0.04 + 0.95 \times 0.10}{11.35}$	
C	=	0.35	

Find Time to Peak using Airport Equation and Uplands Method

<u>Airport Equation</u>	$T_c = 3.26(1.1 - c)L^{0.5}S_w^{-0.33}$	
Length (L)	=	499 m
Elevation 1 (El ₁)	=	483.87 m
Elevation 2 (El ₂)	=	458.14 m
Slope (S)	=	0.052 m/m
Time of Concentration (T _c)	=	31.79 minutes
Total Time of Concentration (T _c)	=	31.79 minutes
T _c	=	0.53 hrs.
Time to Peak (T _p = 2/3 T _c)	=	0.35 hrs.

<u>Uplands Method</u>			
Section	=	1	2
Land Cover	=	Pasture	Woods
Length	=	125 m	44 m
Slope	=	0.052 m/m	0.052 m/m
Velocity	=	0.52 m/s	0.52 m/s
Time	=	0.07 hrs.	0.02 hrs.
Total Time	=	0.09 hrs.	

Governing Time to Peak

<u>Airport Equation</u>		
T _c	=	0.53 hrs.
T _p	=	0.35 hrs.
D _T (1/5 T _p)	=	4 mins.

GSP Inc., Horning's Mill
Post-Development OTTHYMO Parameters

Drainage ID	=	200	
<u>Lot Coverage</u>			
Total Catchment Area	=	102,819	m ²
Number of Lots	=	26	
Area of House	=	320	m ²
Rooftop Area	=	8,320	m ²
Number of Driveways	=	26	
Length of Driveways	=	20.0	m
Width of Driveway	=	9.0	m
Area of Driveways	=	4,633	m ²
Existing Imperviousness	=	982	m ²
Number of Walkways	=	26	
Length of Walkway	=	4.0	m
Width of Walkway	=	2.0	m
Area of Walkways	=	208	m ²
<u>20.0 m R.O.W. - 9.1 m Road (Assumed):</u>			
Area of Road	=	6,512	m ²
Total Impervious Area	=	2.07	ha
Total Catchment Area	=	10.28	ha
Total Catchment Area Without Pond	=	9.68	ha
% Total Impervious	=	2.07	ha
		9.68	ha
	=	21%	

Drainage ID = 201

Pasture = 0.82 ha.
Total Area = 0.82 ha.

Based on soils revealed in Cambium Inc.'s Geotechnical Investigation and Borehole Logs, the following Soil Group was assumed:

Hydrologic Soils Group: = B

CN Value is as follows:

CN = 74 (Pasture as per NVCA Guidelines)

IA Value is as follows:

IA = 8 (Pasture as per NVCA Guidelines)

Runoff Coefficient Value is as follows:

C = 0.20 (Pasture as per NVCA Guidelines)

Find Time to Peak using Airport Equation and Uplands Method

Airport Equation

$$T_c = 3.26(1.1 - c)L^{0.5}S_w^{-0.33}$$

Length (L) = 99 m
Elevation 1 (El₁) = 472.15 m
Elevation 2 (El₂) = 469.36 m
Slope (S) = 0.028 m/m
Time of Concentration (T_c) = 20.67 minutes
Total Time of Concentration (T_c) = 20.67 minutes
= 0.34 hrs.

Uplands Method

Section = 1
Land Cover = Pasture
Length = 99 m
Slope = 0.028 m/m
Velocity = 0.39 m/s
Time of Concentration (T_c) = 0.07 hrs.
Total Time of Concentration (T_c) = 0.07 hrs.

Governing Time to Peak

Airport Equation

T_c = 0.34 hrs.
T_p (T_p = 2/3 T_c) = 0.23 hrs.
D_T (1/5 T_p) = 3 mins.

Drainage ID	=	202	
Pasture	=	0.22	ha.
Impervious	=	0.03	ha.
Total Area	=	0.24	ha.

Based on soils revealed in Cambium Inc.'s Geotechnical Investigation and Borehole Logs, the following Soil Group was assumed:

Hydrologic Soils Group:	=	B
-------------------------	---	---

CN Value is as follows:

CN	=	69	(Pasture as per NVCA Guidelines)
CN	=	100	(Impervious as per NVCA Guidelines)
CN	=	$\frac{69 \times 0.20 + 100 \times 0.03}{0.24}$	
CN	=	73	

IA Value is as follows:

IA	=	8	(Pasture as per NVCA Guidelines)
IA	=	2	(Impervious as per NVCA Guidelines)
IA	=	$\frac{8 \times 0.20 + 2 \times 0.03}{0.24}$	
IA	=	7.3	

Runoff Coefficient Value is as follows:

C	=	0.15	(Grass as per NVCA Guidelines)
C	=	0.95	(Impervious as per NVCA Guidelines)
C	=	$\frac{0.15 \times 1.65 + 0.95 \times 0.08}{0.24}$	
C	=	0.24	

Find Time to Peak using Airport Equation and Uplands Method

<u>Airport Equation</u>		$T_c = 3.26(1.1 - c)L^{0.5}S_w^{-0.33}$	
Length (L)	=	97	m
Elevation 1 (El ₁)	=	462.85	m
Elevation 2 (El ₂)	=	458.58	m
Slope (S)	=	0.044	m/m
Time of Concentration (T _c)	=	16.78	minutes
Total Time of Concentration (T _c)	=	16.78	minutes
	=	0.28	hrs.

Uplands Method

Section	=	1	
Land Cover	=	Pasture	
Length	=	97	m
Slope	=	0.044	m/m
Velocity	=	0.48	m/s
Time of Concentration (T _c)	=	0.06	hrs.
Total Time of Concentration (T _c)	=	0.06	hrs.

Governing Time to Peak

<u>Airport Equation</u>			
T _c	=	0.28	hrs.
T _p (T _p = 2/3 T _c)	=	0.19	hrs.
D _T (1/5 T _p)	=	2	mins.



APPENDIX C

PRE-DEVELOPMENT OTTHYMO RESULTS



100

Area draining to the Northeast

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ba458ca8-a9ee-4292-8efc-f63654c3c9a8\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ba458ca8-a9ee-4292-8efc-f63654c3c9a8\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 01 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\8501ff12
Ptotal= 36.95 mm	Comments: 4hr 2year CHICAGO STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	18.78	2.33	4.89	3.50	2.55
0.17	2.47	1.33	83.11	2.50	4.28	3.67	2.39
0.33	2.82	1.50	24.57	2.67	3.82	3.83	2.26
0.50	3.31	1.67	13.01	2.83	3.46	4.00	2.15
0.67	4.05	1.83	9.01	3.00	3.17		
0.83	5.30	2.00	6.97	3.17	2.93		
1.00	7.98	2.17	5.73	3.33	2.72		

CALIB

NASHYD (0100)	Area (ha)= 11.35	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.20	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.35	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	7.98	2.250	5.73	3.33	2.93
0.167	0.00	1.250	18.78	2.333	5.73	3.42	2.72
0.250	2.47	1.333	18.78	2.417	4.89	3.50	2.72
0.333	2.47	1.417	83.11	2.500	4.89	3.58	2.55
0.417	2.82	1.500	83.11	2.583	4.28	3.67	2.55
0.500	2.82	1.583	24.57	2.667	4.28	3.75	2.39
0.583	3.31	1.667	24.57	2.750	3.82	3.83	2.39
0.667	3.31	1.750	13.01	2.833	3.82	3.92	2.26
0.750	4.05	1.833	13.01	2.917	3.46	4.00	2.26
0.833	4.05	1.917	9.01	3.000	3.46	4.08	2.15
0.917	5.30	2.000	9.01	3.083	3.17	4.17	2.15
1.000	5.30	2.083	6.97	3.167	3.17		
1.083	7.98	2.167	6.97	3.250	2.93		

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.156 (i)
 TIME TO PEAK (hrs)= 1.917
 RUNOFF VOLUME (mm)= 7.156
 TOTAL RAINFALL (mm)= 36.955
 RUNOFF COEFFICIENT = 0.194

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ef81fde4-621b-4d0e-8716-39239967bc1c\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ef81fde4-621b-4d0e-8716-39239967bc1c\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 02 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\0cb77411
Ptotal= 50.52 mm	Comments: 4hr 5year CHICAGO STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	25.64	2.33	6.96	3.50	3.68
0.17	3.57	1.33	108.92	2.50	6.12	3.67	3.47
0.33	4.07	1.50	33.31	2.67	5.48	3.83	3.28
0.50	4.76	1.67	17.99	2.83	4.97	4.00	3.12
0.67	5.79	1.83	12.60	3.00	4.56		
0.83	7.53	2.00	9.82	3.17	4.22		
1.00	11.20	2.17	8.12	3.33	3.93		

CALIB

NASHYD (0100)	Area (ha)= 11.35	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.20	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.35	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	11.20	2.250	8.12	3.33	4.22
0.167	0.00	1.250	25.64	2.333	8.12	3.42	3.93
0.250	3.57	1.333	25.64	2.417	6.96	3.50	3.93
0.333	3.57	1.417	108.92	2.500	6.96	3.58	3.68
0.417	4.07	1.500	108.92	2.583	6.12	3.67	3.68
0.500	4.07	1.583	33.31	2.667	6.12	3.75	3.47
0.583	4.76	1.667	33.31	2.750	5.48	3.83	3.47
0.667	4.76	1.750	17.99	2.833	5.48	3.92	3.28
0.750	5.79	1.833	17.99	2.917	4.97	4.00	3.28
0.833	5.79	1.917	12.60	3.000	4.97	4.08	3.12
0.917	7.53	2.000	12.60	3.083	4.56	4.17	3.12
1.000	7.53	2.083	9.82	3.167	4.56		
1.083	11.20	2.167	9.82	3.250	4.22		

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.307 (i)
 TIME TO PEAK (hrs)= 1.917
 RUNOFF VOLUME (mm)= 13.668
 TOTAL RAINFALL (mm)= 50.518
 RUNOFF COEFFICIENT = 0.271

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

FINISH

=====

=====

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ea4fa228-ad17-4611-a5ed-d7499b0bc3f6\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ea4fa228-ad17-4611-a5ed-d7499b0bc3f6\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 03 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\05237a76
Ptotal= 59.69 mm	Comments: 4hr 10year CHICAGO STORM - CITY OF BARRI

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	30.27	2.33	8.35	3.50	4.45
0.17	4.32	1.33	126.55	2.50	7.35	3.67	4.19
0.33	4.91	1.50	39.22	2.67	6.59	3.83	3.97
0.50	5.73	1.67	21.35	2.83	5.99	4.00	3.77
0.67	6.96	1.83	15.01	3.00	5.50		
0.83	9.03	2.00	11.74	3.17	5.09		
1.00	13.36	2.17	9.72	3.33	4.74		

CALIB

NASHYD (0100)	Area (ha)= 11.35	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.20	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.35	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	13.36	2.250	9.72	3.33	5.09
0.167	0.00	1.250	30.27	2.333	9.72	3.42	4.74
0.250	4.32	1.333	30.27	2.417	8.35	3.50	4.74
0.333	4.32	1.417	126.55	2.500	8.35	3.58	4.45
0.417	4.91	1.500	126.55	2.583	7.35	3.67	4.45
0.500	4.91	1.583	39.22	2.667	7.35	3.75	4.19
0.583	5.73	1.667	39.22	2.750	6.59	3.83	4.19
0.667	5.73	1.750	21.35	2.833	6.59	3.92	3.97
0.750	6.96	1.833	21.35	2.917	5.99	4.00	3.97
0.833	6.96	1.917	15.01	3.000	5.99	4.08	3.77
0.917	9.03	2.000	15.01	3.083	5.50	4.17	3.77
1.000	9.03	2.083	11.74	3.167	5.50		
1.083	13.36	2.167	11.74	3.250	5.09		

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.428 (i)
 TIME TO PEAK (hrs)= 1.917
 RUNOFF VOLUME (mm)= 18.813
 TOTAL RAINFALL (mm)= 59.693
 RUNOFF COEFFICIENT = 0.315

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

```

V      V      I      SSSSS  U      U      A      L      (v 6.2.2015)
V      V      I      SS      U      U      A A      L
V      V      I      SS      U      U      AAAAA  L
V      V      I      SS      U      U      A      A  L
VV      I      SSSSS  UUUUU  A      A  LLLLL

```

```

000      TTTTT  TTTTT  H      H      Y      Y      M      M      000      TM
O      O      T      T      H      H      Y Y      MM MM  O      O
O      O      T      T      H      H      Y      M      M      O      O
000      T      T      H      H      Y      M      M      000

```

Developed and Distributed by Smart City Water Inc
 Copyright 2007 - 2022 Smart City Water Inc
 All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
 Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\5928bd0-5321-4e4c-a28e-7d317dd749d4\scen
 Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\5928bd0-5321-4e4c-a28e-7d317dd749d4\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

 ** SIMULATION : Run 04 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\4ed3113b
Ptotal= 71.24 mm	Comments: 4hr 25year CHICAGO STORM - CITY OF BARRI

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
0.00	0.00	1.17	36.37	2.33	10.09	3.50	5.38
0.17	5.22	1.33	148.15	2.50	8.89	3.67	5.08
0.33	5.94	1.50	47.06	2.67	7.96	3.83	4.80
0.50	6.93	1.67	25.72	2.83	7.24	4.00	4.57
0.67	8.42	1.83	18.11	3.00	6.65		
0.83	10.91	2.00	14.17	3.17	6.15		
1.00	16.13	2.17	11.74	3.33	5.74		

CALIB

NASHYD (0100)	Area (ha)= 11.35	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.20	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.35	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	16.13	2.250	11.74	3.33	6.15
0.167	0.00	1.250	36.37	2.333	11.74	3.42	5.74
0.250	5.22	1.333	36.37	2.417	10.09	3.50	5.74
0.333	5.22	1.417	148.15	2.500	10.09	3.58	5.38
0.417	5.94	1.500	148.15	2.583	8.89	3.67	5.38
0.500	5.94	1.583	47.06	2.667	8.89	3.75	5.08
0.583	6.93	1.667	47.06	2.750	7.96	3.83	5.08
0.667	6.93	1.750	25.72	2.833	7.96	3.92	4.80
0.750	8.42	1.833	25.72	2.917	7.24	4.00	4.80
0.833	8.42	1.917	18.11	3.000	7.24	4.08	4.57
0.917	10.91	2.000	18.11	3.083	6.65	4.17	4.57
1.000	10.91	2.083	14.17	3.167	6.65		
1.083	16.13	2.167	14.17	3.250	6.15		

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.600 (i)
 TIME TO PEAK (hrs)= 1.917
 RUNOFF VOLUME (mm)= 25.951
 TOTAL RAINFALL (mm)= 71.237
 RUNOFF COEFFICIENT = 0.364

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\5163f435-f51c-416a-a109-2b1f420f335a\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\5163f435-f51c-416a-a109-2b1f420f335a\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 05 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\806310ce
Ptotal= 79.45 mm	Comments: 4hr 50year CHICAGO STORM - CITY OF BARRI

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	40.22	2.33	11.37	3.50	6.11
0.17	5.93	1.33	164.22	2.50	10.03	3.67	5.77
0.33	6.74	1.50	51.92	2.67	9.00	3.83	5.46
0.50	7.85	1.67	28.58	2.83	8.19	4.00	5.19
0.67	9.50	1.83	20.23	3.00	7.53		
0.83	12.27	2.00	15.88	3.17	6.98		
1.00	18.04	2.17	13.20	3.33	6.51		

CALIB

NASHYD (0100)	Area (ha)= 11.35	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.20	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.35	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	18.04	2.250	13.20	3.33	6.98
0.167	0.00	1.250	40.22	2.333	13.20	3.42	6.51
0.250	5.93	1.333	40.22	2.417	11.37	3.50	6.51
0.333	5.93	1.417	164.22	2.500	11.37	3.58	6.11
0.417	6.74	1.500	164.22	2.583	10.03	3.67	6.11
0.500	6.74	1.583	51.92	2.667	10.03	3.75	5.77
0.583	7.85	1.667	51.92	2.750	9.00	3.83	5.77
0.667	7.85	1.750	28.58	2.833	9.00	3.92	5.46
0.750	9.50	1.833	28.58	2.917	8.19	4.00	5.46
0.833	9.50	1.917	20.23	3.000	8.19	4.08	5.19
0.917	12.27	2.000	20.23	3.083	7.53	4.17	5.19
1.000	12.27	2.083	15.88	3.167	7.53		
1.083	18.04	2.167	15.88	3.250	6.98		

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.729 (i)
 TIME TO PEAK (hrs)= 1.917
 RUNOFF VOLUME (mm)= 31.405
 TOTAL RAINFALL (mm)= 79.453
 RUNOFF COEFFICIENT = 0.395

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\b777d7cb-91b5-4e3d-b9ab-9295e068ea74\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\b777d7cb-91b5-4e3d-b9ab-9295e068ea74\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 06 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\47ce8768
Ptotal= 87.58 mm	Comments: 4hr 100year CHICAGO STORM - CITY OF BARR

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	45.22	2.33	12.44	3.50	6.60
0.17	6.41	1.33	180.15	2.50	10.94	3.67	6.22
0.33	7.29	1.50	58.54	2.67	9.80	3.83	5.89
0.50	8.52	1.67	31.96	2.83	8.90	4.00	5.59
0.67	10.36	1.83	22.45	3.00	8.16		
0.83	13.45	2.00	17.52	3.17	7.56		
1.00	19.96	2.17	14.50	3.33	7.04		

CALIB

NASHYD (0100)	Area (ha)= 11.35	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.20	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.35	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	19.96	2.250	14.50	3.33	7.56
0.167	0.00	1.250	45.22	2.333	14.50	3.42	7.04
0.250	6.41	1.333	45.22	2.417	12.44	3.50	7.04
0.333	6.41	1.417	180.15	2.500	12.44	3.58	6.60
0.417	7.29	1.500	180.15	2.583	10.94	3.67	6.60
0.500	7.29	1.583	58.54	2.667	10.94	3.75	6.22
0.583	8.52	1.667	58.54	2.750	9.80	3.83	6.22
0.667	8.52	1.750	31.96	2.833	9.80	3.92	5.89
0.750	10.36	1.833	31.96	2.917	8.90	4.00	5.89
0.833	10.36	1.917	22.45	3.000	8.90	4.08	5.59
0.917	13.45	2.000	22.45	3.083	8.16	4.17	5.59
1.000	13.45	2.083	17.52	3.167	8.16		
1.083	19.96	2.167	17.52	3.250	7.56		

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.875 (i)
 TIME TO PEAK (hrs)= 1.917
 RUNOFF VOLUME (mm)= 37.054
 TOTAL RAINFALL (mm)= 87.578
 RUNOFF COEFFICIENT = 0.423

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\38639de7-2f51-4740-aad1-74720b25ce43\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\38639de7-2f51-4740-aad1-74720b25ce43\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 07 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\9bce3a2a
Ptotal= 55.00 mm	Comments: 24hr 2year SCS STORM - CITY OF BARRIE

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
0.00	0.55	6.00	1.10	12.00	7.92	18.00	0.99
0.25	0.55	6.25	1.10	12.25	7.92	18.25	0.99
0.50	0.55	6.50	1.10	12.50	4.07	18.50	0.99
0.75	0.55	6.75	1.10	12.75	4.07	18.75	0.99
1.00	0.55	7.00	1.10	13.00	0.77	19.00	0.99
1.25	0.55	7.25	1.10	13.25	0.77	19.25	0.99
1.50	0.55	7.50	1.10	13.50	4.51	19.50	0.99
1.75	0.99	7.75	1.10	13.75	4.51	19.75	0.99
2.00	0.71	8.00	1.49	14.00	1.65	20.00	0.66
2.25	0.71	8.25	1.49	14.25	1.65	20.25	0.66
2.50	0.71	8.50	1.49	14.50	1.65	20.50	0.66
2.75	0.71	8.75	1.49	14.75	1.65	20.75	0.66

3.00	0.71	9.00	1.76	15.00	1.65	21.00	0.66
3.25	0.71	9.25	1.76	15.25	1.65	21.25	0.66
3.50	0.71	9.50	1.98	15.50	1.65	21.50	0.66
3.75	0.71	9.75	1.98	15.75	1.65	21.75	0.66
4.00	0.88	10.00	2.53	16.00	0.99	22.00	0.66
4.25	0.88	10.25	2.53	16.25	0.99	22.25	0.66
4.50	0.88	10.50	3.41	16.50	0.99	22.50	0.66
4.75	0.88	10.75	3.41	16.75	0.99	22.75	0.66
5.00	0.88	11.00	5.28	17.00	0.99	23.00	0.66
5.25	0.88	11.25	5.28	17.25	0.99	23.25	0.66
5.50	0.88	11.50	22.88	17.50	0.99	23.50	0.66
5.75	0.88	11.75	60.72	17.75	0.99	23.75	0.66

CALIB							
NASHYD	(0100)	Area	(ha)= 11.35	Curve Number	(CN)= 73.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 7.20	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.35				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.55	6.083	1.10	12.083	7.93	18.08	0.99
0.167	0.55	6.167	1.10	12.167	7.92	18.17	0.99
0.250	0.55	6.250	1.10	12.250	7.92	18.25	0.99
0.333	0.55	6.333	1.10	12.333	7.92	18.33	0.99
0.417	0.55	6.417	1.10	12.417	7.92	18.42	0.99
0.500	0.55	6.500	1.10	12.500	7.92	18.50	0.99
0.583	0.55	6.583	1.10	12.583	4.07	18.58	0.99
0.667	0.55	6.667	1.10	12.667	4.07	18.67	0.99
0.750	0.55	6.750	1.10	12.750	4.07	18.75	0.99
0.833	0.55	6.833	1.10	12.833	4.07	18.83	0.99
0.917	0.55	6.917	1.10	12.917	4.07	18.92	0.99
1.000	0.55	7.000	1.10	13.000	4.07	19.00	0.99
1.083	0.55	7.083	1.10	13.083	0.77	19.08	0.99
1.167	0.55	7.167	1.10	13.167	0.77	19.17	0.99
1.250	0.55	7.250	1.10	13.250	0.77	19.25	0.99
1.333	0.55	7.333	1.10	13.333	0.77	19.33	0.99
1.417	0.55	7.417	1.10	13.417	0.77	19.42	0.99
1.500	0.55	7.500	1.10	13.500	0.77	19.50	0.99
1.583	0.55	7.583	1.10	13.583	4.51	19.58	0.99
1.667	0.55	7.667	1.10	13.667	4.51	19.67	0.99
1.750	0.55	7.750	1.10	13.750	4.51	19.75	0.99
1.833	0.99	7.833	1.10	13.833	4.51	19.83	0.99
1.917	0.99	7.917	1.10	13.917	4.51	19.92	0.99
2.000	0.99	8.000	1.10	14.000	4.51	20.00	0.99
2.083	0.71	8.083	1.49	14.083	1.65	20.08	0.66
2.167	0.71	8.167	1.49	14.167	1.65	20.17	0.66
2.250	0.71	8.250	1.48	14.250	1.65	20.25	0.66
2.333	0.71	8.333	1.49	14.333	1.65	20.33	0.66
2.417	0.71	8.417	1.49	14.417	1.65	20.42	0.66
2.500	0.71	8.500	1.48	14.500	1.65	20.50	0.66
2.583	0.71	8.583	1.49	14.583	1.65	20.58	0.66
2.667	0.71	8.667	1.49	14.667	1.65	20.67	0.66
2.750	0.71	8.750	1.48	14.750	1.65	20.75	0.66
2.833	0.71	8.833	1.49	14.833	1.65	20.83	0.66
2.917	0.71	8.917	1.49	14.917	1.65	20.92	0.66
3.000	0.71	9.000	1.49	15.000	1.65	21.00	0.66
3.083	0.71	9.083	1.76	15.083	1.65	21.08	0.66

3.167	0.71	9.167	1.76	15.167	1.65	21.17	0.66
3.250	0.71	9.250	1.76	15.250	1.65	21.25	0.66
3.333	0.71	9.333	1.76	15.333	1.65	21.33	0.66
3.417	0.71	9.417	1.76	15.417	1.65	21.42	0.66
3.500	0.71	9.500	1.76	15.500	1.65	21.50	0.66
3.583	0.71	9.583	1.98	15.583	1.65	21.58	0.66
3.667	0.71	9.667	1.98	15.667	1.65	21.67	0.66
3.750	0.71	9.750	1.98	15.750	1.65	21.75	0.66
3.833	0.71	9.833	1.98	15.833	1.65	21.83	0.66
3.917	0.71	9.917	1.98	15.917	1.65	21.92	0.66
4.000	0.71	10.000	1.98	16.000	1.65	22.00	0.66
4.083	0.88	10.083	2.53	16.083	0.99	22.08	0.66
4.167	0.88	10.167	2.53	16.167	0.99	22.17	0.66
4.250	0.88	10.250	2.53	16.250	0.99	22.25	0.66
4.333	0.88	10.333	2.53	16.333	0.99	22.33	0.66
4.417	0.88	10.417	2.53	16.417	0.99	22.42	0.66
4.500	0.88	10.500	2.53	16.500	0.99	22.50	0.66
4.583	0.88	10.583	3.41	16.583	0.99	22.58	0.66
4.667	0.88	10.667	3.41	16.667	0.99	22.67	0.66
4.750	0.88	10.750	3.41	16.750	0.99	22.75	0.66
4.833	0.88	10.833	3.41	16.833	0.99	22.83	0.66
4.917	0.88	10.917	3.41	16.917	0.99	22.92	0.66
5.000	0.88	11.000	3.41	17.000	0.99	23.00	0.66
5.083	0.88	11.083	5.28	17.083	0.99	23.08	0.66
5.167	0.88	11.167	5.28	17.167	0.99	23.17	0.66
5.250	0.88	11.250	5.28	17.250	0.99	23.25	0.66
5.333	0.88	11.333	5.28	17.333	0.99	23.33	0.66
5.417	0.88	11.417	5.28	17.417	0.99	23.42	0.66
5.500	0.88	11.500	5.28	17.500	0.99	23.50	0.66
5.583	0.88	11.583	22.88	17.583	0.99	23.58	0.66
5.667	0.88	11.667	22.88	17.667	0.99	23.67	0.66
5.750	0.88	11.750	22.88	17.750	0.99	23.75	0.66
5.833	0.88	11.833	60.72	17.833	0.99	23.83	0.66
5.917	0.88	11.917	60.72	17.917	0.99	23.92	0.66
6.000	0.88	12.000	60.72	18.000	0.99	24.00	0.66

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.300 (i)
TIME TO PEAK (hrs)= 12.250
RUNOFF VOLUME (mm)= 16.116
TOTAL RAINFALL (mm)= 55.000
RUNOFF COEFFICIENT = 0.293

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\baf3b75a-a091-4fe3-bbe0-a168bbba3b91\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\baf3b75a-a091-4fe3-bbe0-a168bbba3b91\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 08 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\689870c2
Ptotal= 76.00 mm	Comments: 24hr 5year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.76	6.00	1.52	12.00	10.94	18.00	1.37
0.25	0.76	6.25	1.52	12.25	10.94	18.25	1.37
0.50	0.76	6.50	1.52	12.50	5.62	18.50	1.37
0.75	0.76	6.75	1.52	12.75	5.62	18.75	1.37
1.00	0.76	7.00	1.52	13.00	1.06	19.00	1.37
1.25	0.76	7.25	1.52	13.25	1.06	19.25	1.37
1.50	0.76	7.50	1.52	13.50	6.23	19.50	1.37
1.75	1.37	7.75	1.52	13.75	6.23	19.75	1.37
2.00	0.99	8.00	2.05	14.00	2.28	20.00	0.91
2.25	0.99	8.25	2.05	14.25	2.28	20.25	0.91
2.50	0.99	8.50	2.05	14.50	2.28	20.50	0.91
2.75	0.99	8.75	2.05	14.75	2.28	20.75	0.91

3.00	0.99	9.00	2.43	15.00	2.28	21.00	0.91
3.25	0.99	9.25	2.43	15.25	2.28	21.25	0.91
3.50	0.99	9.50	2.74	15.50	2.28	21.50	0.91
3.75	0.99	9.75	2.74	15.75	2.28	21.75	0.91
4.00	1.22	10.00	3.50	16.00	1.37	22.00	0.91
4.25	1.22	10.25	3.50	16.25	1.37	22.25	0.91
4.50	1.22	10.50	4.71	16.50	1.37	22.50	0.91
4.75	1.22	10.75	4.71	16.75	1.37	22.75	0.91
5.00	1.22	11.00	7.30	17.00	1.37	23.00	0.91
5.25	1.22	11.25	7.30	17.25	1.37	23.25	0.91
5.50	1.22	11.50	31.62	17.50	1.37	23.50	0.91
5.75	1.22	11.75	83.90	17.75	1.37	23.75	0.91

CALIB							
NASHYD	(0100)	Area	(ha)= 11.35	Curve Number	(CN)= 73.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 7.20	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.35				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.76	6.083	1.52	12.083	10.95	18.08	1.37
0.167	0.76	6.167	1.52	12.167	10.94	18.17	1.37
0.250	0.76	6.250	1.52	12.250	10.94	18.25	1.37
0.333	0.76	6.333	1.52	12.333	10.94	18.33	1.37
0.417	0.76	6.417	1.52	12.417	10.94	18.42	1.37
0.500	0.76	6.500	1.52	12.500	10.94	18.50	1.37
0.583	0.76	6.583	1.52	12.583	5.62	18.58	1.37
0.667	0.76	6.667	1.52	12.667	5.62	18.67	1.37
0.750	0.76	6.750	1.52	12.750	5.62	18.75	1.37
0.833	0.76	6.833	1.52	12.833	5.62	18.83	1.37
0.917	0.76	6.917	1.52	12.917	5.62	18.92	1.37
1.000	0.76	7.000	1.52	13.000	5.62	19.00	1.37
1.083	0.76	7.083	1.52	13.083	1.06	19.08	1.37
1.167	0.76	7.167	1.52	13.167	1.06	19.17	1.37
1.250	0.76	7.250	1.52	13.250	1.06	19.25	1.37
1.333	0.76	7.333	1.52	13.333	1.06	19.33	1.37
1.417	0.76	7.417	1.52	13.417	1.06	19.42	1.37
1.500	0.76	7.500	1.52	13.500	1.06	19.50	1.37
1.583	0.76	7.583	1.52	13.583	6.23	19.58	1.37
1.667	0.76	7.667	1.52	13.667	6.23	19.67	1.37
1.750	0.76	7.750	1.52	13.750	6.23	19.75	1.37
1.833	1.37	7.833	1.52	13.833	6.23	19.83	1.37
1.917	1.37	7.917	1.52	13.917	6.23	19.92	1.37
2.000	1.37	8.000	1.52	14.000	6.23	20.00	1.37
2.083	0.99	8.083	2.05	14.083	2.28	20.08	0.91
2.167	0.99	8.167	2.05	14.167	2.28	20.17	0.91
2.250	0.99	8.250	2.05	14.250	2.28	20.25	0.91
2.333	0.99	8.333	2.05	14.333	2.28	20.33	0.91
2.417	0.99	8.417	2.05	14.417	2.28	20.42	0.91
2.500	0.99	8.500	2.05	14.500	2.28	20.50	0.91
2.583	0.99	8.583	2.05	14.583	2.28	20.58	0.91
2.667	0.99	8.667	2.05	14.667	2.28	20.67	0.91
2.750	0.99	8.750	2.05	14.750	2.28	20.75	0.91
2.833	0.99	8.833	2.05	14.833	2.28	20.83	0.91
2.917	0.99	8.917	2.05	14.917	2.28	20.92	0.91
3.000	0.99	9.000	2.05	15.000	2.28	21.00	0.91
3.083	0.99	9.083	2.43	15.083	2.28	21.08	0.91

3.167	0.99	9.167	2.43	15.167	2.28	21.17	0.91
3.250	0.99	9.250	2.43	15.250	2.28	21.25	0.91
3.333	0.99	9.333	2.43	15.333	2.28	21.33	0.91
3.417	0.99	9.417	2.43	15.417	2.28	21.42	0.91
3.500	0.99	9.500	2.43	15.500	2.28	21.50	0.91
3.583	0.99	9.583	2.74	15.583	2.28	21.58	0.91
3.667	0.99	9.667	2.74	15.667	2.28	21.67	0.91
3.750	0.99	9.750	2.74	15.750	2.28	21.75	0.91
3.833	0.99	9.833	2.74	15.833	2.28	21.83	0.91
3.917	0.99	9.917	2.74	15.917	2.28	21.92	0.91
4.000	0.99	10.000	2.74	16.000	2.28	22.00	0.91
4.083	1.22	10.083	3.50	16.083	1.37	22.08	0.91
4.167	1.22	10.167	3.50	16.167	1.37	22.17	0.91
4.250	1.22	10.250	3.50	16.250	1.37	22.25	0.91
4.333	1.22	10.333	3.50	16.333	1.37	22.33	0.91
4.417	1.22	10.417	3.50	16.417	1.37	22.42	0.91
4.500	1.22	10.500	3.50	16.500	1.37	22.50	0.91
4.583	1.22	10.583	4.71	16.583	1.37	22.58	0.91
4.667	1.22	10.667	4.71	16.667	1.37	22.67	0.91
4.750	1.22	10.750	4.71	16.750	1.37	22.75	0.91
4.833	1.22	10.833	4.71	16.833	1.37	22.83	0.91
4.917	1.22	10.917	4.71	16.917	1.37	22.92	0.91
5.000	1.22	11.000	4.71	17.000	1.37	23.00	0.91
5.083	1.22	11.083	7.30	17.083	1.37	23.08	0.91
5.167	1.22	11.167	7.30	17.167	1.37	23.17	0.91
5.250	1.22	11.250	7.30	17.250	1.37	23.25	0.91
5.333	1.22	11.333	7.30	17.333	1.37	23.33	0.91
5.417	1.22	11.417	7.30	17.417	1.37	23.42	0.91
5.500	1.22	11.500	7.30	17.500	1.37	23.50	0.91
5.583	1.22	11.583	31.61	17.583	1.37	23.58	0.91
5.667	1.22	11.667	31.62	17.667	1.37	23.67	0.91
5.750	1.22	11.750	31.62	17.750	1.37	23.75	0.91
5.833	1.22	11.833	83.90	17.833	1.37	23.83	0.91
5.917	1.22	11.917	83.90	17.917	1.37	23.92	0.91
6.000	1.22	12.000	83.90	18.000	1.37	24.00	0.91

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.555 (i)
TIME TO PEAK (hrs)= 12.250
RUNOFF VOLUME (mm)= 29.079
TOTAL RAINFALL (mm)= 76.000
RUNOFF COEFFICIENT = 0.383

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\4dc5a568-c574-4abb-95c9-a3299e46b4f5\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\4dc5a568-c574-4abb-95c9-a3299e46b4f5\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 09 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\0d41b358
Ptotal= 89.90 mm	Comments: 24hr 10year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.90	6.00	1.80	12.00	12.95	18.00	1.62
0.25	0.90	6.25	1.80	12.25	12.95	18.25	1.62
0.50	0.90	6.50	1.80	12.50	6.65	18.50	1.62
0.75	0.90	6.75	1.80	12.75	6.65	18.75	1.62
1.00	0.90	7.00	1.80	13.00	1.26	19.00	1.62
1.25	0.90	7.25	1.80	13.25	1.26	19.25	1.62
1.50	0.90	7.50	1.80	13.50	7.37	19.50	1.62
1.75	1.62	7.75	1.80	13.75	7.37	19.75	1.62
2.00	1.17	8.00	2.43	14.00	2.70	20.00	1.08
2.25	1.17	8.25	2.43	14.25	2.70	20.25	1.08
2.50	1.17	8.50	2.43	14.50	2.70	20.50	1.08
2.75	1.17	8.75	2.43	14.75	2.70	20.75	1.08

3.00	1.17	9.00	2.88	15.00	2.70	21.00	1.08
3.25	1.17	9.25	2.88	15.25	2.70	21.25	1.08
3.50	1.17	9.50	3.24	15.50	2.70	21.50	1.08
3.75	1.17	9.75	3.24	15.75	2.70	21.75	1.08
4.00	1.44	10.00	4.14	16.00	1.62	22.00	1.08
4.25	1.44	10.25	4.14	16.25	1.62	22.25	1.08
4.50	1.44	10.50	5.57	16.50	1.62	22.50	1.08
4.75	1.44	10.75	5.57	16.75	1.62	22.75	1.08
5.00	1.44	11.00	8.63	17.00	1.62	23.00	1.08
5.25	1.44	11.25	8.63	17.25	1.62	23.25	1.08
5.50	1.44	11.50	37.40	17.50	1.62	23.50	1.08
5.75	1.44	11.75	99.25	17.75	1.62	23.75	1.08

CALIB							
NASHYD	(0100)	Area	(ha)= 11.35	Curve Number	(CN)= 73.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 7.20	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.35				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.90	6.083	1.80	12.083	12.96	18.08	1.62
0.167	0.90	6.167	1.80	12.167	12.95	18.17	1.62
0.250	0.90	6.250	1.80	12.250	12.95	18.25	1.62
0.333	0.90	6.333	1.80	12.333	12.95	18.33	1.62
0.417	0.90	6.417	1.80	12.417	12.95	18.42	1.62
0.500	0.90	6.500	1.80	12.500	12.95	18.50	1.62
0.583	0.90	6.583	1.80	12.583	6.65	18.58	1.62
0.667	0.90	6.667	1.80	12.667	6.65	18.67	1.62
0.750	0.90	6.750	1.80	12.750	6.65	18.75	1.62
0.833	0.90	6.833	1.80	12.833	6.65	18.83	1.62
0.917	0.90	6.917	1.80	12.917	6.65	18.92	1.62
1.000	0.90	7.000	1.80	13.000	6.65	19.00	1.62
1.083	0.90	7.083	1.80	13.083	1.26	19.08	1.62
1.167	0.90	7.167	1.80	13.167	1.26	19.17	1.62
1.250	0.90	7.250	1.80	13.250	1.26	19.25	1.62
1.333	0.90	7.333	1.80	13.333	1.26	19.33	1.62
1.417	0.90	7.417	1.80	13.417	1.26	19.42	1.62
1.500	0.90	7.500	1.80	13.500	1.26	19.50	1.62
1.583	0.90	7.583	1.80	13.583	7.37	19.58	1.62
1.667	0.90	7.667	1.80	13.667	7.37	19.67	1.62
1.750	0.90	7.750	1.80	13.750	7.37	19.75	1.62
1.833	1.62	7.833	1.80	13.833	7.37	19.83	1.62
1.917	1.62	7.917	1.80	13.917	7.37	19.92	1.62
2.000	1.62	8.000	1.80	14.000	7.37	20.00	1.62
2.083	1.17	8.083	2.43	14.083	2.70	20.08	1.08
2.167	1.17	8.167	2.43	14.167	2.70	20.17	1.08
2.250	1.17	8.250	2.43	14.250	2.70	20.25	1.08
2.333	1.17	8.333	2.43	14.333	2.70	20.33	1.08
2.417	1.17	8.417	2.43	14.417	2.70	20.42	1.08
2.500	1.17	8.500	2.43	14.500	2.70	20.50	1.08
2.583	1.17	8.583	2.43	14.583	2.70	20.58	1.08
2.667	1.17	8.667	2.43	14.667	2.70	20.67	1.08
2.750	1.17	8.750	2.43	14.750	2.70	20.75	1.08
2.833	1.17	8.833	2.43	14.833	2.70	20.83	1.08
2.917	1.17	8.917	2.43	14.917	2.70	20.92	1.08
3.000	1.17	9.000	2.43	15.000	2.70	21.00	1.08
3.083	1.17	9.083	2.88	15.083	2.70	21.08	1.08

3.167	1.17	9.167	2.88	15.167	2.70	21.17	1.08
3.250	1.17	9.250	2.88	15.250	2.70	21.25	1.08
3.333	1.17	9.333	2.88	15.333	2.70	21.33	1.08
3.417	1.17	9.417	2.88	15.417	2.70	21.42	1.08
3.500	1.17	9.500	2.88	15.500	2.70	21.50	1.08
3.583	1.17	9.583	3.24	15.583	2.70	21.58	1.08
3.667	1.17	9.667	3.24	15.667	2.70	21.67	1.08
3.750	1.17	9.750	3.24	15.750	2.70	21.75	1.08
3.833	1.17	9.833	3.24	15.833	2.70	21.83	1.08
3.917	1.17	9.917	3.24	15.917	2.70	21.92	1.08
4.000	1.17	10.000	3.24	16.000	2.70	22.00	1.08
4.083	1.44	10.083	4.14	16.083	1.62	22.08	1.08
4.167	1.44	10.167	4.14	16.167	1.62	22.17	1.08
4.250	1.44	10.250	4.14	16.250	1.62	22.25	1.08
4.333	1.44	10.333	4.14	16.333	1.62	22.33	1.08
4.417	1.44	10.417	4.14	16.417	1.62	22.42	1.08
4.500	1.44	10.500	4.14	16.500	1.62	22.50	1.08
4.583	1.44	10.583	5.57	16.583	1.62	22.58	1.08
4.667	1.44	10.667	5.57	16.667	1.62	22.67	1.08
4.750	1.44	10.750	5.57	16.750	1.62	22.75	1.08
4.833	1.44	10.833	5.57	16.833	1.62	22.83	1.08
4.917	1.44	10.917	5.57	16.917	1.62	22.92	1.08
5.000	1.44	11.000	5.57	17.000	1.62	23.00	1.08
5.083	1.44	11.083	8.63	17.083	1.62	23.08	1.08
5.167	1.44	11.167	8.63	17.167	1.62	23.17	1.08
5.250	1.44	11.250	8.63	17.250	1.62	23.25	1.08
5.333	1.44	11.333	8.63	17.333	1.62	23.33	1.08
5.417	1.44	11.417	8.63	17.417	1.62	23.42	1.08
5.500	1.44	11.500	8.63	17.500	1.62	23.50	1.08
5.583	1.44	11.583	37.40	17.583	1.62	23.58	1.08
5.667	1.44	11.667	37.40	17.667	1.62	23.67	1.08
5.750	1.44	11.750	37.40	17.750	1.62	23.75	1.08
5.833	1.44	11.833	99.24	17.833	1.62	23.83	1.08
5.917	1.44	11.917	99.25	17.917	1.62	23.92	1.08
6.000	1.44	12.000	99.25	18.000	1.62	24.00	1.08

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.745 (i)
TIME TO PEAK (hrs)= 12.167
RUNOFF VOLUME (mm)= 38.710
TOTAL RAINFALL (mm)= 89.900
RUNOFF COEFFICIENT = 0.431

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\78439ddb-c4b1-438e-ba1c-bffbad1ca4f0\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\78439ddb-c4b1-438e-ba1c-bffbad1ca4f0\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 10 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\9ad5e3ee
Ptotal=107.50 mm	Comments: 24hr 25year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	1.08	6.00	2.15	12.00	15.48	18.00	1.93
0.25	1.08	6.25	2.15	12.25	15.48	18.25	1.93
0.50	1.08	6.50	2.15	12.50	7.95	18.50	1.93
0.75	1.08	6.75	2.15	12.75	7.95	18.75	1.93
1.00	1.08	7.00	2.15	13.00	1.50	19.00	1.93
1.25	1.08	7.25	2.15	13.25	1.50	19.25	1.93
1.50	1.08	7.50	2.15	13.50	8.81	19.50	1.93
1.75	1.93	7.75	2.15	13.75	8.81	19.75	1.93
2.00	1.40	8.00	2.90	14.00	3.22	20.00	1.29
2.25	1.40	8.25	2.90	14.25	3.22	20.25	1.29
2.50	1.40	8.50	2.90	14.50	3.22	20.50	1.29
2.75	1.40	8.75	2.90	14.75	3.22	20.75	1.29

3.00	1.40	9.00	3.44	15.00	3.22	21.00	1.29
3.25	1.40	9.25	3.44	15.25	3.22	21.25	1.29
3.50	1.40	9.50	3.87	15.50	3.22	21.50	1.29
3.75	1.40	9.75	3.87	15.75	3.22	21.75	1.29
4.00	1.72	10.00	4.95	16.00	1.93	22.00	1.29
4.25	1.72	10.25	4.95	16.25	1.93	22.25	1.29
4.50	1.72	10.50	6.66	16.50	1.93	22.50	1.29
4.75	1.72	10.75	6.66	16.75	1.93	22.75	1.29
5.00	1.72	11.00	10.32	17.00	1.93	23.00	1.29
5.25	1.72	11.25	10.32	17.25	1.93	23.25	1.29
5.50	1.72	11.50	44.72	17.50	1.93	23.50	1.29
5.75	1.72	11.75	118.68	17.75	1.93	23.75	1.29

CALIB							
NASHYD	(0100)	Area	(ha)= 11.35	Curve Number	(CN)= 73.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 7.20	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.35				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.08	6.083	2.15	12.083	15.49	18.08	1.94
0.167	1.08	6.167	2.15	12.167	15.48	18.17	1.93
0.250	1.08	6.250	2.15	12.250	15.48	18.25	1.93
0.333	1.08	6.333	2.15	12.333	15.48	18.33	1.94
0.417	1.08	6.417	2.15	12.417	15.48	18.42	1.93
0.500	1.08	6.500	2.15	12.500	15.48	18.50	1.93
0.583	1.08	6.583	2.15	12.583	7.96	18.58	1.94
0.667	1.08	6.667	2.15	12.667	7.95	18.67	1.93
0.750	1.08	6.750	2.15	12.750	7.95	18.75	1.93
0.833	1.07	6.833	2.15	12.833	7.95	18.83	1.94
0.917	1.08	6.917	2.15	12.917	7.95	18.92	1.93
1.000	1.08	7.000	2.15	13.000	7.95	19.00	1.93
1.083	1.07	7.083	2.15	13.083	1.51	19.08	1.94
1.167	1.08	7.167	2.15	13.167	1.50	19.17	1.93
1.250	1.08	7.250	2.15	13.250	1.50	19.25	1.93
1.333	1.08	7.333	2.15	13.333	1.50	19.33	1.94
1.417	1.08	7.417	2.15	13.417	1.50	19.42	1.93
1.500	1.08	7.500	2.15	13.500	1.50	19.50	1.94
1.583	1.08	7.583	2.15	13.583	8.81	19.58	1.93
1.667	1.08	7.667	2.15	13.667	8.81	19.67	1.93
1.750	1.08	7.750	2.15	13.750	8.81	19.75	1.94
1.833	1.93	7.833	2.15	13.833	8.81	19.83	1.93
1.917	1.93	7.917	2.15	13.917	8.81	19.92	1.93
2.000	1.93	8.000	2.15	14.000	8.81	20.00	1.93
2.083	1.40	8.083	2.90	14.083	3.23	20.08	1.29
2.167	1.40	8.167	2.90	14.167	3.22	20.17	1.29
2.250	1.40	8.250	2.90	14.250	3.22	20.25	1.29
2.333	1.40	8.333	2.90	14.333	3.22	20.33	1.29
2.417	1.40	8.417	2.90	14.417	3.22	20.42	1.29
2.500	1.40	8.500	2.90	14.500	3.22	20.50	1.29
2.583	1.40	8.583	2.90	14.583	3.22	20.58	1.29
2.667	1.40	8.667	2.90	14.667	3.22	20.67	1.29
2.750	1.40	8.750	2.90	14.750	3.22	20.75	1.29
2.833	1.40	8.833	2.90	14.833	3.22	20.83	1.29
2.917	1.40	8.917	2.90	14.917	3.22	20.92	1.29
3.000	1.40	9.000	2.90	15.000	3.22	21.00	1.29
3.083	1.40	9.083	3.44	15.083	3.22	21.08	1.29

3.167	1.40	9.167	3.44	15.167	3.22	21.17	1.29
3.250	1.40	9.250	3.44	15.250	3.22	21.25	1.29
3.333	1.40	9.333	3.44	15.333	3.22	21.33	1.29
3.417	1.40	9.417	3.44	15.417	3.22	21.42	1.29
3.500	1.40	9.500	3.44	15.500	3.22	21.50	1.29
3.583	1.40	9.583	3.87	15.583	3.22	21.58	1.29
3.667	1.40	9.667	3.87	15.667	3.22	21.67	1.29
3.750	1.40	9.750	3.87	15.750	3.22	21.75	1.29
3.833	1.40	9.833	3.87	15.833	3.22	21.83	1.29
3.917	1.40	9.917	3.87	15.917	3.22	21.92	1.29
4.000	1.40	10.000	3.87	16.000	3.22	22.00	1.29
4.083	1.72	10.083	4.94	16.083	1.94	22.08	1.29
4.167	1.72	10.167	4.95	16.167	1.93	22.17	1.29
4.250	1.72	10.250	4.95	16.250	1.93	22.25	1.29
4.333	1.72	10.333	4.94	16.333	1.94	22.33	1.29
4.417	1.72	10.417	4.95	16.417	1.93	22.42	1.29
4.500	1.72	10.500	4.95	16.500	1.93	22.50	1.29
4.583	1.72	10.583	6.66	16.583	1.94	22.58	1.29
4.667	1.72	10.667	6.66	16.667	1.93	22.67	1.29
4.750	1.72	10.750	6.66	16.750	1.93	22.75	1.29
4.833	1.72	10.833	6.66	16.833	1.94	22.83	1.29
4.917	1.72	10.917	6.66	16.917	1.93	22.92	1.29
5.000	1.72	11.000	6.66	17.000	1.93	23.00	1.29
5.083	1.72	11.083	10.32	17.083	1.94	23.08	1.29
5.167	1.72	11.167	10.32	17.167	1.93	23.17	1.29
5.250	1.72	11.250	10.32	17.250	1.93	23.25	1.29
5.333	1.72	11.333	10.32	17.333	1.94	23.33	1.29
5.417	1.72	11.417	10.32	17.417	1.93	23.42	1.29
5.500	1.72	11.500	10.32	17.500	1.93	23.50	1.29
5.583	1.72	11.583	44.72	17.583	1.94	23.58	1.29
5.667	1.72	11.667	44.72	17.667	1.93	23.67	1.29
5.750	1.72	11.750	44.72	17.750	1.93	23.75	1.29
5.833	1.72	11.833	118.67	17.833	1.94	23.83	1.29
5.917	1.72	11.917	118.68	17.917	1.93	23.92	1.29
6.000	1.72	12.000	118.68	18.000	1.93	24.00	1.29

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 1.007 (i)
TIME TO PEAK (hrs)= 12.167
RUNOFF VOLUME (mm)= 51.780
TOTAL RAINFALL (mm)= 107.500
RUNOFF COEFFICIENT = 0.482

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ea7a419b-0d38-4031-b0db-5fd9af185cfd\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ea7a419b-0d38-4031-b0db-5fd9af185cfd\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 11 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\9948bc8a
Ptotal=120.60 mm	Comments: 24hr 50year SCS STORM - CITY OF BARRIE

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
0.00	1.21	6.00	2.41	12.00	17.37	18.00	2.17
0.25	1.21	6.25	2.41	12.25	17.37	18.25	2.17
0.50	1.21	6.50	2.41	12.50	8.92	18.50	2.17
0.75	1.21	6.75	2.41	12.75	8.92	18.75	2.17
1.00	1.21	7.00	2.41	13.00	1.69	19.00	2.17
1.25	1.21	7.25	2.41	13.25	1.69	19.25	2.17
1.50	1.21	7.50	2.41	13.50	9.89	19.50	2.17
1.75	2.17	7.75	2.41	13.75	9.89	19.75	2.17
2.00	1.57	8.00	3.26	14.00	3.62	20.00	1.45
2.25	1.57	8.25	3.26	14.25	3.62	20.25	1.45
2.50	1.57	8.50	3.26	14.50	3.62	20.50	1.45
2.75	1.57	8.75	3.26	14.75	3.62	20.75	1.45

3.00	1.57	9.00	3.86	15.00	3.62	21.00	1.45
3.25	1.57	9.25	3.86	15.25	3.62	21.25	1.45
3.50	1.57	9.50	4.34	15.50	3.62	21.50	1.45
3.75	1.57	9.75	4.34	15.75	3.62	21.75	1.45
4.00	1.93	10.00	5.55	16.00	2.17	22.00	1.45
4.25	1.93	10.25	5.55	16.25	2.17	22.25	1.45
4.50	1.93	10.50	7.48	16.50	2.17	22.50	1.45
4.75	1.93	10.75	7.48	16.75	2.17	22.75	1.45
5.00	1.93	11.00	11.58	17.00	2.17	23.00	1.45
5.25	1.93	11.25	11.58	17.25	2.17	23.25	1.45
5.50	1.93	11.50	50.17	17.50	2.17	23.50	1.45
5.75	1.93	11.75	133.14	17.75	2.17	23.75	1.45

CALIB							
NASHYD	(0100)	Area	(ha)= 11.35	Curve Number	(CN)= 73.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 7.20	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.35				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.21	6.083	2.41	12.083	17.38	18.08	2.17
0.167	1.21	6.167	2.41	12.167	17.37	18.17	2.17
0.250	1.21	6.250	2.41	12.250	17.37	18.25	2.17
0.333	1.21	6.333	2.41	12.333	17.37	18.33	2.17
0.417	1.21	6.417	2.41	12.417	17.37	18.42	2.17
0.500	1.21	6.500	2.41	12.500	17.37	18.50	2.17
0.583	1.21	6.583	2.41	12.583	8.93	18.58	2.17
0.667	1.21	6.667	2.41	12.667	8.92	18.67	2.17
0.750	1.21	6.750	2.41	12.750	8.92	18.75	2.17
0.833	1.21	6.833	2.41	12.833	8.92	18.83	2.17
0.917	1.21	6.917	2.41	12.917	8.92	18.92	2.17
1.000	1.21	7.000	2.41	13.000	8.92	19.00	2.17
1.083	1.21	7.083	2.41	13.083	1.69	19.08	2.17
1.167	1.21	7.167	2.41	13.167	1.69	19.17	2.17
1.250	1.21	7.250	2.41	13.250	1.69	19.25	2.17
1.333	1.21	7.333	2.41	13.333	1.69	19.33	2.17
1.417	1.21	7.417	2.41	13.417	1.69	19.42	2.17
1.500	1.21	7.500	2.41	13.500	1.69	19.50	2.17
1.583	1.21	7.583	2.41	13.583	9.89	19.58	2.17
1.667	1.21	7.667	2.41	13.667	9.89	19.67	2.17
1.750	1.21	7.750	2.41	13.750	9.89	19.75	2.17
1.833	2.17	7.833	2.41	13.833	9.89	19.83	2.17
1.917	2.17	7.917	2.41	13.917	9.89	19.92	2.17
2.000	2.17	8.000	2.41	14.000	9.89	20.00	2.17
2.083	1.57	8.083	3.26	14.083	3.62	20.08	1.45
2.167	1.57	8.167	3.26	14.167	3.62	20.17	1.45
2.250	1.57	8.250	3.26	14.250	3.62	20.25	1.45
2.333	1.57	8.333	3.26	14.333	3.62	20.33	1.45
2.417	1.57	8.417	3.26	14.417	3.62	20.42	1.45
2.500	1.57	8.500	3.26	14.500	3.62	20.50	1.45
2.583	1.57	8.583	3.26	14.583	3.62	20.58	1.45
2.667	1.57	8.667	3.26	14.667	3.62	20.67	1.45
2.750	1.57	8.750	3.26	14.750	3.62	20.75	1.45
2.833	1.57	8.833	3.26	14.833	3.62	20.83	1.45
2.917	1.57	8.917	3.26	14.917	3.62	20.92	1.45
3.000	1.57	9.000	3.26	15.000	3.62	21.00	1.45
3.083	1.57	9.083	3.86	15.083	3.62	21.08	1.45

3.167	1.57	9.167	3.86	15.167	3.62	21.17	1.45
3.250	1.57	9.250	3.86	15.250	3.62	21.25	1.45
3.333	1.57	9.333	3.86	15.333	3.62	21.33	1.45
3.417	1.57	9.417	3.86	15.417	3.62	21.42	1.45
3.500	1.57	9.500	3.86	15.500	3.62	21.50	1.45
3.583	1.57	9.583	4.34	15.583	3.62	21.58	1.45
3.667	1.57	9.667	4.34	15.667	3.62	21.67	1.45
3.750	1.57	9.750	4.34	15.750	3.62	21.75	1.45
3.833	1.57	9.833	4.34	15.833	3.62	21.83	1.45
3.917	1.57	9.917	4.34	15.917	3.62	21.92	1.45
4.000	1.57	10.000	4.34	16.000	3.62	22.00	1.45
4.083	1.93	10.083	5.55	16.083	2.17	22.08	1.45
4.167	1.93	10.167	5.55	16.167	2.17	22.17	1.45
4.250	1.93	10.250	5.55	16.250	2.17	22.25	1.45
4.333	1.93	10.333	5.55	16.333	2.17	22.33	1.45
4.417	1.93	10.417	5.55	16.417	2.17	22.42	1.45
4.500	1.93	10.500	5.55	16.500	2.17	22.50	1.45
4.583	1.93	10.583	7.48	16.583	2.17	22.58	1.45
4.667	1.93	10.667	7.48	16.667	2.17	22.67	1.45
4.750	1.93	10.750	7.48	16.750	2.17	22.75	1.45
4.833	1.93	10.833	7.48	16.833	2.17	22.83	1.45
4.917	1.93	10.917	7.48	16.917	2.17	22.92	1.45
5.000	1.93	11.000	7.48	17.000	2.17	23.00	1.45
5.083	1.93	11.083	11.58	17.083	2.17	23.08	1.45
5.167	1.93	11.167	11.58	17.167	2.17	23.17	1.45
5.250	1.93	11.250	11.58	17.250	2.17	23.25	1.45
5.333	1.93	11.333	11.58	17.333	2.17	23.33	1.45
5.417	1.93	11.417	11.58	17.417	2.17	23.42	1.45
5.500	1.93	11.500	11.58	17.500	2.17	23.50	1.45
5.583	1.93	11.583	50.17	17.583	2.17	23.58	1.45
5.667	1.93	11.667	50.17	17.667	2.17	23.67	1.45
5.750	1.93	11.750	50.17	17.750	2.17	23.75	1.45
5.833	1.93	11.833	133.13	17.833	2.17	23.83	1.45
5.917	1.93	11.917	133.14	17.917	2.17	23.92	1.45
6.000	1.93	12.000	133.14	18.000	2.17	24.00	1.45

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 1.212 (i)
TIME TO PEAK (hrs)= 12.167
RUNOFF VOLUME (mm)= 62.007
TOTAL RAINFALL (mm)= 120.600
RUNOFF COEFFICIENT = 0.514

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\78f8d168-9cdb-4c65-8c67-d58f7d9134a5\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\78f8d168-9cdb-4c65-8c67-d58f7d9134a5\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 12 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\6d480168
Ptotal=133.60 mm	Comments: 24hr 100year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	1.34	6.00	2.67	12.00	19.24	18.00	2.40
0.25	1.34	6.25	2.67	12.25	19.24	18.25	2.40
0.50	1.34	6.50	2.67	12.50	9.89	18.50	2.40
0.75	1.34	6.75	2.67	12.75	9.89	18.75	2.40
1.00	1.34	7.00	2.67	13.00	1.87	19.00	2.40
1.25	1.34	7.25	2.67	13.25	1.87	19.25	2.40
1.50	1.34	7.50	2.67	13.50	10.96	19.50	2.40
1.75	2.40	7.75	2.67	13.75	10.96	19.75	2.40
2.00	1.74	8.00	3.61	14.00	4.01	20.00	1.60
2.25	1.74	8.25	3.61	14.25	4.01	20.25	1.60
2.50	1.74	8.50	3.61	14.50	4.01	20.50	1.60
2.75	1.74	8.75	3.61	14.75	4.01	20.75	1.60

3.00	1.74	9.00	4.28	15.00	4.01	21.00	1.60
3.25	1.74	9.25	4.28	15.25	4.01	21.25	1.60
3.50	1.74	9.50	4.81	15.50	4.01	21.50	1.60
3.75	1.74	9.75	4.81	15.75	4.01	21.75	1.60
4.00	2.14	10.00	6.15	16.00	2.40	22.00	1.60
4.25	2.14	10.25	6.15	16.25	2.40	22.25	1.60
4.50	2.14	10.50	8.28	16.50	2.40	22.50	1.60
4.75	2.14	10.75	8.28	16.75	2.40	22.75	1.60
5.00	2.14	11.00	12.83	17.00	2.40	23.00	1.60
5.25	2.14	11.25	12.83	17.25	2.40	23.25	1.60
5.50	2.14	11.50	55.58	17.50	2.40	23.50	1.60
5.75	2.14	11.75	147.49	17.75	2.40	23.75	1.60

CALIB							
NASHYD	(0100)	Area	(ha)= 11.35	Curve Number	(CN)= 73.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 7.20	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.35				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.34	6.083	2.67	12.083	19.25	18.08	2.40
0.167	1.34	6.167	2.67	12.167	19.24	18.17	2.40
0.250	1.34	6.250	2.67	12.250	19.24	18.25	2.40
0.333	1.34	6.333	2.67	12.333	19.24	18.33	2.40
0.417	1.34	6.417	2.67	12.417	19.24	18.42	2.40
0.500	1.34	6.500	2.67	12.500	19.24	18.50	2.40
0.583	1.34	6.583	2.67	12.583	9.89	18.58	2.40
0.667	1.34	6.667	2.67	12.667	9.89	18.67	2.40
0.750	1.34	6.750	2.67	12.750	9.89	18.75	2.40
0.833	1.34	6.833	2.67	12.833	9.89	18.83	2.40
0.917	1.34	6.917	2.67	12.917	9.89	18.92	2.40
1.000	1.34	7.000	2.67	13.000	9.89	19.00	2.40
1.083	1.34	7.083	2.67	13.083	1.87	19.08	2.40
1.167	1.34	7.167	2.67	13.167	1.87	19.17	2.40
1.250	1.34	7.250	2.67	13.250	1.87	19.25	2.40
1.333	1.34	7.333	2.67	13.333	1.87	19.33	2.40
1.417	1.34	7.417	2.67	13.417	1.87	19.42	2.40
1.500	1.34	7.500	2.67	13.500	1.87	19.50	2.40
1.583	1.34	7.583	2.67	13.583	10.95	19.58	2.40
1.667	1.34	7.667	2.67	13.667	10.96	19.67	2.40
1.750	1.34	7.750	2.67	13.750	10.96	19.75	2.40
1.833	2.40	7.833	2.67	13.833	10.96	19.83	2.40
1.917	2.40	7.917	2.67	13.917	10.96	19.92	2.40
2.000	2.40	8.000	2.67	14.000	10.96	20.00	2.40
2.083	1.74	8.083	3.61	14.083	4.01	20.08	1.60
2.167	1.74	8.167	3.61	14.167	4.01	20.17	1.60
2.250	1.74	8.250	3.61	14.250	4.01	20.25	1.60
2.333	1.74	8.333	3.61	14.333	4.01	20.33	1.60
2.417	1.74	8.417	3.61	14.417	4.01	20.42	1.60
2.500	1.74	8.500	3.61	14.500	4.01	20.50	1.60
2.583	1.74	8.583	3.61	14.583	4.01	20.58	1.60
2.667	1.74	8.667	3.61	14.667	4.01	20.67	1.60
2.750	1.74	8.750	3.61	14.750	4.01	20.75	1.60
2.833	1.74	8.833	3.61	14.833	4.01	20.83	1.60
2.917	1.74	8.917	3.61	14.917	4.01	20.92	1.60
3.000	1.74	9.000	3.61	15.000	4.01	21.00	1.60
3.083	1.74	9.083	4.28	15.083	4.01	21.08	1.60

3.167	1.74	9.167	4.28	15.167	4.01	21.17	1.60
3.250	1.74	9.250	4.28	15.250	4.01	21.25	1.60
3.333	1.74	9.333	4.28	15.333	4.01	21.33	1.60
3.417	1.74	9.417	4.28	15.417	4.01	21.42	1.60
3.500	1.74	9.500	4.28	15.500	4.01	21.50	1.60
3.583	1.74	9.583	4.81	15.583	4.01	21.58	1.60
3.667	1.74	9.667	4.81	15.667	4.01	21.67	1.60
3.750	1.74	9.750	4.81	15.750	4.01	21.75	1.60
3.833	1.74	9.833	4.81	15.833	4.01	21.83	1.60
3.917	1.74	9.917	4.81	15.917	4.01	21.92	1.60
4.000	1.74	10.000	4.81	16.000	4.01	22.00	1.60
4.083	2.14	10.083	6.15	16.083	2.41	22.08	1.60
4.167	2.14	10.167	6.15	16.167	2.40	22.17	1.60
4.250	2.14	10.250	6.15	16.250	2.40	22.25	1.60
4.333	2.14	10.333	6.15	16.333	2.40	22.33	1.60
4.417	2.14	10.417	6.15	16.417	2.40	22.42	1.60
4.500	2.14	10.500	6.15	16.500	2.40	22.50	1.60
4.583	2.14	10.583	8.28	16.583	2.40	22.58	1.60
4.667	2.14	10.667	8.28	16.667	2.40	22.67	1.60
4.750	2.14	10.750	8.28	16.750	2.40	22.75	1.60
4.833	2.14	10.833	8.28	16.833	2.40	22.83	1.60
4.917	2.14	10.917	8.28	16.917	2.40	22.92	1.60
5.000	2.14	11.000	8.28	17.000	2.40	23.00	1.60
5.083	2.14	11.083	12.83	17.083	2.40	23.08	1.60
5.167	2.14	11.167	12.83	17.167	2.40	23.17	1.60
5.250	2.14	11.250	12.83	17.250	2.40	23.25	1.60
5.333	2.14	11.333	12.83	17.333	2.40	23.33	1.60
5.417	2.14	11.417	12.83	17.417	2.40	23.42	1.60
5.500	2.14	11.500	12.83	17.500	2.40	23.50	1.60
5.583	2.14	11.583	55.57	17.583	2.40	23.58	1.60
5.667	2.14	11.667	55.58	17.667	2.40	23.67	1.60
5.750	2.14	11.750	55.58	17.750	2.40	23.75	1.60
5.833	2.14	11.833	147.48	17.833	2.40	23.83	1.60
5.917	2.14	11.917	147.49	17.917	2.40	23.92	1.60
6.000	2.14	12.000	147.49	18.000	2.40	24.00	1.60

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 1.423 (i)

TIME TO PEAK (hrs)= 12.167

RUNOFF VOLUME (mm)= 72.494

TOTAL RAINFALL (mm)= 133.600

RUNOFF COEFFICIENT = 0.543

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\1fef9938-20f9-46b3-ad1b-0ddac1d564e7\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\1fef9938-20f9-46b3-ad1b-0ddac1d564e7\scen

DATE: 02-23-2024

TIME: 08:29:30

USER:

COMMENTS: _____

** SIMULATION : Run 13 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\2218ca26-588a-4c72-a3d8-a41c1a450bb1\b0a73a8f
Ptotal=193.00 mm	Comments: REGIONAL STORM TIMMINS - 12 hour storm

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
0.00	15.00	3.00	3.00	6.00	43.00	9.00	13.00
1.00	20.00	4.00	5.00	7.00	20.00	10.00	13.00
2.00	10.00	5.00	20.00	8.00	23.00	11.00	8.00

CALIB	Area (ha)= 11.35	Curve Number (CN)= 73.0
NASHYD (0100)	Ia (mm)= 7.20	# of Linear Res.(N)= 3.00
ID= 1 DT= 5.0 min	U.H. Tp(hrs)= 0.35	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	15.00	3.083	3.00	6.083	43.00	9.08	13.00
0.167	15.00	3.167	3.00	6.167	43.00	9.17	13.00
0.250	15.00	3.250	3.00	6.250	43.00	9.25	13.00
0.333	15.00	3.333	3.00	6.333	43.00	9.33	13.00
0.417	15.00	3.417	3.00	6.417	43.00	9.42	13.00
0.500	15.00	3.500	3.00	6.500	43.00	9.50	13.00
0.583	15.00	3.583	3.00	6.583	43.00	9.58	13.00
0.667	15.00	3.667	3.00	6.667	43.00	9.67	13.00
0.750	15.00	3.750	3.00	6.750	43.00	9.75	13.00
0.833	15.00	3.833	3.00	6.833	43.00	9.83	13.00
0.917	15.00	3.917	3.00	6.917	43.00	9.92	13.00
1.000	15.00	4.000	3.00	7.000	43.00	10.00	13.00
1.083	20.00	4.083	5.00	7.083	20.00	10.08	13.00
1.167	20.00	4.167	5.00	7.167	20.00	10.17	13.00
1.250	20.00	4.250	5.00	7.250	20.00	10.25	13.00
1.333	20.00	4.333	5.00	7.333	20.00	10.33	13.00
1.417	20.00	4.417	5.00	7.417	20.00	10.42	13.00
1.500	20.00	4.500	5.00	7.500	20.00	10.50	13.00
1.583	20.00	4.583	5.00	7.583	20.00	10.58	13.00
1.667	20.00	4.667	5.00	7.667	20.00	10.67	13.00
1.750	20.00	4.750	5.00	7.750	20.00	10.75	13.00
1.833	20.00	4.833	5.00	7.833	20.00	10.83	13.00
1.917	20.00	4.917	5.00	7.917	20.00	10.92	13.00
2.000	20.00	5.000	5.00	8.000	20.00	11.00	13.00
2.083	10.00	5.083	20.00	8.083	23.00	11.08	8.00
2.167	10.00	5.167	20.00	8.167	23.00	11.17	8.00
2.250	10.00	5.250	20.00	8.250	23.00	11.25	8.00
2.333	10.00	5.333	20.00	8.333	23.00	11.33	8.00
2.417	10.00	5.417	20.00	8.417	23.00	11.42	8.00
2.500	10.00	5.500	20.00	8.500	23.00	11.50	8.00
2.583	10.00	5.583	20.00	8.583	23.00	11.58	8.00
2.667	10.00	5.667	20.00	8.667	23.00	11.67	8.00
2.750	10.00	5.750	20.00	8.750	23.00	11.75	8.00
2.833	10.00	5.833	20.00	8.833	23.00	11.83	8.00
2.917	10.00	5.917	20.00	8.917	23.00	11.92	8.00
3.000	10.00	6.000	20.00	9.000	23.00	12.00	8.00

Unit Hyd Qpeak (cms)= 1.239

PEAK FLOW (cms)= 0.964 (i)

TIME TO PEAK (hrs)= 7.083

RUNOFF VOLUME (mm)= 123.378

TOTAL RAINFALL (mm)= 193.000


RUNOFF COEFFICIENT = 0.639

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.



APPENDIX D

POST-DEVELOPMENT OTTHYMO RESULT



V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\78768325-db61-484e-a956-c7d325c2de9a\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\78768325-db61-484e-a956-c7d325c2de9a\scen

DATE: 02-23-2024

TIME: 08:29:45

USER:

COMMENTS: _____

** SIMULATION : Run 01 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\8501ff12
Ptotal= 36.95 mm	Comments: 4hr 2year CHICAGO STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	18.78	2.33	4.89	3.50	2.55
0.17	2.47	1.33	83.11	2.50	4.28	3.67	2.39
0.33	2.82	1.50	24.57	2.67	3.82	3.83	2.26
0.50	3.31	1.67	13.01	2.83	3.46	4.00	2.15
0.67	4.05	1.83	9.01	3.00	3.17		
0.83	5.30	2.00	6.97	3.17	2.93		
1.00	7.98	2.17	5.73	3.33	2.72		

CALIB

NASHYD (0201)	Area (ha)= 0.81	Curve Number (CN)= 74.0
ID= 1 DT= 5.0 min	Ia (mm)= 8.00	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.23	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	7.98	2.250	5.73	3.33	2.93
0.167	0.00	1.250	18.78	2.333	5.73	3.42	2.72
0.250	2.47	1.333	18.78	2.417	4.89	3.50	2.72
0.333	2.47	1.417	83.11	2.500	4.89	3.58	2.55
0.417	2.82	1.500	83.11	2.583	4.28	3.67	2.55
0.500	2.82	1.583	24.57	2.667	4.28	3.75	2.39
0.583	3.31	1.667	24.57	2.750	3.82	3.83	2.39
0.667	3.31	1.750	13.01	2.833	3.82	3.92	2.26
0.750	4.05	1.833	13.01	2.917	3.46	4.00	2.26
0.833	4.05	1.917	9.01	3.000	3.46	4.08	2.15
0.917	5.30	2.000	9.01	3.083	3.17	4.17	2.15
1.000	5.30	2.083	6.97	3.167	3.17		
1.083	7.98	2.167	6.97	3.250	2.93		

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.014 (i)
 TIME TO PEAK (hrs)= 1.750
 RUNOFF VOLUME (mm)= 7.085
 TOTAL RAINFALL (mm)= 36.955
 RUNOFF COEFFICIENT = 0.192

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB		
NASHYD (0202)	Area (ha)= 0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	7.98	2.250	5.73	3.33	2.93
0.167	0.00	1.250	18.78	2.333	5.73	3.42	2.72
0.250	2.47	1.333	18.78	2.417	4.89	3.50	2.72
0.333	2.47	1.417	83.11	2.500	4.89	3.58	2.55
0.417	2.82	1.500	83.11	2.583	4.28	3.67	2.55
0.500	2.82	1.583	24.57	2.667	4.28	3.75	2.39
0.583	3.31	1.667	24.57	2.750	3.82	3.83	2.39
0.667	3.31	1.750	13.01	2.833	3.82	3.92	2.26
0.750	4.05	1.833	13.01	2.917	3.46	4.00	2.26
0.833	4.05	1.917	9.01	3.000	3.46	4.08	2.15
0.917	5.30	2.000	9.01	3.083	3.17	4.17	2.15
1.000	5.30	2.083	6.97	3.167	3.17		
1.083	7.98	2.167	6.97	3.250	2.93		

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.005 (i)

TIME TO PEAK (hrs)= 1.667
 RUNOFF VOLUME (mm)= 7.097
 TOTAL RAINFALL (mm)= 36.955
 RUNOFF COEFFICIENT = 0.192

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

 CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min

 Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

IMPERVIOUS PERVIOUS (i)
 Surface Area (ha)= 2.03 7.65
 Dep. Storage (mm)= 1.00 5.00
 Average Slope (%)= 1.00 2.00
 Length (m)= 254.03 40.00
 Mannings n = 0.013 0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	7.98	2.250	5.73	3.33	2.93
0.167	0.00	1.250	18.78	2.333	5.73	3.42	2.72
0.250	2.47	1.333	18.78	2.417	4.89	3.50	2.72
0.333	2.47	1.417	83.11	2.500	4.89	3.58	2.55
0.417	2.82	1.500	83.11	2.583	4.28	3.67	2.55
0.500	2.82	1.583	24.57	2.667	4.28	3.75	2.39
0.583	3.31	1.667	24.57	2.750	3.82	3.83	2.39
0.667	3.31	1.750	13.01	2.833	3.82	3.92	2.26
0.750	4.05	1.833	13.01	2.917	3.46	4.00	2.26
0.833	4.05	1.917	9.01	3.000	3.46	4.08	2.15
0.917	5.30	2.000	9.01	3.083	3.17	4.17	2.15
1.000	5.30	2.083	6.97	3.167	3.17		
1.083	7.98	2.167	6.97	3.250	2.93		

Max.Eff.Inten.(mm/hr)= 83.11 9.96
 over (min) 5.00 20.00
 Storage Coeff. (min)= 4.81 (ii) 17.88 (ii)
 Unit Hyd. Tpeak (min)= 5.00 20.00
 Unit Hyd. peak (cms)= 0.22 0.06

PEAK FLOW (cms)= 0.42 0.12
 TIME TO PEAK (hrs)= 1.50 1.75
 RUNOFF VOLUME (mm)= 35.95 6.99
 TOTAL RAINFALL (mm)= 36.95 36.95
 RUNOFF COEFFICIENT = 0.97 0.19

TOTALS
 0.455 (iii)
 1.50
 13.07
 36.95
 0.35

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

(i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
 CN* = 69.0 Ia = Dep. Storage (Above)
 (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
 THAN THE STORAGE COEFFICIENT.
 (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

 RESERVOIR(0300)
 IN= 2---> OUT= 1

 OVERFLOW IS OFF

DT= 5.0 min	OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
	0.0000	0.0000	0.7200	0.1600
	0.0500	0.0500	0.7300	0.1800
	0.1500	0.0700	0.8600	0.1850
	0.3000	0.0900	0.9500	0.1900
	0.4200	0.1200	0.9900	0.1950
	0.5500	0.1300	1.1900	0.2300
	0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	0.455	1.50	13.07
OUTFLOW: ID= 1 (0300)	9.680	0.112	2.25	13.05

PEAK FLOW REDUCTION [Qout/Qin](%)= 24.64
 TIME SHIFT OF PEAK FLOW (min)= 45.00
 MAXIMUM STORAGE USED (ha.m.)= 0.0624

ADD HYD (0400) 1 + 2 = 3	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.014	1.75	7.08
+ ID2= 2 (0202):	0.24	0.005	1.67	7.10
=====				
ID = 3 (0400):	1.05	0.018	1.75	7.09

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

ADD HYD (0400) 3 + 2 = 1	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.018	1.75	7.09
+ ID2= 2 (0300):	9.68	0.112	2.25	13.05
=====				
ID = 1 (0400):	10.73	0.122	2.17	12.46

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\bad7bbac-5ed5-4663-872d-0e4ac25b4c53\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\bad7bbac-5ed5-4663-872d-0e4ac25b4c53\scen

DATE: 02-23-2024

TIME: 08:29:46

USER:

COMMENTS: _____

** SIMULATION : Run 02 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\0cb77411
Ptotal= 50.52 mm	Comments: 4hr 5year CHICAGO STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	25.64	2.33	6.96	3.50	3.68
0.17	3.57	1.33	108.92	2.50	6.12	3.67	3.47
0.33	4.07	1.50	33.31	2.67	5.48	3.83	3.28
0.50	4.76	1.67	17.99	2.83	4.97	4.00	3.12
0.67	5.79	1.83	12.60	3.00	4.56		
0.83	7.53	2.00	9.82	3.17	4.22		
1.00	11.20	2.17	8.12	3.33	3.93		

CALIB

NASHYD (0201)	Area (ha)= 0.81	Curve Number (CN)= 74.0
ID= 1 DT= 5.0 min	Ia (mm)= 8.00	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.23	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	11.20	2.250	8.12	3.33	4.22
0.167	0.00	1.250	25.64	2.333	8.12	3.42	3.93
0.250	3.57	1.333	25.64	2.417	6.96	3.50	3.93
0.333	3.57	1.417	108.92	2.500	6.96	3.58	3.68
0.417	4.07	1.500	108.92	2.583	6.12	3.67	3.68
0.500	4.07	1.583	33.31	2.667	6.12	3.75	3.47
0.583	4.76	1.667	33.31	2.750	5.48	3.83	3.47
0.667	4.76	1.750	17.99	2.833	5.48	3.92	3.28
0.750	5.79	1.833	17.99	2.917	4.97	4.00	3.28
0.833	5.79	1.917	12.60	3.000	4.97	4.08	3.12
0.917	7.53	2.000	12.60	3.083	4.56	4.17	3.12
1.000	7.53	2.083	9.82	3.167	4.56		
1.083	11.20	2.167	9.82	3.250	4.22		

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.028 (i)
 TIME TO PEAK (hrs)= 1.750
 RUNOFF VOLUME (mm)= 13.705
 TOTAL RAINFALL (mm)= 50.518
 RUNOFF COEFFICIENT = 0.271

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB		
NASHYD (0202)	Area (ha)= 0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	11.20	2.250	8.12	3.33	4.22
0.167	0.00	1.250	25.64	2.333	8.12	3.42	3.93
0.250	3.57	1.333	25.64	2.417	6.96	3.50	3.93
0.333	3.57	1.417	108.92	2.500	6.96	3.58	3.68
0.417	4.07	1.500	108.92	2.583	6.12	3.67	3.68
0.500	4.07	1.583	33.31	2.667	6.12	3.75	3.47
0.583	4.76	1.667	33.31	2.750	5.48	3.83	3.47
0.667	4.76	1.750	17.99	2.833	5.48	3.92	3.28
0.750	5.79	1.833	17.99	2.917	4.97	4.00	3.28
0.833	5.79	1.917	12.60	3.000	4.97	4.08	3.12
0.917	7.53	2.000	12.60	3.083	4.56	4.17	3.12
1.000	7.53	2.083	9.82	3.167	4.56		
1.083	11.20	2.167	9.82	3.250	4.22		

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.009 (i)

TIME TO PEAK (hrs)= 1.667
 RUNOFF VOLUME (mm)= 13.584
 TOTAL RAINFALL (mm)= 50.518
 RUNOFF COEFFICIENT = 0.269

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

 CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min
 Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	11.20	2.250	8.12	3.33	4.22
0.167	0.00	1.250	25.64	2.333	8.12	3.42	3.93
0.250	3.57	1.333	25.64	2.417	6.96	3.50	3.93
0.333	3.57	1.417	108.92	2.500	6.96	3.58	3.68
0.417	4.07	1.500	108.92	2.583	6.12	3.67	3.68
0.500	4.07	1.583	33.31	2.667	6.12	3.75	3.47
0.583	4.76	1.667	33.31	2.750	5.48	3.83	3.47
0.667	4.76	1.750	17.99	2.833	5.48	3.92	3.28
0.750	5.79	1.833	17.99	2.917	4.97	4.00	3.28
0.833	5.79	1.917	12.60	3.000	4.97	4.08	3.12
0.917	7.53	2.000	12.60	3.083	4.56	4.17	3.12
1.000	7.53	2.083	9.82	3.167	4.56		
1.083	11.20	2.167	9.82	3.250	4.22		

Max.Eff.Inten.(mm/hr)=	108.92	22.75
over (min)	5.00	15.00
Storage Coeff. (min)=	4.32 (ii)	13.71 (ii)
Unit Hyd. Tpeak (min)=	5.00	15.00
Unit Hyd. peak (cms)=	0.23	0.08

			TOTALS
PEAK FLOW (cms)=	0.57	0.26	0.684 (iii)
TIME TO PEAK (hrs)=	1.50	1.67	1.50
RUNOFF VOLUME (mm)=	49.52	12.98	20.65
TOTAL RAINFALL (mm)=	50.52	50.52	50.52
RUNOFF COEFFICIENT =	0.98	0.26	0.41

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

(i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
 CN* = 69.0 Ia = Dep. Storage (Above)
 (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
 THAN THE STORAGE COEFFICIENT.
 (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

 RESERVOIR(0300)
 IN= 2---> OUT= 1
 OVERFLOW IS OFF

DT= 5.0 min	OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
	0.0000	0.0000	0.7200	0.1600
	0.0500	0.0500	0.7300	0.1800
	0.1500	0.0700	0.8600	0.1850
	0.3000	0.0900	0.9500	0.1900
	0.4200	0.1200	0.9900	0.1950
	0.5500	0.1300	1.1900	0.2300
	0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	0.684	1.50	20.65
OUTFLOW: ID= 1 (0300)	9.680	0.251	2.00	20.63

PEAK FLOW REDUCTION [Qout/Qin](%)= 36.72
 TIME SHIFT OF PEAK FLOW (min)= 30.00
 MAXIMUM STORAGE USED (ha.m.)= 0.0835

ADD HYD (0400) 1 + 2 = 3	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.028	1.75	13.70
+ ID2= 2 (0202):	0.24	0.009	1.67	13.58
=====				
ID = 3 (0400):	1.05	0.037	1.75	13.68

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

ADD HYD (0400) 3 + 2 = 1	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.037	1.75	13.68
+ ID2= 2 (0300):	9.68	0.251	2.00	20.63
=====				
ID = 1 (0400):	10.73	0.277	2.00	19.95

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\4e53c6d-aa91-459e-af31-09be4c370827\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\4e53c6d-aa91-459e-af31-09be4c370827\scen

DATE: 02-23-2024

TIME: 08:29:45

USER:

COMMENTS: _____

** SIMULATION : Run 03 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\05237a76
Ptotal= 59.69 mm	Comments: 4hr 10year CHICAGO STORM - CITY OF BARRI

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	30.27	2.33	8.35	3.50	4.45
0.17	4.32	1.33	126.55	2.50	7.35	3.67	4.19
0.33	4.91	1.50	39.22	2.67	6.59	3.83	3.97
0.50	5.73	1.67	21.35	2.83	5.99	4.00	3.77
0.67	6.96	1.83	15.01	3.00	5.50		
0.83	9.03	2.00	11.74	3.17	5.09		
1.00	13.36	2.17	9.72	3.33	4.74		

CALIB

NASHYD (0201)	Area (ha)= 0.81	Curve Number (CN)= 74.0
ID= 1 DT= 5.0 min	Ia (mm)= 8.00	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.23	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	13.36	2.250	9.72	3.33	5.09
0.167	0.00	1.250	30.27	2.333	9.72	3.42	4.74
0.250	4.32	1.333	30.27	2.417	8.35	3.50	4.74
0.333	4.32	1.417	126.55	2.500	8.35	3.58	4.45
0.417	4.91	1.500	126.55	2.583	7.35	3.67	4.45
0.500	4.91	1.583	39.22	2.667	7.35	3.75	4.19
0.583	5.73	1.667	39.22	2.750	6.59	3.83	4.19
0.667	5.73	1.750	21.35	2.833	6.59	3.92	3.97
0.750	6.96	1.833	21.35	2.917	5.99	4.00	3.97
0.833	6.96	1.917	15.01	3.000	5.99	4.08	3.77
0.917	9.03	2.000	15.01	3.083	5.50	4.17	3.77
1.000	9.03	2.083	11.74	3.167	5.50		
1.083	13.36	2.167	11.74	3.250	5.09		

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.039 (i)
 TIME TO PEAK (hrs)= 1.750
 RUNOFF VOLUME (mm)= 18.939
 TOTAL RAINFALL (mm)= 59.693
 RUNOFF COEFFICIENT = 0.317

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB		
NASHYD (0202)	Area (ha)= 0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	13.36	2.250	9.72	3.33	5.09
0.167	0.00	1.250	30.27	2.333	9.72	3.42	4.74
0.250	4.32	1.333	30.27	2.417	8.35	3.50	4.74
0.333	4.32	1.417	126.55	2.500	8.35	3.58	4.45
0.417	4.91	1.500	126.55	2.583	7.35	3.67	4.45
0.500	4.91	1.583	39.22	2.667	7.35	3.75	4.19
0.583	5.73	1.667	39.22	2.750	6.59	3.83	4.19
0.667	5.73	1.750	21.35	2.833	6.59	3.92	3.97
0.750	6.96	1.833	21.35	2.917	5.99	4.00	3.97
0.833	6.96	1.917	15.01	3.000	5.99	4.08	3.77
0.917	9.03	2.000	15.01	3.083	5.50	4.17	3.77
1.000	9.03	2.083	11.74	3.167	5.50		
1.083	13.36	2.167	11.74	3.250	5.09		

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.013 (i)

TIME TO PEAK (hrs)= 1.667
 RUNOFF VOLUME (mm)= 18.713
 TOTAL RAINFALL (mm)= 59.693
 RUNOFF COEFFICIENT = 0.313

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

 CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min
 Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	13.36	2.250	9.72	3.33	5.09
0.167	0.00	1.250	30.27	2.333	9.72	3.42	4.74
0.250	4.32	1.333	30.27	2.417	8.35	3.50	4.74
0.333	4.32	1.417	126.55	2.500	8.35	3.58	4.45
0.417	4.91	1.500	126.55	2.583	7.35	3.67	4.45
0.500	4.91	1.583	39.22	2.667	7.35	3.75	4.19
0.583	5.73	1.667	39.22	2.750	6.59	3.83	4.19
0.667	5.73	1.750	21.35	2.833	6.59	3.92	3.97
0.750	6.96	1.833	21.35	2.917	5.99	4.00	3.97
0.833	6.96	1.917	15.01	3.000	5.99	4.08	3.77
0.917	9.03	2.000	15.01	3.083	5.50	4.17	3.77
1.000	9.03	2.083	11.74	3.167	5.50		
1.083	13.36	2.167	11.74	3.250	5.09		

Max.Eff.Inten.(mm/hr)=	126.55	31.49
over (min)	5.00	15.00
Storage Coeff. (min)=	4.07 (ii)	12.31 (ii)
Unit Hyd. Tpeak (min)=	5.00	15.00
Unit Hyd. peak (cms)=	0.24	0.09

PEAK FLOW (cms)=	0.67	0.38	*TOTALS*
TIME TO PEAK (hrs)=	1.50	1.67	0.845 (iii)
RUNOFF VOLUME (mm)=	58.69	17.72	1.50
TOTAL RAINFALL (mm)=	59.69	59.69	26.32
RUNOFF COEFFICIENT =	0.98	0.30	59.69
			0.44

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

(i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
 CN* = 69.0 Ia = Dep. Storage (Above)
 (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
 THAN THE STORAGE COEFFICIENT.
 (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

 RESERVOIR(0300)
 IN= 2---> OUT= 1
 OVERFLOW IS OFF

DT= 5.0 min	OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
	0.0000	0.0000	0.7200	0.1600
	0.0500	0.0500	0.7300	0.1800
	0.1500	0.0700	0.8600	0.1850
	0.3000	0.0900	0.9500	0.1900
	0.4200	0.1200	0.9900	0.1950
	0.5500	0.1300	1.1900	0.2300
	0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	0.845	1.50	26.32
OUTFLOW: ID= 1 (0300)	9.680	0.338	2.00	26.30

PEAK FLOW REDUCTION [Qout/Qin](%)= 39.96
 TIME SHIFT OF PEAK FLOW (min)= 30.00
 MAXIMUM STORAGE USED (ha.m.)= 0.0996

ADD HYD (0400) 1 + 2 = 3	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.039	1.75	18.94
+ ID2= 2 (0202):	0.24	0.013	1.67	18.71
=====				
ID = 3 (0400):	1.05	0.051	1.75	18.89

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

ADD HYD (0400) 3 + 2 = 1	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.051	1.75	18.89
+ ID2= 2 (0300):	9.68	0.338	2.00	26.30
=====				
ID = 1 (0400):	10.73	0.378	1.92	25.57

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ba2d25ff-cb4c-4041-a773-3b294e7ea9e2\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ba2d25ff-cb4c-4041-a773-3b294e7ea9e2\scen

DATE: 02-23-2024

TIME: 08:29:46

USER:

COMMENTS: _____

** SIMULATION : Run 04 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\4ed3113b
Ptotal= 71.24 mm	Comments: 4hr 25year CHICAGO STORM - CITY OF BARRI

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	36.37	2.33	10.09	3.50	5.38
0.17	5.22	1.33	148.15	2.50	8.89	3.67	5.08
0.33	5.94	1.50	47.06	2.67	7.96	3.83	4.80
0.50	6.93	1.67	25.72	2.83	7.24	4.00	4.57
0.67	8.42	1.83	18.11	3.00	6.65		
0.83	10.91	2.00	14.17	3.17	6.15		
1.00	16.13	2.17	11.74	3.33	5.74		

CALIB

NASHYD (0201)	Area (ha)= 0.81	Curve Number (CN)= 74.0
ID= 1 DT= 5.0 min	Ia (mm)= 8.00	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.23	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	16.13	2.250	11.74	3.33	6.15
0.167	0.00	1.250	36.37	2.333	11.74	3.42	5.74
0.250	5.22	1.333	36.37	2.417	10.09	3.50	5.74
0.333	5.22	1.417	148.15	2.500	10.09	3.58	5.38
0.417	5.94	1.500	148.15	2.583	8.89	3.67	5.38
0.500	5.94	1.583	47.06	2.667	8.89	3.75	5.08
0.583	6.93	1.667	47.06	2.750	7.96	3.83	5.08
0.667	6.93	1.750	25.72	2.833	7.96	3.92	4.80
0.750	8.42	1.833	25.72	2.917	7.24	4.00	4.80
0.833	8.42	1.917	18.11	3.000	7.24	4.08	4.57
0.917	10.91	2.000	18.11	3.083	6.65	4.17	4.57
1.000	10.91	2.083	14.17	3.167	6.65		
1.083	16.13	2.167	14.17	3.250	6.15		

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.055 (i)
 TIME TO PEAK (hrs)= 1.750
 RUNOFF VOLUME (mm)= 26.196
 TOTAL RAINFALL (mm)= 71.237
 RUNOFF COEFFICIENT = 0.368

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB		
NASHYD (0202)	Area (ha)= 0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	16.13	2.250	11.74	3.33	6.15
0.167	0.00	1.250	36.37	2.333	11.74	3.42	5.74
0.250	5.22	1.333	36.37	2.417	10.09	3.50	5.74
0.333	5.22	1.417	148.15	2.500	10.09	3.58	5.38
0.417	5.94	1.500	148.15	2.583	8.89	3.67	5.38
0.500	5.94	1.583	47.06	2.667	8.89	3.75	5.08
0.583	6.93	1.667	47.06	2.750	7.96	3.83	5.08
0.667	6.93	1.750	25.72	2.833	7.96	3.92	4.80
0.750	8.42	1.833	25.72	2.917	7.24	4.00	4.80
0.833	8.42	1.917	18.11	3.000	7.24	4.08	4.57
0.917	10.91	2.000	18.11	3.083	6.65	4.17	4.57
1.000	10.91	2.083	14.17	3.167	6.65		
1.083	16.13	2.167	14.17	3.250	6.15		

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.018 (i)

TIME TO PEAK (hrs)= 1.667
 RUNOFF VOLUME (mm)= 25.831
 TOTAL RAINFALL (mm)= 71.237
 RUNOFF COEFFICIENT = 0.363

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

 CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min
 Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	16.13	2.250	11.74	3.33	6.15
0.167	0.00	1.250	36.37	2.333	11.74	3.42	5.74
0.250	5.22	1.333	36.37	2.417	10.09	3.50	5.74
0.333	5.22	1.417	148.15	2.500	10.09	3.58	5.38
0.417	5.94	1.500	148.15	2.583	8.89	3.67	5.38
0.500	5.94	1.583	47.06	2.667	8.89	3.75	5.08
0.583	6.93	1.667	47.06	2.750	7.96	3.83	5.08
0.667	6.93	1.750	25.72	2.833	7.96	3.92	4.80
0.750	8.42	1.833	25.72	2.917	7.24	4.00	4.80
0.833	8.42	1.917	18.11	3.000	7.24	4.08	4.57
0.917	10.91	2.000	18.11	3.083	6.65	4.17	4.57
1.000	10.91	2.083	14.17	3.167	6.65		
1.083	16.13	2.167	14.17	3.250	6.15		

Max.Eff.Inten.(mm/hr)=	148.15	43.67
over (min)	5.00	15.00
Storage Coeff. (min)=	3.82 (ii)	11.06 (ii)
Unit Hyd. Tpeak (min)=	5.00	15.00
Unit Hyd. peak (cms)=	0.25	0.09

			TOTALS
PEAK FLOW (cms)=	0.79	0.56	1.062 (iii)
TIME TO PEAK (hrs)=	1.50	1.67	1.50
RUNOFF VOLUME (mm)=	70.24	24.33	33.97
TOTAL RAINFALL (mm)=	71.24	71.24	71.24
RUNOFF COEFFICIENT =	0.99	0.34	0.48

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

(i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
 CN* = 69.0 Ia = Dep. Storage (Above)
 (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
 THAN THE STORAGE COEFFICIENT.
 (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

 RESERVOIR(0300)
 IN= 2---> OUT= 1
 OVERFLOW IS OFF

DT= 5.0 min	OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
	0.0000	0.0000	0.7200	0.1600
	0.0500	0.0500	0.7300	0.1800
	0.1500	0.0700	0.8600	0.1850
	0.3000	0.0900	0.9500	0.1900
	0.4200	0.1200	0.9900	0.1950
	0.5500	0.1300	1.1900	0.2300
	0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	1.062	1.50	33.97
OUTFLOW: ID= 1 (0300)	9.680	0.466	1.92	33.94

PEAK FLOW REDUCTION [Qout/Qin](%)= 43.88
 TIME SHIFT OF PEAK FLOW (min)= 25.00
 MAXIMUM STORAGE USED (ha.m.)= 0.1239

ADD HYD (0400) 1 + 2 = 3	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.055	1.75	26.20
+ ID2= 2 (0202):	0.24	0.018	1.67	25.83
=====				
ID = 3 (0400):	1.05	0.072	1.67	26.11

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

ADD HYD (0400) 3 + 2 = 1	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.072	1.67	26.11
+ ID2= 2 (0300):	9.68	0.466	1.92	33.94
=====				
ID = 1 (0400):	10.73	0.524	1.92	33.17

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\0324624-2274-4d28-9e58-0cfe8473d129\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\0324624-2274-4d28-9e58-0cfe8473d129\scen

DATE: 02-23-2024

TIME: 08:29:45

USER:

COMMENTS: _____

** SIMULATION : Run 05 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\806310ce
Ptotal= 79.45 mm	Comments: 4hr 50year CHICAGO STORM - CITY OF BARRI

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	40.22	2.33	11.37	3.50	6.11
0.17	5.93	1.33	164.22	2.50	10.03	3.67	5.77
0.33	6.74	1.50	51.92	2.67	9.00	3.83	5.46
0.50	7.85	1.67	28.58	2.83	8.19	4.00	5.19
0.67	9.50	1.83	20.23	3.00	7.53		
0.83	12.27	2.00	15.88	3.17	6.98		
1.00	18.04	2.17	13.20	3.33	6.51		

CALIB

NASHYD (0201)	Area (ha)= 0.81	Curve Number (CN)= 74.0
ID= 1 DT= 5.0 min	Ia (mm)= 8.00	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.23	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	18.04	2.250	13.20	3.33	6.98
0.167	0.00	1.250	40.22	2.333	13.20	3.42	6.51
0.250	5.93	1.333	40.22	2.417	11.37	3.50	6.51
0.333	5.93	1.417	164.22	2.500	11.37	3.58	6.11
0.417	6.74	1.500	164.22	2.583	10.03	3.67	6.11
0.500	6.74	1.583	51.92	2.667	10.03	3.75	5.77
0.583	7.85	1.667	51.92	2.750	9.00	3.83	5.77
0.667	7.85	1.750	28.58	2.833	9.00	3.92	5.46
0.750	9.50	1.833	28.58	2.917	8.19	4.00	5.46
0.833	9.50	1.917	20.23	3.000	8.19	4.08	5.19
0.917	12.27	2.000	20.23	3.083	7.53	4.17	5.19
1.000	12.27	2.083	15.88	3.167	7.53		
1.083	18.04	2.167	15.88	3.250	6.98		

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.067 (i)
 TIME TO PEAK (hrs)= 1.750
 RUNOFF VOLUME (mm)= 31.736
 TOTAL RAINFALL (mm)= 79.453
 RUNOFF COEFFICIENT = 0.399

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB		
NASHYD (0202)	Area (ha)= 0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	18.04	2.250	13.20	3.33	6.98
0.167	0.00	1.250	40.22	2.333	13.20	3.42	6.51
0.250	5.93	1.333	40.22	2.417	11.37	3.50	6.51
0.333	5.93	1.417	164.22	2.500	11.37	3.58	6.11
0.417	6.74	1.500	164.22	2.583	10.03	3.67	6.11
0.500	6.74	1.583	51.92	2.667	10.03	3.75	5.77
0.583	7.85	1.667	51.92	2.750	9.00	3.83	5.77
0.667	7.85	1.750	28.58	2.833	9.00	3.92	5.46
0.750	9.50	1.833	28.58	2.917	8.19	4.00	5.46
0.833	9.50	1.917	20.23	3.000	8.19	4.08	5.19
0.917	12.27	2.000	20.23	3.083	7.53	4.17	5.19
1.000	12.27	2.083	15.88	3.167	7.53		
1.083	18.04	2.167	15.88	3.250	6.98		

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.022 (i)

TIME TO PEAK (hrs)= 1.667
 RUNOFF VOLUME (mm)= 31.269
 TOTAL RAINFALL (mm)= 79.453
 RUNOFF COEFFICIENT = 0.394

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min

Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	18.04	2.250	13.20	3.33	6.98
0.167	0.00	1.250	40.22	2.333	13.20	3.42	6.51
0.250	5.93	1.333	40.22	2.417	11.37	3.50	6.51
0.333	5.93	1.417	164.22	2.500	11.37	3.58	6.11
0.417	6.74	1.500	164.22	2.583	10.03	3.67	6.11
0.500	6.74	1.583	51.92	2.667	10.03	3.75	5.77
0.583	7.85	1.667	51.92	2.750	9.00	3.83	5.77
0.667	7.85	1.750	28.58	2.833	9.00	3.92	5.46
0.750	9.50	1.833	28.58	2.917	8.19	4.00	5.46
0.833	9.50	1.917	20.23	3.000	8.19	4.08	5.19
0.917	12.27	2.000	20.23	3.083	7.53	4.17	5.19
1.000	12.27	2.083	15.88	3.167	7.53		
1.083	18.04	2.167	15.88	3.250	6.98		

Max.Eff.Inten.(mm/hr)=	164.22	53.35
over (min)	5.00	15.00
Storage Coeff. (min)=	3.67 (ii)	10.34 (ii)
Unit Hyd. Tpeak (min)=	5.00	15.00
Unit Hyd. peak (cms)=	0.25	0.09

TOTALS
 1.231 (iii)
 1.50
 39.70
 79.45
 0.50

PEAK FLOW (cms)=	0.88	0.70
TIME TO PEAK (hrs)=	1.50	1.67
RUNOFF VOLUME (mm)=	78.45	29.40
TOTAL RAINFALL (mm)=	79.45	79.45
RUNOFF COEFFICIENT =	0.99	0.37

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

- (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
 CN* = 69.0 Ia = Dep. Storage (Above)
- (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
 THAN THE STORAGE COEFFICIENT.
- (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

RESERVOIR(0300)
 IN= 2---> OUT= 1

OVERFLOW IS OFF

DT= 5.0 min	OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
	0.0000	0.0000	0.7200	0.1600
	0.0500	0.0500	0.7300	0.1800
	0.1500	0.0700	0.8600	0.1850
	0.3000	0.0900	0.9500	0.1900
	0.4200	0.1200	0.9900	0.1950
	0.5500	0.1300	1.1900	0.2300
	0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	1.231	1.50	39.70
OUTFLOW: ID= 1 (0300)	9.680	0.567	1.92	39.67

PEAK FLOW REDUCTION [Qout/Qin](%)= 46.07
 TIME SHIFT OF PEAK FLOW (min)= 25.00
 MAXIMUM STORAGE USED (ha.m.)= 0.1385

ADD HYD (0400) 1 + 2 = 3	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.067	1.75	31.74
+ ID2= 2 (0202):	0.24	0.022	1.67	31.27
=====				
ID = 3 (0400):	1.05	0.089	1.67	31.63

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

ADD HYD (0400) 3 + 2 = 1	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.089	1.67	31.63
+ ID2= 2 (0300):	9.68	0.567	1.92	39.67
=====				
ID = 1 (0400):	10.73	0.643	1.83	38.89

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ee3afb-cc1a-4a42-bd2b-7b0332bd9826\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\ee3afb-cc1a-4a42-bd2b-7b0332bd9826\scen

DATE: 02-23-2024

TIME: 08:29:46

USER:

COMMENTS: _____

** SIMULATION : Run 06 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\47ce8768
Ptotal= 87.58 mm	Comments: 4hr 100year CHICAGO STORM - CITY OF BARR

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.00	1.17	45.22	2.33	12.44	3.50	6.60
0.17	6.41	1.33	180.15	2.50	10.94	3.67	6.22
0.33	7.29	1.50	58.54	2.67	9.80	3.83	5.89
0.50	8.52	1.67	31.96	2.83	8.90	4.00	5.59
0.67	10.36	1.83	22.45	3.00	8.16		
0.83	13.45	2.00	17.52	3.17	7.56		
1.00	19.96	2.17	14.50	3.33	7.04		

CALIB

NASHYD (0201)	Area (ha)= 0.81	Curve Number (CN)= 74.0
ID= 1 DT= 5.0 min	Ia (mm)= 8.00	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.23	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	19.96	2.250	14.50	3.33	7.56
0.167	0.00	1.250	45.22	2.333	14.50	3.42	7.04
0.250	6.41	1.333	45.22	2.417	12.44	3.50	7.04
0.333	6.41	1.417	180.15	2.500	12.44	3.58	6.60
0.417	7.29	1.500	180.15	2.583	10.94	3.67	6.60
0.500	7.29	1.583	58.54	2.667	10.94	3.75	6.22
0.583	8.52	1.667	58.54	2.750	9.80	3.83	6.22
0.667	8.52	1.750	31.96	2.833	9.80	3.92	5.89
0.750	10.36	1.833	31.96	2.917	8.90	4.00	5.89
0.833	10.36	1.917	22.45	3.000	8.90	4.08	5.59
0.917	13.45	2.000	22.45	3.083	8.16	4.17	5.59
1.000	13.45	2.083	17.52	3.167	8.16		
1.083	19.96	2.167	17.52	3.250	7.56		

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.081 (i)
 TIME TO PEAK (hrs)= 1.750
 RUNOFF VOLUME (mm)= 37.469
 TOTAL RAINFALL (mm)= 87.578
 RUNOFF COEFFICIENT = 0.428

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB		
NASHYD (0202)	Area (ha)= 0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
-----	U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	19.96	2.250	14.50	3.33	7.56
0.167	0.00	1.250	45.22	2.333	14.50	3.42	7.04
0.250	6.41	1.333	45.22	2.417	12.44	3.50	7.04
0.333	6.41	1.417	180.15	2.500	12.44	3.58	6.60
0.417	7.29	1.500	180.15	2.583	10.94	3.67	6.60
0.500	7.29	1.583	58.54	2.667	10.94	3.75	6.22
0.583	8.52	1.667	58.54	2.750	9.80	3.83	6.22
0.667	8.52	1.750	31.96	2.833	9.80	3.92	5.89
0.750	10.36	1.833	31.96	2.917	8.90	4.00	5.89
0.833	10.36	1.917	22.45	3.000	8.90	4.08	5.59
0.917	13.45	2.000	22.45	3.083	8.16	4.17	5.59
1.000	13.45	2.083	17.52	3.167	8.16		
1.083	19.96	2.167	17.52	3.250	7.56		

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.027 (i)

TIME TO PEAK (hrs)= 1.667
RUNOFF VOLUME (mm)= 36.903
TOTAL RAINFALL (mm)= 87.578
RUNOFF COEFFICIENT = 0.421

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
STANDHYD (0200)
ID= 1 DT= 5.0 min

Area (ha)= 9.68
Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.00	1.167	19.96	2.250	14.50	3.33	7.56
0.167	0.00	1.250	45.22	2.333	14.50	3.42	7.04
0.250	6.41	1.333	45.22	2.417	12.44	3.50	7.04
0.333	6.41	1.417	180.15	2.500	12.44	3.58	6.60
0.417	7.29	1.500	180.15	2.583	10.94	3.67	6.60
0.500	7.29	1.583	58.54	2.667	10.94	3.75	6.22
0.583	8.52	1.667	58.54	2.750	9.80	3.83	6.22
0.667	8.52	1.750	31.96	2.833	9.80	3.92	5.89
0.750	10.36	1.833	31.96	2.917	8.90	4.00	5.89
0.833	10.36	1.917	22.45	3.000	8.90	4.08	5.59
0.917	13.45	2.000	22.45	3.083	8.16	4.17	5.59
1.000	13.45	2.083	17.52	3.167	8.16		
1.083	19.96	2.167	17.52	3.250	7.56		

Max.Eff.Inten.(mm/hr)=	180.15	63.59
over (min)	5.00	10.00
Storage Coeff. (min)=	3.53 (ii)	9.76 (ii)
Unit Hyd. Tpeak (min)=	5.00	10.00
Unit Hyd. peak (cms)=	0.26	0.11

PEAK FLOW (cms)=	0.97	0.89	*TOTALS*
TIME TO PEAK (hrs)=	1.50	1.58	1.657 (iii)
RUNOFF VOLUME (mm)=	86.58	34.67	1.50
TOTAL RAINFALL (mm)=	87.58	87.58	45.57
RUNOFF COEFFICIENT =	0.99	0.40	87.58
			0.52

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

(i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 69.0 Ia = Dep. Storage (Above)
(ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
(iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

RESERVOIR(0300)
IN= 2---> OUT= 1

OVERFLOW IS OFF

DT= 5.0 min	OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
	0.0000	0.0000	0.7200	0.1600
	0.0500	0.0500	0.7300	0.1800
	0.1500	0.0700	0.8600	0.1850
	0.3000	0.0900	0.9500	0.1900
	0.4200	0.1200	0.9900	0.1950
	0.5500	0.1300	1.1900	0.2300
	0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	1.657	1.50	45.57
OUTFLOW: ID= 1 (0300)	9.680	0.720	1.83	45.54

PEAK FLOW REDUCTION [Qout/Qin](%)= 43.45
 TIME SHIFT OF PEAK FLOW (min)= 20.00
 MAXIMUM STORAGE USED (ha.m.)= 0.1606

ADD HYD (0400) 1 + 2 = 3	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.081	1.75	37.47
+ ID2= 2 (0202):	0.24	0.027	1.67	36.90
=====				
ID = 3 (0400):	1.05	0.107	1.67	37.34

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

ADD HYD (0400) 3 + 2 = 1	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.107	1.67	37.34
+ ID2= 2 (0300):	9.68	0.720	1.83	45.54
=====				
ID = 1 (0400):	10.73	0.816	1.83	44.74

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

FINISH
 =====
 =====

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\1624655e-075a-477c-9724-d1a5bba31e0f\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\1624655e-075a-477c-9724-d1a5bba31e0f\scen

DATE: 02-23-2024

TIME: 08:29:45

USER:

COMMENTS: _____

** SIMULATION : Run 07 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\9bce3a2a
Ptotal= 55.00 mm	Comments: 24hr 2year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.55	6.00	1.10	12.00	7.92	18.00	0.99
0.25	0.55	6.25	1.10	12.25	7.92	18.25	0.99
0.50	0.55	6.50	1.10	12.50	4.07	18.50	0.99
0.75	0.55	6.75	1.10	12.75	4.07	18.75	0.99
1.00	0.55	7.00	1.10	13.00	0.77	19.00	0.99
1.25	0.55	7.25	1.10	13.25	0.77	19.25	0.99
1.50	0.55	7.50	1.10	13.50	4.51	19.50	0.99
1.75	0.99	7.75	1.10	13.75	4.51	19.75	0.99
2.00	0.71	8.00	1.49	14.00	1.65	20.00	0.66
2.25	0.71	8.25	1.49	14.25	1.65	20.25	0.66
2.50	0.71	8.50	1.49	14.50	1.65	20.50	0.66
2.75	0.71	8.75	1.49	14.75	1.65	20.75	0.66

3.00	0.71	9.00	1.76	15.00	1.65	21.00	0.66
3.25	0.71	9.25	1.76	15.25	1.65	21.25	0.66
3.50	0.71	9.50	1.98	15.50	1.65	21.50	0.66
3.75	0.71	9.75	1.98	15.75	1.65	21.75	0.66
4.00	0.88	10.00	2.53	16.00	0.99	22.00	0.66
4.25	0.88	10.25	2.53	16.25	0.99	22.25	0.66
4.50	0.88	10.50	3.41	16.50	0.99	22.50	0.66
4.75	0.88	10.75	3.41	16.75	0.99	22.75	0.66
5.00	0.88	11.00	5.28	17.00	0.99	23.00	0.66
5.25	0.88	11.25	5.28	17.25	0.99	23.25	0.66
5.50	0.88	11.50	22.88	17.50	0.99	23.50	0.66
5.75	0.88	11.75	60.72	17.75	0.99	23.75	0.66

CALIB							
NASHYD	(0201)	Area	(ha)= 0.81	Curve Number	(CN)= 74.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 8.00	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.23				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.55	6.083	1.10	12.083	7.93	18.08	0.99
0.167	0.55	6.167	1.10	12.167	7.92	18.17	0.99
0.250	0.55	6.250	1.10	12.250	7.92	18.25	0.99
0.333	0.55	6.333	1.10	12.333	7.92	18.33	0.99
0.417	0.55	6.417	1.10	12.417	7.92	18.42	0.99
0.500	0.55	6.500	1.10	12.500	7.92	18.50	0.99
0.583	0.55	6.583	1.10	12.583	4.07	18.58	0.99
0.667	0.55	6.667	1.10	12.667	4.07	18.67	0.99
0.750	0.55	6.750	1.10	12.750	4.07	18.75	0.99
0.833	0.55	6.833	1.10	12.833	4.07	18.83	0.99
0.917	0.55	6.917	1.10	12.917	4.07	18.92	0.99
1.000	0.55	7.000	1.10	13.000	4.07	19.00	0.99
1.083	0.55	7.083	1.10	13.083	0.77	19.08	0.99
1.167	0.55	7.167	1.10	13.167	0.77	19.17	0.99
1.250	0.55	7.250	1.10	13.250	0.77	19.25	0.99
1.333	0.55	7.333	1.10	13.333	0.77	19.33	0.99
1.417	0.55	7.417	1.10	13.417	0.77	19.42	0.99
1.500	0.55	7.500	1.10	13.500	0.77	19.50	0.99
1.583	0.55	7.583	1.10	13.583	4.51	19.58	0.99
1.667	0.55	7.667	1.10	13.667	4.51	19.67	0.99
1.750	0.55	7.750	1.10	13.750	4.51	19.75	0.99
1.833	0.99	7.833	1.10	13.833	4.51	19.83	0.99
1.917	0.99	7.917	1.10	13.917	4.51	19.92	0.99
2.000	0.99	8.000	1.10	14.000	4.51	20.00	0.99
2.083	0.71	8.083	1.49	14.083	1.65	20.08	0.66
2.167	0.71	8.167	1.49	14.167	1.65	20.17	0.66
2.250	0.71	8.250	1.48	14.250	1.65	20.25	0.66
2.333	0.71	8.333	1.49	14.333	1.65	20.33	0.66
2.417	0.71	8.417	1.49	14.417	1.65	20.42	0.66
2.500	0.71	8.500	1.48	14.500	1.65	20.50	0.66
2.583	0.71	8.583	1.49	14.583	1.65	20.58	0.66
2.667	0.71	8.667	1.49	14.667	1.65	20.67	0.66
2.750	0.71	8.750	1.48	14.750	1.65	20.75	0.66
2.833	0.71	8.833	1.49	14.833	1.65	20.83	0.66
2.917	0.71	8.917	1.49	14.917	1.65	20.92	0.66
3.000	0.71	9.000	1.49	15.000	1.65	21.00	0.66
3.083	0.71	9.083	1.76	15.083	1.65	21.08	0.66

3.167	0.71	9.167	1.76	15.167	1.65	21.17	0.66
3.250	0.71	9.250	1.76	15.250	1.65	21.25	0.66
3.333	0.71	9.333	1.76	15.333	1.65	21.33	0.66
3.417	0.71	9.417	1.76	15.417	1.65	21.42	0.66
3.500	0.71	9.500	1.76	15.500	1.65	21.50	0.66
3.583	0.71	9.583	1.98	15.583	1.65	21.58	0.66
3.667	0.71	9.667	1.98	15.667	1.65	21.67	0.66
3.750	0.71	9.750	1.98	15.750	1.65	21.75	0.66
3.833	0.71	9.833	1.98	15.833	1.65	21.83	0.66
3.917	0.71	9.917	1.98	15.917	1.65	21.92	0.66
4.000	0.71	10.000	1.98	16.000	1.65	22.00	0.66
4.083	0.88	10.083	2.53	16.083	0.99	22.08	0.66
4.167	0.88	10.167	2.53	16.167	0.99	22.17	0.66
4.250	0.88	10.250	2.53	16.250	0.99	22.25	0.66
4.333	0.88	10.333	2.53	16.333	0.99	22.33	0.66
4.417	0.88	10.417	2.53	16.417	0.99	22.42	0.66
4.500	0.88	10.500	2.53	16.500	0.99	22.50	0.66
4.583	0.88	10.583	3.41	16.583	0.99	22.58	0.66
4.667	0.88	10.667	3.41	16.667	0.99	22.67	0.66
4.750	0.88	10.750	3.41	16.750	0.99	22.75	0.66
4.833	0.88	10.833	3.41	16.833	0.99	22.83	0.66
4.917	0.88	10.917	3.41	16.917	0.99	22.92	0.66
5.000	0.88	11.000	3.41	17.000	0.99	23.00	0.66
5.083	0.88	11.083	5.28	17.083	0.99	23.08	0.66
5.167	0.88	11.167	5.28	17.167	0.99	23.17	0.66
5.250	0.88	11.250	5.28	17.250	0.99	23.25	0.66
5.333	0.88	11.333	5.28	17.333	0.99	23.33	0.66
5.417	0.88	11.417	5.28	17.417	0.99	23.42	0.66
5.500	0.88	11.500	5.28	17.500	0.99	23.50	0.66
5.583	0.88	11.583	22.88	17.583	0.99	23.58	0.66
5.667	0.88	11.667	22.88	17.667	0.99	23.67	0.66
5.750	0.88	11.750	22.88	17.750	0.99	23.75	0.66
5.833	0.88	11.833	60.72	17.833	0.99	23.83	0.66
5.917	0.88	11.917	60.72	17.917	0.99	23.92	0.66
6.000	0.88	12.000	60.72	18.000	0.99	24.00	0.66

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.029 (i)
TIME TO PEAK (hrs)= 12.083
RUNOFF VOLUME (mm)= 16.195
TOTAL RAINFALL (mm)= 55.000
RUNOFF COEFFICIENT = 0.294

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB			
NASHYD (0202)		Area (ha)= 0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min		Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
		U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.55	6.083	1.10	12.083	7.93	18.08	0.99
0.167	0.55	6.167	1.10	12.167	7.92	18.17	0.99
0.250	0.55	6.250	1.10	12.250	7.92	18.25	0.99
0.333	0.55	6.333	1.10	12.333	7.92	18.33	0.99
0.417	0.55	6.417	1.10	12.417	7.92	18.42	0.99

0.500	0.55	6.500	1.10	12.500	7.92	18.50	0.99
0.583	0.55	6.583	1.10	12.583	4.07	18.58	0.99
0.667	0.55	6.667	1.10	12.667	4.07	18.67	0.99
0.750	0.55	6.750	1.10	12.750	4.07	18.75	0.99
0.833	0.55	6.833	1.10	12.833	4.07	18.83	0.99
0.917	0.55	6.917	1.10	12.917	4.07	18.92	0.99
1.000	0.55	7.000	1.10	13.000	4.07	19.00	0.99
1.083	0.55	7.083	1.10	13.083	0.77	19.08	0.99
1.167	0.55	7.167	1.10	13.167	0.77	19.17	0.99
1.250	0.55	7.250	1.10	13.250	0.77	19.25	0.99
1.333	0.55	7.333	1.10	13.333	0.77	19.33	0.99
1.417	0.55	7.417	1.10	13.417	0.77	19.42	0.99
1.500	0.55	7.500	1.10	13.500	0.77	19.50	0.99
1.583	0.55	7.583	1.10	13.583	4.51	19.58	0.99
1.667	0.55	7.667	1.10	13.667	4.51	19.67	0.99
1.750	0.55	7.750	1.10	13.750	4.51	19.75	0.99
1.833	0.99	7.833	1.10	13.833	4.51	19.83	0.99
1.917	0.99	7.917	1.10	13.917	4.51	19.92	0.99
2.000	0.99	8.000	1.10	14.000	4.51	20.00	0.99
2.083	0.71	8.083	1.49	14.083	1.65	20.08	0.66
2.167	0.71	8.167	1.49	14.167	1.65	20.17	0.66
2.250	0.71	8.250	1.48	14.250	1.65	20.25	0.66
2.333	0.71	8.333	1.49	14.333	1.65	20.33	0.66
2.417	0.71	8.417	1.49	14.417	1.65	20.42	0.66
2.500	0.71	8.500	1.48	14.500	1.65	20.50	0.66
2.583	0.71	8.583	1.49	14.583	1.65	20.58	0.66
2.667	0.71	8.667	1.49	14.667	1.65	20.67	0.66
2.750	0.71	8.750	1.48	14.750	1.65	20.75	0.66
2.833	0.71	8.833	1.49	14.833	1.65	20.83	0.66
2.917	0.71	8.917	1.49	14.917	1.65	20.92	0.66
3.000	0.71	9.000	1.49	15.000	1.65	21.00	0.66
3.083	0.71	9.083	1.76	15.083	1.65	21.08	0.66
3.167	0.71	9.167	1.76	15.167	1.65	21.17	0.66
3.250	0.71	9.250	1.76	15.250	1.65	21.25	0.66
3.333	0.71	9.333	1.76	15.333	1.65	21.33	0.66
3.417	0.71	9.417	1.76	15.417	1.65	21.42	0.66
3.500	0.71	9.500	1.76	15.500	1.65	21.50	0.66
3.583	0.71	9.583	1.98	15.583	1.65	21.58	0.66
3.667	0.71	9.667	1.98	15.667	1.65	21.67	0.66
3.750	0.71	9.750	1.98	15.750	1.65	21.75	0.66
3.833	0.71	9.833	1.98	15.833	1.65	21.83	0.66
3.917	0.71	9.917	1.98	15.917	1.65	21.92	0.66
4.000	0.71	10.000	1.98	16.000	1.65	22.00	0.66
4.083	0.88	10.083	2.53	16.083	0.99	22.08	0.66
4.167	0.88	10.167	2.53	16.167	0.99	22.17	0.66
4.250	0.88	10.250	2.53	16.250	0.99	22.25	0.66
4.333	0.88	10.333	2.53	16.333	0.99	22.33	0.66
4.417	0.88	10.417	2.53	16.417	0.99	22.42	0.66
4.500	0.88	10.500	2.53	16.500	0.99	22.50	0.66
4.583	0.88	10.583	3.41	16.583	0.99	22.58	0.66
4.667	0.88	10.667	3.41	16.667	0.99	22.67	0.66
4.750	0.88	10.750	3.41	16.750	0.99	22.75	0.66
4.833	0.88	10.833	3.41	16.833	0.99	22.83	0.66
4.917	0.88	10.917	3.41	16.917	0.99	22.92	0.66
5.000	0.88	11.000	3.41	17.000	0.99	23.00	0.66
5.083	0.88	11.083	5.28	17.083	0.99	23.08	0.66
5.167	0.88	11.167	5.28	17.167	0.99	23.17	0.66
5.250	0.88	11.250	5.28	17.250	0.99	23.25	0.66
5.333	0.88	11.333	5.28	17.333	0.99	23.33	0.66
5.417	0.88	11.417	5.28	17.417	0.99	23.42	0.66
5.500	0.88	11.500	5.28	17.500	0.99	23.50	0.66
5.583	0.88	11.583	22.88	17.583	0.99	23.58	0.66
5.667	0.88	11.667	22.88	17.667	0.99	23.67	0.66
5.750	0.88	11.750	22.88	17.750	0.99	23.75	0.66

5.833	0.88	11.833	60.72	17.833	0.99	23.83	0.66
5.917	0.88	11.917	60.72	17.917	0.99	23.92	0.66
6.000	0.88	12.000	60.72	18.000	0.99	24.00	0.66

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.009 (i)
 TIME TO PEAK (hrs)= 12.083
 RUNOFF VOLUME (mm)= 16.023
 TOTAL RAINFALL (mm)= 55.000
 RUNOFF COEFFICIENT = 0.291

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min

Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.55	6.083	1.10	12.083	7.93	18.08	0.99
0.167	0.55	6.167	1.10	12.167	7.92	18.17	0.99
0.250	0.55	6.250	1.10	12.250	7.92	18.25	0.99
0.333	0.55	6.333	1.10	12.333	7.92	18.33	0.99
0.417	0.55	6.417	1.10	12.417	7.92	18.42	0.99
0.500	0.55	6.500	1.10	12.500	7.92	18.50	0.99
0.583	0.55	6.583	1.10	12.583	4.07	18.58	0.99
0.667	0.55	6.667	1.10	12.667	4.07	18.67	0.99
0.750	0.55	6.750	1.10	12.750	4.07	18.75	0.99
0.833	0.55	6.833	1.10	12.833	4.07	18.83	0.99
0.917	0.55	6.917	1.10	12.917	4.07	18.92	0.99
1.000	0.55	7.000	1.10	13.000	4.07	19.00	0.99
1.083	0.55	7.083	1.10	13.083	0.77	19.08	0.99
1.167	0.55	7.167	1.10	13.167	0.77	19.17	0.99
1.250	0.55	7.250	1.10	13.250	0.77	19.25	0.99
1.333	0.55	7.333	1.10	13.333	0.77	19.33	0.99
1.417	0.55	7.417	1.10	13.417	0.77	19.42	0.99
1.500	0.55	7.500	1.10	13.500	0.77	19.50	0.99
1.583	0.55	7.583	1.10	13.583	4.51	19.58	0.99
1.667	0.55	7.667	1.10	13.667	4.51	19.67	0.99
1.750	0.55	7.750	1.10	13.750	4.51	19.75	0.99
1.833	0.99	7.833	1.10	13.833	4.51	19.83	0.99
1.917	0.99	7.917	1.10	13.917	4.51	19.92	0.99
2.000	0.99	8.000	1.10	14.000	4.51	20.00	0.99
2.083	0.71	8.083	1.49	14.083	1.65	20.08	0.66
2.167	0.71	8.167	1.49	14.167	1.65	20.17	0.66
2.250	0.71	8.250	1.48	14.250	1.65	20.25	0.66
2.333	0.71	8.333	1.49	14.333	1.65	20.33	0.66
2.417	0.71	8.417	1.49	14.417	1.65	20.42	0.66
2.500	0.71	8.500	1.48	14.500	1.65	20.50	0.66
2.583	0.71	8.583	1.49	14.583	1.65	20.58	0.66

2.667	0.71	8.667	1.49	14.667	1.65	20.67	0.66
2.750	0.71	8.750	1.48	14.750	1.65	20.75	0.66
2.833	0.71	8.833	1.49	14.833	1.65	20.83	0.66
2.917	0.71	8.917	1.49	14.917	1.65	20.92	0.66
3.000	0.71	9.000	1.49	15.000	1.65	21.00	0.66
3.083	0.71	9.083	1.76	15.083	1.65	21.08	0.66
3.167	0.71	9.167	1.76	15.167	1.65	21.17	0.66
3.250	0.71	9.250	1.76	15.250	1.65	21.25	0.66
3.333	0.71	9.333	1.76	15.333	1.65	21.33	0.66
3.417	0.71	9.417	1.76	15.417	1.65	21.42	0.66
3.500	0.71	9.500	1.76	15.500	1.65	21.50	0.66
3.583	0.71	9.583	1.98	15.583	1.65	21.58	0.66
3.667	0.71	9.667	1.98	15.667	1.65	21.67	0.66
3.750	0.71	9.750	1.98	15.750	1.65	21.75	0.66
3.833	0.71	9.833	1.98	15.833	1.65	21.83	0.66
3.917	0.71	9.917	1.98	15.917	1.65	21.92	0.66
4.000	0.71	10.000	1.98	16.000	1.65	22.00	0.66
4.083	0.88	10.083	2.53	16.083	0.99	22.08	0.66
4.167	0.88	10.167	2.53	16.167	0.99	22.17	0.66
4.250	0.88	10.250	2.53	16.250	0.99	22.25	0.66
4.333	0.88	10.333	2.53	16.333	0.99	22.33	0.66
4.417	0.88	10.417	2.53	16.417	0.99	22.42	0.66
4.500	0.88	10.500	2.53	16.500	0.99	22.50	0.66
4.583	0.88	10.583	3.41	16.583	0.99	22.58	0.66
4.667	0.88	10.667	3.41	16.667	0.99	22.67	0.66
4.750	0.88	10.750	3.41	16.750	0.99	22.75	0.66
4.833	0.88	10.833	3.41	16.833	0.99	22.83	0.66
4.917	0.88	10.917	3.41	16.917	0.99	22.92	0.66
5.000	0.88	11.000	3.41	17.000	0.99	23.00	0.66
5.083	0.88	11.083	5.28	17.083	0.99	23.08	0.66
5.167	0.88	11.167	5.28	17.167	0.99	23.17	0.66
5.250	0.88	11.250	5.28	17.250	0.99	23.25	0.66
5.333	0.88	11.333	5.28	17.333	0.99	23.33	0.66
5.417	0.88	11.417	5.28	17.417	0.99	23.42	0.66
5.500	0.88	11.500	5.28	17.500	0.99	23.50	0.66
5.583	0.88	11.583	22.88	17.583	0.99	23.58	0.66
5.667	0.88	11.667	22.88	17.667	0.99	23.67	0.66
5.750	0.88	11.750	22.88	17.750	0.99	23.75	0.66
5.833	0.88	11.833	60.72	17.833	0.99	23.83	0.66
5.917	0.88	11.917	60.72	17.917	0.99	23.92	0.66
6.000	0.88	12.000	60.72	18.000	0.99	24.00	0.66

Max.Eff.Inten.(mm/hr)=	60.72	20.62
over (min)	5.00	20.00
Storage Coeff. (min)=	5.46 (ii)	15.22 (ii)
Unit Hyd. Tpeak (min)=	5.00	20.00
Unit Hyd. peak (cms)=	0.20	0.07

TOTALS

PEAK FLOW (cms)=	0.33	0.23	0.490 (iii)
TIME TO PEAK (hrs)=	12.00	12.17	12.00
RUNOFF VOLUME (mm)=	54.00	15.23	23.37
TOTAL RAINFALL (mm)=	55.00	55.00	55.00
RUNOFF COEFFICIENT =	0.98	0.28	0.42

- (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 69.0 Ia = Dep. Storage (Above)
- (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
- (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

IN= 2---> OUT= 1
DT= 5.0 min

OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
0.0000	0.0000	0.7200	0.1600
0.0500	0.0500	0.7300	0.1800
0.1500	0.0700	0.8600	0.1850
0.3000	0.0900	0.9500	0.1900
0.4200	0.1200	0.9900	0.1950
0.5500	0.1300	1.1900	0.2300
0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	0.490	12.00	23.37
OUTFLOW: ID= 1 (0300)	9.680	0.199	12.42	23.35

PEAK FLOW REDUCTION [Qout/Qin](%)= 40.65
TIME SHIFT OF PEAK FLOW (min)= 25.00
MAXIMUM STORAGE USED (ha.m.)= 0.0766

ADD HYD (0400)
1 + 2 = 3

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.029	12.08	16.20
+ ID2= 2 (0202):	0.24	0.009	12.08	16.02
=====				
ID = 3 (0400):	1.05	0.038	12.08	16.16

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

ADD HYD (0400)
3 + 2 = 1

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.038	12.08	16.16
+ ID2= 2 (0300):	9.68	0.199	12.42	23.35
=====				
ID = 1 (0400):	10.73	0.219	12.33	22.64

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\d797fcae-28d3-4b09-9809-be9946203867\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\d797fcae-28d3-4b09-9809-be9946203867\scen

DATE: 02-23-2024

TIME: 08:29:46

USER:

COMMENTS: _____

** SIMULATION : Run 08 **

READ STORM

Ptotal= 76.00 mm

Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\689870c2
Comments: 24hr 5year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.76	6.00	1.52	12.00	10.94	18.00	1.37
0.25	0.76	6.25	1.52	12.25	10.94	18.25	1.37
0.50	0.76	6.50	1.52	12.50	5.62	18.50	1.37
0.75	0.76	6.75	1.52	12.75	5.62	18.75	1.37
1.00	0.76	7.00	1.52	13.00	1.06	19.00	1.37
1.25	0.76	7.25	1.52	13.25	1.06	19.25	1.37
1.50	0.76	7.50	1.52	13.50	6.23	19.50	1.37
1.75	1.37	7.75	1.52	13.75	6.23	19.75	1.37
2.00	0.99	8.00	2.05	14.00	2.28	20.00	0.91
2.25	0.99	8.25	2.05	14.25	2.28	20.25	0.91
2.50	0.99	8.50	2.05	14.50	2.28	20.50	0.91
2.75	0.99	8.75	2.05	14.75	2.28	20.75	0.91

3.00	0.99	9.00	2.43	15.00	2.28	21.00	0.91
3.25	0.99	9.25	2.43	15.25	2.28	21.25	0.91
3.50	0.99	9.50	2.74	15.50	2.28	21.50	0.91
3.75	0.99	9.75	2.74	15.75	2.28	21.75	0.91
4.00	1.22	10.00	3.50	16.00	1.37	22.00	0.91
4.25	1.22	10.25	3.50	16.25	1.37	22.25	0.91
4.50	1.22	10.50	4.71	16.50	1.37	22.50	0.91
4.75	1.22	10.75	4.71	16.75	1.37	22.75	0.91
5.00	1.22	11.00	7.30	17.00	1.37	23.00	0.91
5.25	1.22	11.25	7.30	17.25	1.37	23.25	0.91
5.50	1.22	11.50	31.62	17.50	1.37	23.50	0.91
5.75	1.22	11.75	83.90	17.75	1.37	23.75	0.91

CALIB
 NASHYD (0201)
 ID= 1 DT= 5.0 min

Area (ha)= 0.81 Curve Number (CN)= 74.0
 Ia (mm)= 8.00 # of Linear Res.(N)= 3.00
 U.H. Tp(hrs)= 0.23

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.76	6.083	1.52	12.083	10.95	18.08	1.37
0.167	0.76	6.167	1.52	12.167	10.94	18.17	1.37
0.250	0.76	6.250	1.52	12.250	10.94	18.25	1.37
0.333	0.76	6.333	1.52	12.333	10.94	18.33	1.37
0.417	0.76	6.417	1.52	12.417	10.94	18.42	1.37
0.500	0.76	6.500	1.52	12.500	10.94	18.50	1.37
0.583	0.76	6.583	1.52	12.583	5.62	18.58	1.37
0.667	0.76	6.667	1.52	12.667	5.62	18.67	1.37
0.750	0.76	6.750	1.52	12.750	5.62	18.75	1.37
0.833	0.76	6.833	1.52	12.833	5.62	18.83	1.37
0.917	0.76	6.917	1.52	12.917	5.62	18.92	1.37
1.000	0.76	7.000	1.52	13.000	5.62	19.00	1.37
1.083	0.76	7.083	1.52	13.083	1.06	19.08	1.37
1.167	0.76	7.167	1.52	13.167	1.06	19.17	1.37
1.250	0.76	7.250	1.52	13.250	1.06	19.25	1.37
1.333	0.76	7.333	1.52	13.333	1.06	19.33	1.37
1.417	0.76	7.417	1.52	13.417	1.06	19.42	1.37
1.500	0.76	7.500	1.52	13.500	1.06	19.50	1.37
1.583	0.76	7.583	1.52	13.583	6.23	19.58	1.37
1.667	0.76	7.667	1.52	13.667	6.23	19.67	1.37
1.750	0.76	7.750	1.52	13.750	6.23	19.75	1.37
1.833	1.37	7.833	1.52	13.833	6.23	19.83	1.37
1.917	1.37	7.917	1.52	13.917	6.23	19.92	1.37
2.000	1.37	8.000	1.52	14.000	6.23	20.00	1.37
2.083	0.99	8.083	2.05	14.083	2.28	20.08	0.91
2.167	0.99	8.167	2.05	14.167	2.28	20.17	0.91
2.250	0.99	8.250	2.05	14.250	2.28	20.25	0.91
2.333	0.99	8.333	2.05	14.333	2.28	20.33	0.91
2.417	0.99	8.417	2.05	14.417	2.28	20.42	0.91
2.500	0.99	8.500	2.05	14.500	2.28	20.50	0.91
2.583	0.99	8.583	2.05	14.583	2.28	20.58	0.91
2.667	0.99	8.667	2.05	14.667	2.28	20.67	0.91
2.750	0.99	8.750	2.05	14.750	2.28	20.75	0.91
2.833	0.99	8.833	2.05	14.833	2.28	20.83	0.91
2.917	0.99	8.917	2.05	14.917	2.28	20.92	0.91
3.000	0.99	9.000	2.05	15.000	2.28	21.00	0.91
3.083	0.99	9.083	2.43	15.083	2.28	21.08	0.91

3.167	0.99	9.167	2.43	15.167	2.28	21.17	0.91
3.250	0.99	9.250	2.43	15.250	2.28	21.25	0.91
3.333	0.99	9.333	2.43	15.333	2.28	21.33	0.91
3.417	0.99	9.417	2.43	15.417	2.28	21.42	0.91
3.500	0.99	9.500	2.43	15.500	2.28	21.50	0.91
3.583	0.99	9.583	2.74	15.583	2.28	21.58	0.91
3.667	0.99	9.667	2.74	15.667	2.28	21.67	0.91
3.750	0.99	9.750	2.74	15.750	2.28	21.75	0.91
3.833	0.99	9.833	2.74	15.833	2.28	21.83	0.91
3.917	0.99	9.917	2.74	15.917	2.28	21.92	0.91
4.000	0.99	10.000	2.74	16.000	2.28	22.00	0.91
4.083	1.22	10.083	3.50	16.083	1.37	22.08	0.91
4.167	1.22	10.167	3.50	16.167	1.37	22.17	0.91
4.250	1.22	10.250	3.50	16.250	1.37	22.25	0.91
4.333	1.22	10.333	3.50	16.333	1.37	22.33	0.91
4.417	1.22	10.417	3.50	16.417	1.37	22.42	0.91
4.500	1.22	10.500	3.50	16.500	1.37	22.50	0.91
4.583	1.22	10.583	4.71	16.583	1.37	22.58	0.91
4.667	1.22	10.667	4.71	16.667	1.37	22.67	0.91
4.750	1.22	10.750	4.71	16.750	1.37	22.75	0.91
4.833	1.22	10.833	4.71	16.833	1.37	22.83	0.91
4.917	1.22	10.917	4.71	16.917	1.37	22.92	0.91
5.000	1.22	11.000	4.71	17.000	1.37	23.00	0.91
5.083	1.22	11.083	7.30	17.083	1.37	23.08	0.91
5.167	1.22	11.167	7.30	17.167	1.37	23.17	0.91
5.250	1.22	11.250	7.30	17.250	1.37	23.25	0.91
5.333	1.22	11.333	7.30	17.333	1.37	23.33	0.91
5.417	1.22	11.417	7.30	17.417	1.37	23.42	0.91
5.500	1.22	11.500	7.30	17.500	1.37	23.50	0.91
5.583	1.22	11.583	31.61	17.583	1.37	23.58	0.91
5.667	1.22	11.667	31.62	17.667	1.37	23.67	0.91
5.750	1.22	11.750	31.62	17.750	1.37	23.75	0.91
5.833	1.22	11.833	83.90	17.833	1.37	23.83	0.91
5.917	1.22	11.917	83.90	17.917	1.37	23.92	0.91
6.000	1.22	12.000	83.90	18.000	1.37	24.00	0.91

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.054 (i)
TIME TO PEAK (hrs)= 12.083
RUNOFF VOLUME (mm)= 29.374
TOTAL RAINFALL (mm)= 76.000
RUNOFF COEFFICIENT = 0.386

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB			
NASHYD (0202)			
ID= 1 DT= 5.0 min			
		Area (ha)= 0.24	Curve Number (CN)= 73.0
		Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
		U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.76	6.083	1.52	12.083	10.95	18.08	1.37
0.167	0.76	6.167	1.52	12.167	10.94	18.17	1.37
0.250	0.76	6.250	1.52	12.250	10.94	18.25	1.37
0.333	0.76	6.333	1.52	12.333	10.94	18.33	1.37
0.417	0.76	6.417	1.52	12.417	10.94	18.42	1.37

0.500	0.76	6.500	1.52	12.500	10.94	18.50	1.37
0.583	0.76	6.583	1.52	12.583	5.62	18.58	1.37
0.667	0.76	6.667	1.52	12.667	5.62	18.67	1.37
0.750	0.76	6.750	1.52	12.750	5.62	18.75	1.37
0.833	0.76	6.833	1.52	12.833	5.62	18.83	1.37
0.917	0.76	6.917	1.52	12.917	5.62	18.92	1.37
1.000	0.76	7.000	1.52	13.000	5.62	19.00	1.37
1.083	0.76	7.083	1.52	13.083	1.06	19.08	1.37
1.167	0.76	7.167	1.52	13.167	1.06	19.17	1.37
1.250	0.76	7.250	1.52	13.250	1.06	19.25	1.37
1.333	0.76	7.333	1.52	13.333	1.06	19.33	1.37
1.417	0.76	7.417	1.52	13.417	1.06	19.42	1.37
1.500	0.76	7.500	1.52	13.500	1.06	19.50	1.37
1.583	0.76	7.583	1.52	13.583	6.23	19.58	1.37
1.667	0.76	7.667	1.52	13.667	6.23	19.67	1.37
1.750	0.76	7.750	1.52	13.750	6.23	19.75	1.37
1.833	1.37	7.833	1.52	13.833	6.23	19.83	1.37
1.917	1.37	7.917	1.52	13.917	6.23	19.92	1.37
2.000	1.37	8.000	1.52	14.000	6.23	20.00	1.37
2.083	0.99	8.083	2.05	14.083	2.28	20.08	0.91
2.167	0.99	8.167	2.05	14.167	2.28	20.17	0.91
2.250	0.99	8.250	2.05	14.250	2.28	20.25	0.91
2.333	0.99	8.333	2.05	14.333	2.28	20.33	0.91
2.417	0.99	8.417	2.05	14.417	2.28	20.42	0.91
2.500	0.99	8.500	2.05	14.500	2.28	20.50	0.91
2.583	0.99	8.583	2.05	14.583	2.28	20.58	0.91
2.667	0.99	8.667	2.05	14.667	2.28	20.67	0.91
2.750	0.99	8.750	2.05	14.750	2.28	20.75	0.91
2.833	0.99	8.833	2.05	14.833	2.28	20.83	0.91
2.917	0.99	8.917	2.05	14.917	2.28	20.92	0.91
3.000	0.99	9.000	2.05	15.000	2.28	21.00	0.91
3.083	0.99	9.083	2.43	15.083	2.28	21.08	0.91
3.167	0.99	9.167	2.43	15.167	2.28	21.17	0.91
3.250	0.99	9.250	2.43	15.250	2.28	21.25	0.91
3.333	0.99	9.333	2.43	15.333	2.28	21.33	0.91
3.417	0.99	9.417	2.43	15.417	2.28	21.42	0.91
3.500	0.99	9.500	2.43	15.500	2.28	21.50	0.91
3.583	0.99	9.583	2.74	15.583	2.28	21.58	0.91
3.667	0.99	9.667	2.74	15.667	2.28	21.67	0.91
3.750	0.99	9.750	2.74	15.750	2.28	21.75	0.91
3.833	0.99	9.833	2.74	15.833	2.28	21.83	0.91
3.917	0.99	9.917	2.74	15.917	2.28	21.92	0.91
4.000	0.99	10.000	2.74	16.000	2.28	22.00	0.91
4.083	1.22	10.083	3.50	16.083	1.37	22.08	0.91
4.167	1.22	10.167	3.50	16.167	1.37	22.17	0.91
4.250	1.22	10.250	3.50	16.250	1.37	22.25	0.91
4.333	1.22	10.333	3.50	16.333	1.37	22.33	0.91
4.417	1.22	10.417	3.50	16.417	1.37	22.42	0.91
4.500	1.22	10.500	3.50	16.500	1.37	22.50	0.91
4.583	1.22	10.583	4.71	16.583	1.37	22.58	0.91
4.667	1.22	10.667	4.71	16.667	1.37	22.67	0.91
4.750	1.22	10.750	4.71	16.750	1.37	22.75	0.91
4.833	1.22	10.833	4.71	16.833	1.37	22.83	0.91
4.917	1.22	10.917	4.71	16.917	1.37	22.92	0.91
5.000	1.22	11.000	4.71	17.000	1.37	23.00	0.91
5.083	1.22	11.083	7.30	17.083	1.37	23.08	0.91
5.167	1.22	11.167	7.30	17.167	1.37	23.17	0.91
5.250	1.22	11.250	7.30	17.250	1.37	23.25	0.91
5.333	1.22	11.333	7.30	17.333	1.37	23.33	0.91
5.417	1.22	11.417	7.30	17.417	1.37	23.42	0.91
5.500	1.22	11.500	7.30	17.500	1.37	23.50	0.91
5.583	1.22	11.583	31.61	17.583	1.37	23.58	0.91
5.667	1.22	11.667	31.62	17.667	1.37	23.67	0.91
5.750	1.22	11.750	31.62	17.750	1.37	23.75	0.91

5.833	1.22	11.833	83.90	17.833	1.37	23.83	0.91
5.917	1.22	11.917	83.90	17.917	1.37	23.92	0.91
6.000	1.22	12.000	83.90	18.000	1.37	24.00	0.91

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.017 (i)
 TIME TO PEAK (hrs)= 12.083
 RUNOFF VOLUME (mm)= 28.949
 TOTAL RAINFALL (mm)= 76.000
 RUNOFF COEFFICIENT = 0.381

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min

Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.76	6.083	1.52	12.083	10.95	18.08	1.37
0.167	0.76	6.167	1.52	12.167	10.94	18.17	1.37
0.250	0.76	6.250	1.52	12.250	10.94	18.25	1.37
0.333	0.76	6.333	1.52	12.333	10.94	18.33	1.37
0.417	0.76	6.417	1.52	12.417	10.94	18.42	1.37
0.500	0.76	6.500	1.52	12.500	10.94	18.50	1.37
0.583	0.76	6.583	1.52	12.583	5.62	18.58	1.37
0.667	0.76	6.667	1.52	12.667	5.62	18.67	1.37
0.750	0.76	6.750	1.52	12.750	5.62	18.75	1.37
0.833	0.76	6.833	1.52	12.833	5.62	18.83	1.37
0.917	0.76	6.917	1.52	12.917	5.62	18.92	1.37
1.000	0.76	7.000	1.52	13.000	5.62	19.00	1.37
1.083	0.76	7.083	1.52	13.083	1.06	19.08	1.37
1.167	0.76	7.167	1.52	13.167	1.06	19.17	1.37
1.250	0.76	7.250	1.52	13.250	1.06	19.25	1.37
1.333	0.76	7.333	1.52	13.333	1.06	19.33	1.37
1.417	0.76	7.417	1.52	13.417	1.06	19.42	1.37
1.500	0.76	7.500	1.52	13.500	1.06	19.50	1.37
1.583	0.76	7.583	1.52	13.583	6.23	19.58	1.37
1.667	0.76	7.667	1.52	13.667	6.23	19.67	1.37
1.750	0.76	7.750	1.52	13.750	6.23	19.75	1.37
1.833	1.37	7.833	1.52	13.833	6.23	19.83	1.37
1.917	1.37	7.917	1.52	13.917	6.23	19.92	1.37
2.000	1.37	8.000	1.52	14.000	6.23	20.00	1.37
2.083	0.99	8.083	2.05	14.083	2.28	20.08	0.91
2.167	0.99	8.167	2.05	14.167	2.28	20.17	0.91
2.250	0.99	8.250	2.05	14.250	2.28	20.25	0.91
2.333	0.99	8.333	2.05	14.333	2.28	20.33	0.91
2.417	0.99	8.417	2.05	14.417	2.28	20.42	0.91
2.500	0.99	8.500	2.05	14.500	2.28	20.50	0.91
2.583	0.99	8.583	2.05	14.583	2.28	20.58	0.91

2.667	0.99	8.667	2.05	14.667	2.28	20.67	0.91
2.750	0.99	8.750	2.05	14.750	2.28	20.75	0.91
2.833	0.99	8.833	2.05	14.833	2.28	20.83	0.91
2.917	0.99	8.917	2.05	14.917	2.28	20.92	0.91
3.000	0.99	9.000	2.05	15.000	2.28	21.00	0.91
3.083	0.99	9.083	2.43	15.083	2.28	21.08	0.91
3.167	0.99	9.167	2.43	15.167	2.28	21.17	0.91
3.250	0.99	9.250	2.43	15.250	2.28	21.25	0.91
3.333	0.99	9.333	2.43	15.333	2.28	21.33	0.91
3.417	0.99	9.417	2.43	15.417	2.28	21.42	0.91
3.500	0.99	9.500	2.43	15.500	2.28	21.50	0.91
3.583	0.99	9.583	2.74	15.583	2.28	21.58	0.91
3.667	0.99	9.667	2.74	15.667	2.28	21.67	0.91
3.750	0.99	9.750	2.74	15.750	2.28	21.75	0.91
3.833	0.99	9.833	2.74	15.833	2.28	21.83	0.91
3.917	0.99	9.917	2.74	15.917	2.28	21.92	0.91
4.000	0.99	10.000	2.74	16.000	2.28	22.00	0.91
4.083	1.22	10.083	3.50	16.083	1.37	22.08	0.91
4.167	1.22	10.167	3.50	16.167	1.37	22.17	0.91
4.250	1.22	10.250	3.50	16.250	1.37	22.25	0.91
4.333	1.22	10.333	3.50	16.333	1.37	22.33	0.91
4.417	1.22	10.417	3.50	16.417	1.37	22.42	0.91
4.500	1.22	10.500	3.50	16.500	1.37	22.50	0.91
4.583	1.22	10.583	4.71	16.583	1.37	22.58	0.91
4.667	1.22	10.667	4.71	16.667	1.37	22.67	0.91
4.750	1.22	10.750	4.71	16.750	1.37	22.75	0.91
4.833	1.22	10.833	4.71	16.833	1.37	22.83	0.91
4.917	1.22	10.917	4.71	16.917	1.37	22.92	0.91
5.000	1.22	11.000	4.71	17.000	1.37	23.00	0.91
5.083	1.22	11.083	7.30	17.083	1.37	23.08	0.91
5.167	1.22	11.167	7.30	17.167	1.37	23.17	0.91
5.250	1.22	11.250	7.30	17.250	1.37	23.25	0.91
5.333	1.22	11.333	7.30	17.333	1.37	23.33	0.91
5.417	1.22	11.417	7.30	17.417	1.37	23.42	0.91
5.500	1.22	11.500	7.30	17.500	1.37	23.50	0.91
5.583	1.22	11.583	31.61	17.583	1.37	23.58	0.91
5.667	1.22	11.667	31.62	17.667	1.37	23.67	0.91
5.750	1.22	11.750	31.62	17.750	1.37	23.75	0.91
5.833	1.22	11.833	83.90	17.833	1.37	23.83	0.91
5.917	1.22	11.917	83.90	17.917	1.37	23.92	0.91
6.000	1.22	12.000	83.90	18.000	1.37	24.00	0.91

Max.Eff.Inten.(mm/hr)=	83.90	36.83
over (min)	5.00	15.00
Storage Coeff. (min)=	4.79 (ii)	12.54 (ii)
Unit Hyd. Tpeak (min)=	5.00	15.00
Unit Hyd. peak (cms)=	0.22	0.08

TOTALS

PEAK FLOW (cms)=	0.46	0.48	0.880 (iii)
TIME TO PEAK (hrs)=	12.00	12.08	12.00
RUNOFF VOLUME (mm)=	75.00	27.23	37.26
TOTAL RAINFALL (mm)=	76.00	76.00	76.00
RUNOFF COEFFICIENT =	0.99	0.36	0.49

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

- (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 69.0 Ia = Dep. Storage (Above)
- (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
- (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

```

| RESERVOIR( 0300) |
| IN= 2---> OUT= 1 |
| DT= 5.0 min      |
|-----|

```

OVERFLOW IS OFF

OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
0.0000	0.0000	0.7200	0.1600
0.0500	0.0500	0.7300	0.1800
0.1500	0.0700	0.8600	0.1850
0.3000	0.0900	0.9500	0.1900
0.4200	0.1200	0.9900	0.1950
0.5500	0.1300	1.1900	0.2300
0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	0.880	12.00	37.26
OUTFLOW: ID= 1 (0300)	9.680	0.386	12.25	37.24

PEAK FLOW REDUCTION [Qout/Qin](%)= 43.86
 TIME SHIFT OF PEAK FLOW (min)= 15.00
 MAXIMUM STORAGE USED (ha.m.)= 0.1120

```

|-----|
| ADD HYD ( 0400) |
| 1 + 2 = 3       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.054	12.08	29.37
+ ID2= 2 (0202):	0.24	0.017	12.08	28.95
=====				
ID = 3 (0400):	1.05	0.071	12.08	29.28

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

```

|-----|
| ADD HYD ( 0400) |
| 3 + 2 = 1       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.071	12.08	29.28
+ ID2= 2 (0300):	9.68	0.386	12.25	37.24
=====				
ID = 1 (0400):	10.73	0.440	12.25	36.46

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\7a1dee26-23d9-4218-9e0a-36d5baec56c3\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\7a1dee26-23d9-4218-9e0a-36d5baec56c3\scen

DATE: 02-23-2024

TIME: 08:29:45

USER:

COMMENTS: _____

** SIMULATION : Run 09 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\0d41b358
Ptotal= 89.90 mm	Comments: 24hr 10year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	0.90	6.00	1.80	12.00	12.95	18.00	1.62
0.25	0.90	6.25	1.80	12.25	12.95	18.25	1.62
0.50	0.90	6.50	1.80	12.50	6.65	18.50	1.62
0.75	0.90	6.75	1.80	12.75	6.65	18.75	1.62
1.00	0.90	7.00	1.80	13.00	1.26	19.00	1.62
1.25	0.90	7.25	1.80	13.25	1.26	19.25	1.62
1.50	0.90	7.50	1.80	13.50	7.37	19.50	1.62
1.75	1.62	7.75	1.80	13.75	7.37	19.75	1.62
2.00	1.17	8.00	2.43	14.00	2.70	20.00	1.08
2.25	1.17	8.25	2.43	14.25	2.70	20.25	1.08
2.50	1.17	8.50	2.43	14.50	2.70	20.50	1.08
2.75	1.17	8.75	2.43	14.75	2.70	20.75	1.08

3.00	1.17	9.00	2.88	15.00	2.70	21.00	1.08
3.25	1.17	9.25	2.88	15.25	2.70	21.25	1.08
3.50	1.17	9.50	3.24	15.50	2.70	21.50	1.08
3.75	1.17	9.75	3.24	15.75	2.70	21.75	1.08
4.00	1.44	10.00	4.14	16.00	1.62	22.00	1.08
4.25	1.44	10.25	4.14	16.25	1.62	22.25	1.08
4.50	1.44	10.50	5.57	16.50	1.62	22.50	1.08
4.75	1.44	10.75	5.57	16.75	1.62	22.75	1.08
5.00	1.44	11.00	8.63	17.00	1.62	23.00	1.08
5.25	1.44	11.25	8.63	17.25	1.62	23.25	1.08
5.50	1.44	11.50	37.40	17.50	1.62	23.50	1.08
5.75	1.44	11.75	99.25	17.75	1.62	23.75	1.08

CALIB							
NASHYD	(0201)	Area	(ha)= 0.81	Curve Number	(CN)= 74.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 8.00	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.23				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.90	6.083	1.80	12.083	12.96	18.08	1.62
0.167	0.90	6.167	1.80	12.167	12.95	18.17	1.62
0.250	0.90	6.250	1.80	12.250	12.95	18.25	1.62
0.333	0.90	6.333	1.80	12.333	12.95	18.33	1.62
0.417	0.90	6.417	1.80	12.417	12.95	18.42	1.62
0.500	0.90	6.500	1.80	12.500	12.95	18.50	1.62
0.583	0.90	6.583	1.80	12.583	6.65	18.58	1.62
0.667	0.90	6.667	1.80	12.667	6.65	18.67	1.62
0.750	0.90	6.750	1.80	12.750	6.65	18.75	1.62
0.833	0.90	6.833	1.80	12.833	6.65	18.83	1.62
0.917	0.90	6.917	1.80	12.917	6.65	18.92	1.62
1.000	0.90	7.000	1.80	13.000	6.65	19.00	1.62
1.083	0.90	7.083	1.80	13.083	1.26	19.08	1.62
1.167	0.90	7.167	1.80	13.167	1.26	19.17	1.62
1.250	0.90	7.250	1.80	13.250	1.26	19.25	1.62
1.333	0.90	7.333	1.80	13.333	1.26	19.33	1.62
1.417	0.90	7.417	1.80	13.417	1.26	19.42	1.62
1.500	0.90	7.500	1.80	13.500	1.26	19.50	1.62
1.583	0.90	7.583	1.80	13.583	7.37	19.58	1.62
1.667	0.90	7.667	1.80	13.667	7.37	19.67	1.62
1.750	0.90	7.750	1.80	13.750	7.37	19.75	1.62
1.833	1.62	7.833	1.80	13.833	7.37	19.83	1.62
1.917	1.62	7.917	1.80	13.917	7.37	19.92	1.62
2.000	1.62	8.000	1.80	14.000	7.37	20.00	1.62
2.083	1.17	8.083	2.43	14.083	2.70	20.08	1.08
2.167	1.17	8.167	2.43	14.167	2.70	20.17	1.08
2.250	1.17	8.250	2.43	14.250	2.70	20.25	1.08
2.333	1.17	8.333	2.43	14.333	2.70	20.33	1.08
2.417	1.17	8.417	2.43	14.417	2.70	20.42	1.08
2.500	1.17	8.500	2.43	14.500	2.70	20.50	1.08
2.583	1.17	8.583	2.43	14.583	2.70	20.58	1.08
2.667	1.17	8.667	2.43	14.667	2.70	20.67	1.08
2.750	1.17	8.750	2.43	14.750	2.70	20.75	1.08
2.833	1.17	8.833	2.43	14.833	2.70	20.83	1.08
2.917	1.17	8.917	2.43	14.917	2.70	20.92	1.08
3.000	1.17	9.000	2.43	15.000	2.70	21.00	1.08
3.083	1.17	9.083	2.88	15.083	2.70	21.08	1.08

3.167	1.17	9.167	2.88	15.167	2.70	21.17	1.08
3.250	1.17	9.250	2.88	15.250	2.70	21.25	1.08
3.333	1.17	9.333	2.88	15.333	2.70	21.33	1.08
3.417	1.17	9.417	2.88	15.417	2.70	21.42	1.08
3.500	1.17	9.500	2.88	15.500	2.70	21.50	1.08
3.583	1.17	9.583	3.24	15.583	2.70	21.58	1.08
3.667	1.17	9.667	3.24	15.667	2.70	21.67	1.08
3.750	1.17	9.750	3.24	15.750	2.70	21.75	1.08
3.833	1.17	9.833	3.24	15.833	2.70	21.83	1.08
3.917	1.17	9.917	3.24	15.917	2.70	21.92	1.08
4.000	1.17	10.000	3.24	16.000	2.70	22.00	1.08
4.083	1.44	10.083	4.14	16.083	1.62	22.08	1.08
4.167	1.44	10.167	4.14	16.167	1.62	22.17	1.08
4.250	1.44	10.250	4.14	16.250	1.62	22.25	1.08
4.333	1.44	10.333	4.14	16.333	1.62	22.33	1.08
4.417	1.44	10.417	4.14	16.417	1.62	22.42	1.08
4.500	1.44	10.500	4.14	16.500	1.62	22.50	1.08
4.583	1.44	10.583	5.57	16.583	1.62	22.58	1.08
4.667	1.44	10.667	5.57	16.667	1.62	22.67	1.08
4.750	1.44	10.750	5.57	16.750	1.62	22.75	1.08
4.833	1.44	10.833	5.57	16.833	1.62	22.83	1.08
4.917	1.44	10.917	5.57	16.917	1.62	22.92	1.08
5.000	1.44	11.000	5.57	17.000	1.62	23.00	1.08
5.083	1.44	11.083	8.63	17.083	1.62	23.08	1.08
5.167	1.44	11.167	8.63	17.167	1.62	23.17	1.08
5.250	1.44	11.250	8.63	17.250	1.62	23.25	1.08
5.333	1.44	11.333	8.63	17.333	1.62	23.33	1.08
5.417	1.44	11.417	8.63	17.417	1.62	23.42	1.08
5.500	1.44	11.500	8.63	17.500	1.62	23.50	1.08
5.583	1.44	11.583	37.40	17.583	1.62	23.58	1.08
5.667	1.44	11.667	37.40	17.667	1.62	23.67	1.08
5.750	1.44	11.750	37.40	17.750	1.62	23.75	1.08
5.833	1.44	11.833	99.24	17.833	1.62	23.83	1.08
5.917	1.44	11.917	99.25	17.917	1.62	23.92	1.08
6.000	1.44	12.000	99.25	18.000	1.62	24.00	1.08

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.073 (i)
TIME TO PEAK (hrs)= 12.083
RUNOFF VOLUME (mm)= 39.149
TOTAL RAINFALL (mm)= 89.900
RUNOFF COEFFICIENT = 0.435

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB			
NASHYD (0202)	Area (ha)=	0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)=	7.30	# of Linear Res.(N)= 3.00
	U.H. Tp(hrs)=	0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.90	6.083	1.80	12.083	12.96	18.08	1.62
0.167	0.90	6.167	1.80	12.167	12.95	18.17	1.62
0.250	0.90	6.250	1.80	12.250	12.95	18.25	1.62
0.333	0.90	6.333	1.80	12.333	12.95	18.33	1.62
0.417	0.90	6.417	1.80	12.417	12.95	18.42	1.62

0.500	0.90	6.500	1.80	12.500	12.95	18.50	1.62
0.583	0.90	6.583	1.80	12.583	6.65	18.58	1.62
0.667	0.90	6.667	1.80	12.667	6.65	18.67	1.62
0.750	0.90	6.750	1.80	12.750	6.65	18.75	1.62
0.833	0.90	6.833	1.80	12.833	6.65	18.83	1.62
0.917	0.90	6.917	1.80	12.917	6.65	18.92	1.62
1.000	0.90	7.000	1.80	13.000	6.65	19.00	1.62
1.083	0.90	7.083	1.80	13.083	1.26	19.08	1.62
1.167	0.90	7.167	1.80	13.167	1.26	19.17	1.62
1.250	0.90	7.250	1.80	13.250	1.26	19.25	1.62
1.333	0.90	7.333	1.80	13.333	1.26	19.33	1.62
1.417	0.90	7.417	1.80	13.417	1.26	19.42	1.62
1.500	0.90	7.500	1.80	13.500	1.26	19.50	1.62
1.583	0.90	7.583	1.80	13.583	7.37	19.58	1.62
1.667	0.90	7.667	1.80	13.667	7.37	19.67	1.62
1.750	0.90	7.750	1.80	13.750	7.37	19.75	1.62
1.833	1.62	7.833	1.80	13.833	7.37	19.83	1.62
1.917	1.62	7.917	1.80	13.917	7.37	19.92	1.62
2.000	1.62	8.000	1.80	14.000	7.37	20.00	1.62
2.083	1.17	8.083	2.43	14.083	2.70	20.08	1.08
2.167	1.17	8.167	2.43	14.167	2.70	20.17	1.08
2.250	1.17	8.250	2.43	14.250	2.70	20.25	1.08
2.333	1.17	8.333	2.43	14.333	2.70	20.33	1.08
2.417	1.17	8.417	2.43	14.417	2.70	20.42	1.08
2.500	1.17	8.500	2.43	14.500	2.70	20.50	1.08
2.583	1.17	8.583	2.43	14.583	2.70	20.58	1.08
2.667	1.17	8.667	2.43	14.667	2.70	20.67	1.08
2.750	1.17	8.750	2.43	14.750	2.70	20.75	1.08
2.833	1.17	8.833	2.43	14.833	2.70	20.83	1.08
2.917	1.17	8.917	2.43	14.917	2.70	20.92	1.08
3.000	1.17	9.000	2.43	15.000	2.70	21.00	1.08
3.083	1.17	9.083	2.88	15.083	2.70	21.08	1.08
3.167	1.17	9.167	2.88	15.167	2.70	21.17	1.08
3.250	1.17	9.250	2.88	15.250	2.70	21.25	1.08
3.333	1.17	9.333	2.88	15.333	2.70	21.33	1.08
3.417	1.17	9.417	2.88	15.417	2.70	21.42	1.08
3.500	1.17	9.500	2.88	15.500	2.70	21.50	1.08
3.583	1.17	9.583	3.24	15.583	2.70	21.58	1.08
3.667	1.17	9.667	3.24	15.667	2.70	21.67	1.08
3.750	1.17	9.750	3.24	15.750	2.70	21.75	1.08
3.833	1.17	9.833	3.24	15.833	2.70	21.83	1.08
3.917	1.17	9.917	3.24	15.917	2.70	21.92	1.08
4.000	1.17	10.000	3.24	16.000	2.70	22.00	1.08
4.083	1.44	10.083	4.14	16.083	1.62	22.08	1.08
4.167	1.44	10.167	4.14	16.167	1.62	22.17	1.08
4.250	1.44	10.250	4.14	16.250	1.62	22.25	1.08
4.333	1.44	10.333	4.14	16.333	1.62	22.33	1.08
4.417	1.44	10.417	4.14	16.417	1.62	22.42	1.08
4.500	1.44	10.500	4.14	16.500	1.62	22.50	1.08
4.583	1.44	10.583	5.57	16.583	1.62	22.58	1.08
4.667	1.44	10.667	5.57	16.667	1.62	22.67	1.08
4.750	1.44	10.750	5.57	16.750	1.62	22.75	1.08
4.833	1.44	10.833	5.57	16.833	1.62	22.83	1.08
4.917	1.44	10.917	5.57	16.917	1.62	22.92	1.08
5.000	1.44	11.000	5.57	17.000	1.62	23.00	1.08
5.083	1.44	11.083	8.63	17.083	1.62	23.08	1.08
5.167	1.44	11.167	8.63	17.167	1.62	23.17	1.08
5.250	1.44	11.250	8.63	17.250	1.62	23.25	1.08
5.333	1.44	11.333	8.63	17.333	1.62	23.33	1.08
5.417	1.44	11.417	8.63	17.417	1.62	23.42	1.08
5.500	1.44	11.500	8.63	17.500	1.62	23.50	1.08
5.583	1.44	11.583	37.40	17.583	1.62	23.58	1.08
5.667	1.44	11.667	37.40	17.667	1.62	23.67	1.08
5.750	1.44	11.750	37.40	17.750	1.62	23.75	1.08

5.833	1.44	11.833	99.24	17.833	1.62	23.83	1.08
5.917	1.44	11.917	99.25	17.917	1.62	23.92	1.08
6.000	1.44	12.000	99.25	18.000	1.62	24.00	1.08

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.023 (i)
 TIME TO PEAK (hrs)= 12.083
 RUNOFF VOLUME (mm)= 38.555
 TOTAL RAINFALL (mm)= 89.900
 RUNOFF COEFFICIENT = 0.429

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min

Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	0.90	6.083	1.80	12.083	12.96	18.08	1.62
0.167	0.90	6.167	1.80	12.167	12.95	18.17	1.62
0.250	0.90	6.250	1.80	12.250	12.95	18.25	1.62
0.333	0.90	6.333	1.80	12.333	12.95	18.33	1.62
0.417	0.90	6.417	1.80	12.417	12.95	18.42	1.62
0.500	0.90	6.500	1.80	12.500	12.95	18.50	1.62
0.583	0.90	6.583	1.80	12.583	6.65	18.58	1.62
0.667	0.90	6.667	1.80	12.667	6.65	18.67	1.62
0.750	0.90	6.750	1.80	12.750	6.65	18.75	1.62
0.833	0.90	6.833	1.80	12.833	6.65	18.83	1.62
0.917	0.90	6.917	1.80	12.917	6.65	18.92	1.62
1.000	0.90	7.000	1.80	13.000	6.65	19.00	1.62
1.083	0.90	7.083	1.80	13.083	1.26	19.08	1.62
1.167	0.90	7.167	1.80	13.167	1.26	19.17	1.62
1.250	0.90	7.250	1.80	13.250	1.26	19.25	1.62
1.333	0.90	7.333	1.80	13.333	1.26	19.33	1.62
1.417	0.90	7.417	1.80	13.417	1.26	19.42	1.62
1.500	0.90	7.500	1.80	13.500	1.26	19.50	1.62
1.583	0.90	7.583	1.80	13.583	7.37	19.58	1.62
1.667	0.90	7.667	1.80	13.667	7.37	19.67	1.62
1.750	0.90	7.750	1.80	13.750	7.37	19.75	1.62
1.833	1.62	7.833	1.80	13.833	7.37	19.83	1.62
1.917	1.62	7.917	1.80	13.917	7.37	19.92	1.62
2.000	1.62	8.000	1.80	14.000	7.37	20.00	1.62
2.083	1.17	8.083	2.43	14.083	2.70	20.08	1.08
2.167	1.17	8.167	2.43	14.167	2.70	20.17	1.08
2.250	1.17	8.250	2.43	14.250	2.70	20.25	1.08
2.333	1.17	8.333	2.43	14.333	2.70	20.33	1.08
2.417	1.17	8.417	2.43	14.417	2.70	20.42	1.08
2.500	1.17	8.500	2.43	14.500	2.70	20.50	1.08
2.583	1.17	8.583	2.43	14.583	2.70	20.58	1.08

2.667	1.17	8.667	2.43	14.667	2.70	20.67	1.08
2.750	1.17	8.750	2.43	14.750	2.70	20.75	1.08
2.833	1.17	8.833	2.43	14.833	2.70	20.83	1.08
2.917	1.17	8.917	2.43	14.917	2.70	20.92	1.08
3.000	1.17	9.000	2.43	15.000	2.70	21.00	1.08
3.083	1.17	9.083	2.88	15.083	2.70	21.08	1.08
3.167	1.17	9.167	2.88	15.167	2.70	21.17	1.08
3.250	1.17	9.250	2.88	15.250	2.70	21.25	1.08
3.333	1.17	9.333	2.88	15.333	2.70	21.33	1.08
3.417	1.17	9.417	2.88	15.417	2.70	21.42	1.08
3.500	1.17	9.500	2.88	15.500	2.70	21.50	1.08
3.583	1.17	9.583	3.24	15.583	2.70	21.58	1.08
3.667	1.17	9.667	3.24	15.667	2.70	21.67	1.08
3.750	1.17	9.750	3.24	15.750	2.70	21.75	1.08
3.833	1.17	9.833	3.24	15.833	2.70	21.83	1.08
3.917	1.17	9.917	3.24	15.917	2.70	21.92	1.08
4.000	1.17	10.000	3.24	16.000	2.70	22.00	1.08
4.083	1.44	10.083	4.14	16.083	1.62	22.08	1.08
4.167	1.44	10.167	4.14	16.167	1.62	22.17	1.08
4.250	1.44	10.250	4.14	16.250	1.62	22.25	1.08
4.333	1.44	10.333	4.14	16.333	1.62	22.33	1.08
4.417	1.44	10.417	4.14	16.417	1.62	22.42	1.08
4.500	1.44	10.500	4.14	16.500	1.62	22.50	1.08
4.583	1.44	10.583	5.57	16.583	1.62	22.58	1.08
4.667	1.44	10.667	5.57	16.667	1.62	22.67	1.08
4.750	1.44	10.750	5.57	16.750	1.62	22.75	1.08
4.833	1.44	10.833	5.57	16.833	1.62	22.83	1.08
4.917	1.44	10.917	5.57	16.917	1.62	22.92	1.08
5.000	1.44	11.000	5.57	17.000	1.62	23.00	1.08
5.083	1.44	11.083	8.63	17.083	1.62	23.08	1.08
5.167	1.44	11.167	8.63	17.167	1.62	23.17	1.08
5.250	1.44	11.250	8.63	17.250	1.62	23.25	1.08
5.333	1.44	11.333	8.63	17.333	1.62	23.33	1.08
5.417	1.44	11.417	8.63	17.417	1.62	23.42	1.08
5.500	1.44	11.500	8.63	17.500	1.62	23.50	1.08
5.583	1.44	11.583	37.40	17.583	1.62	23.58	1.08
5.667	1.44	11.667	37.40	17.667	1.62	23.67	1.08
5.750	1.44	11.750	37.40	17.750	1.62	23.75	1.08
5.833	1.44	11.833	99.24	17.833	1.62	23.83	1.08
5.917	1.44	11.917	99.25	17.917	1.62	23.92	1.08
6.000	1.44	12.000	99.25	18.000	1.62	24.00	1.08

Max.Eff.Inten.(mm/hr)=	99.25	48.91
over (min)	5.00	15.00
Storage Coeff. (min)=	4.48 (ii)	11.40 (ii)
Unit Hyd. Tpeak (min)=	5.00	15.00
Unit Hyd. peak (cms)=	0.23	0.09

TOTALS

PEAK FLOW (cms)=	0.55	0.67	1.138 (iii)
TIME TO PEAK (hrs)=	12.00	12.08	12.00
RUNOFF VOLUME (mm)=	88.90	36.22	47.28
TOTAL RAINFALL (mm)=	89.90	89.90	89.90
RUNOFF COEFFICIENT =	0.99	0.40	0.53

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

- (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 69.0 Ia = Dep. Storage (Above)
- (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
- (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

```

| RESERVOIR( 0300) |
| IN= 2---> OUT= 1 |
| DT= 5.0 min      |
|-----|

```

OVERFLOW IS OFF

OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
0.0000	0.0000	0.7200	0.1600
0.0500	0.0500	0.7300	0.1800
0.1500	0.0700	0.8600	0.1850
0.3000	0.0900	0.9500	0.1900
0.4200	0.1200	0.9900	0.1950
0.5500	0.1300	1.1900	0.2300
0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	1.138	12.00	47.28
OUTFLOW: ID= 1 (0300)	9.680	0.561	12.25	47.26

PEAK FLOW REDUCTION [Qout/Qin](%)= 49.29
 TIME SHIFT OF PEAK FLOW (min)= 15.00
 MAXIMUM STORAGE USED (ha.m.)= 0.1357

```

|-----|
| ADD HYD ( 0400) |
| 1 + 2 = 3       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.073	12.08	39.15
+ ID2= 2 (0202):	0.24	0.023	12.08	38.55
=====				
ID = 3 (0400):	1.05	0.096	12.08	39.01

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

```

|-----|
| ADD HYD ( 0400) |
| 3 + 2 = 1       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.096	12.08	39.01
+ ID2= 2 (0300):	9.68	0.561	12.25	47.26
=====				
ID = 1 (0400):	10.73	0.643	12.17	46.45

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\d5d42c1e-418c-48d2-bcb1-54caa582251f\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\d5d42c1e-418c-48d2-bcb1-54caa582251f\scen

DATE: 02-23-2024

TIME: 08:29:46

USER:

COMMENTS: _____

** SIMULATION : Run 10 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\9ad5e3ee
Ptotal=107.50 mm	Comments: 24hr 25year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	1.08	6.00	2.15	12.00	15.48	18.00	1.93
0.25	1.08	6.25	2.15	12.25	15.48	18.25	1.93
0.50	1.08	6.50	2.15	12.50	7.95	18.50	1.93
0.75	1.08	6.75	2.15	12.75	7.95	18.75	1.93
1.00	1.08	7.00	2.15	13.00	1.50	19.00	1.93
1.25	1.08	7.25	2.15	13.25	1.50	19.25	1.93
1.50	1.08	7.50	2.15	13.50	8.81	19.50	1.93
1.75	1.93	7.75	2.15	13.75	8.81	19.75	1.93
2.00	1.40	8.00	2.90	14.00	3.22	20.00	1.29
2.25	1.40	8.25	2.90	14.25	3.22	20.25	1.29
2.50	1.40	8.50	2.90	14.50	3.22	20.50	1.29
2.75	1.40	8.75	2.90	14.75	3.22	20.75	1.29

3.00	1.40	9.00	3.44	15.00	3.22	21.00	1.29
3.25	1.40	9.25	3.44	15.25	3.22	21.25	1.29
3.50	1.40	9.50	3.87	15.50	3.22	21.50	1.29
3.75	1.40	9.75	3.87	15.75	3.22	21.75	1.29
4.00	1.72	10.00	4.95	16.00	1.93	22.00	1.29
4.25	1.72	10.25	4.95	16.25	1.93	22.25	1.29
4.50	1.72	10.50	6.66	16.50	1.93	22.50	1.29
4.75	1.72	10.75	6.66	16.75	1.93	22.75	1.29
5.00	1.72	11.00	10.32	17.00	1.93	23.00	1.29
5.25	1.72	11.25	10.32	17.25	1.93	23.25	1.29
5.50	1.72	11.50	44.72	17.50	1.93	23.50	1.29
5.75	1.72	11.75	118.68	17.75	1.93	23.75	1.29

CALIB							
NASHYD	(0201)	Area	(ha)= 0.81	Curve Number	(CN)= 74.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 8.00	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.23				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.08	6.083	2.15	12.083	15.49	18.08	1.94
0.167	1.08	6.167	2.15	12.167	15.48	18.17	1.93
0.250	1.08	6.250	2.15	12.250	15.48	18.25	1.93
0.333	1.08	6.333	2.15	12.333	15.48	18.33	1.94
0.417	1.08	6.417	2.15	12.417	15.48	18.42	1.93
0.500	1.08	6.500	2.15	12.500	15.48	18.50	1.93
0.583	1.08	6.583	2.15	12.583	7.96	18.58	1.94
0.667	1.08	6.667	2.15	12.667	7.95	18.67	1.93
0.750	1.08	6.750	2.15	12.750	7.95	18.75	1.93
0.833	1.07	6.833	2.15	12.833	7.95	18.83	1.94
0.917	1.08	6.917	2.15	12.917	7.95	18.92	1.93
1.000	1.08	7.000	2.15	13.000	7.95	19.00	1.93
1.083	1.07	7.083	2.15	13.083	1.51	19.08	1.94
1.167	1.08	7.167	2.15	13.167	1.50	19.17	1.93
1.250	1.08	7.250	2.15	13.250	1.50	19.25	1.93
1.333	1.08	7.333	2.15	13.333	1.50	19.33	1.94
1.417	1.08	7.417	2.15	13.417	1.50	19.42	1.93
1.500	1.08	7.500	2.15	13.500	1.50	19.50	1.94
1.583	1.08	7.583	2.15	13.583	8.81	19.58	1.93
1.667	1.08	7.667	2.15	13.667	8.81	19.67	1.93
1.750	1.08	7.750	2.15	13.750	8.81	19.75	1.94
1.833	1.93	7.833	2.15	13.833	8.81	19.83	1.93
1.917	1.93	7.917	2.15	13.917	8.81	19.92	1.93
2.000	1.93	8.000	2.15	14.000	8.81	20.00	1.93
2.083	1.40	8.083	2.90	14.083	3.23	20.08	1.29
2.167	1.40	8.167	2.90	14.167	3.22	20.17	1.29
2.250	1.40	8.250	2.90	14.250	3.22	20.25	1.29
2.333	1.40	8.333	2.90	14.333	3.22	20.33	1.29
2.417	1.40	8.417	2.90	14.417	3.22	20.42	1.29
2.500	1.40	8.500	2.90	14.500	3.22	20.50	1.29
2.583	1.40	8.583	2.90	14.583	3.22	20.58	1.29
2.667	1.40	8.667	2.90	14.667	3.22	20.67	1.29
2.750	1.40	8.750	2.90	14.750	3.22	20.75	1.29
2.833	1.40	8.833	2.90	14.833	3.22	20.83	1.29
2.917	1.40	8.917	2.90	14.917	3.22	20.92	1.29
3.000	1.40	9.000	2.90	15.000	3.22	21.00	1.29
3.083	1.40	9.083	3.44	15.083	3.22	21.08	1.29

3.167	1.40	9.167	3.44	15.167	3.22	21.17	1.29
3.250	1.40	9.250	3.44	15.250	3.22	21.25	1.29
3.333	1.40	9.333	3.44	15.333	3.22	21.33	1.29
3.417	1.40	9.417	3.44	15.417	3.22	21.42	1.29
3.500	1.40	9.500	3.44	15.500	3.22	21.50	1.29
3.583	1.40	9.583	3.87	15.583	3.22	21.58	1.29
3.667	1.40	9.667	3.87	15.667	3.22	21.67	1.29
3.750	1.40	9.750	3.87	15.750	3.22	21.75	1.29
3.833	1.40	9.833	3.87	15.833	3.22	21.83	1.29
3.917	1.40	9.917	3.87	15.917	3.22	21.92	1.29
4.000	1.40	10.000	3.87	16.000	3.22	22.00	1.29
4.083	1.72	10.083	4.94	16.083	1.94	22.08	1.29
4.167	1.72	10.167	4.95	16.167	1.93	22.17	1.29
4.250	1.72	10.250	4.95	16.250	1.93	22.25	1.29
4.333	1.72	10.333	4.94	16.333	1.94	22.33	1.29
4.417	1.72	10.417	4.95	16.417	1.93	22.42	1.29
4.500	1.72	10.500	4.95	16.500	1.93	22.50	1.29
4.583	1.72	10.583	6.66	16.583	1.94	22.58	1.29
4.667	1.72	10.667	6.66	16.667	1.93	22.67	1.29
4.750	1.72	10.750	6.66	16.750	1.93	22.75	1.29
4.833	1.72	10.833	6.66	16.833	1.94	22.83	1.29
4.917	1.72	10.917	6.66	16.917	1.93	22.92	1.29
5.000	1.72	11.000	6.66	17.000	1.93	23.00	1.29
5.083	1.72	11.083	10.32	17.083	1.94	23.08	1.29
5.167	1.72	11.167	10.32	17.167	1.93	23.17	1.29
5.250	1.72	11.250	10.32	17.250	1.93	23.25	1.29
5.333	1.72	11.333	10.32	17.333	1.94	23.33	1.29
5.417	1.72	11.417	10.32	17.417	1.93	23.42	1.29
5.500	1.72	11.500	10.32	17.500	1.93	23.50	1.29
5.583	1.72	11.583	44.72	17.583	1.94	23.58	1.29
5.667	1.72	11.667	44.72	17.667	1.93	23.67	1.29
5.750	1.72	11.750	44.72	17.750	1.93	23.75	1.29
5.833	1.72	11.833	118.67	17.833	1.94	23.83	1.29
5.917	1.72	11.917	118.68	17.917	1.93	23.92	1.29
6.000	1.72	12.000	118.68	18.000	1.93	24.00	1.29

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.098 (i)
TIME TO PEAK (hrs)= 12.083
RUNOFF VOLUME (mm)= 52.395
TOTAL RAINFALL (mm)= 107.500
RUNOFF COEFFICIENT = 0.487

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB			
NASHYD (0202)		Area (ha)= 0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min		Ia (mm)= 7.30	# of Linear Res.(N)= 3.00
		U.H. Tp(hrs)= 0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.08	6.083	2.15	12.083	15.49	18.08	1.94
0.167	1.08	6.167	2.15	12.167	15.48	18.17	1.93
0.250	1.08	6.250	2.15	12.250	15.48	18.25	1.93
0.333	1.08	6.333	2.15	12.333	15.48	18.33	1.94
0.417	1.08	6.417	2.15	12.417	15.48	18.42	1.93

0.500	1.08	6.500	2.15	12.500	15.48	18.50	1.93
0.583	1.08	6.583	2.15	12.583	7.96	18.58	1.94
0.667	1.08	6.667	2.15	12.667	7.95	18.67	1.93
0.750	1.08	6.750	2.15	12.750	7.95	18.75	1.93
0.833	1.07	6.833	2.15	12.833	7.95	18.83	1.94
0.917	1.08	6.917	2.15	12.917	7.95	18.92	1.93
1.000	1.08	7.000	2.15	13.000	7.95	19.00	1.93
1.083	1.07	7.083	2.15	13.083	1.51	19.08	1.94
1.167	1.08	7.167	2.15	13.167	1.50	19.17	1.93
1.250	1.08	7.250	2.15	13.250	1.50	19.25	1.93
1.333	1.08	7.333	2.15	13.333	1.50	19.33	1.94
1.417	1.08	7.417	2.15	13.417	1.50	19.42	1.93
1.500	1.08	7.500	2.15	13.500	1.50	19.50	1.94
1.583	1.08	7.583	2.15	13.583	8.81	19.58	1.93
1.667	1.08	7.667	2.15	13.667	8.81	19.67	1.93
1.750	1.08	7.750	2.15	13.750	8.81	19.75	1.94
1.833	1.93	7.833	2.15	13.833	8.81	19.83	1.93
1.917	1.93	7.917	2.15	13.917	8.81	19.92	1.93
2.000	1.93	8.000	2.15	14.000	8.81	20.00	1.93
2.083	1.40	8.083	2.90	14.083	3.23	20.08	1.29
2.167	1.40	8.167	2.90	14.167	3.22	20.17	1.29
2.250	1.40	8.250	2.90	14.250	3.22	20.25	1.29
2.333	1.40	8.333	2.90	14.333	3.22	20.33	1.29
2.417	1.40	8.417	2.90	14.417	3.22	20.42	1.29
2.500	1.40	8.500	2.90	14.500	3.22	20.50	1.29
2.583	1.40	8.583	2.90	14.583	3.22	20.58	1.29
2.667	1.40	8.667	2.90	14.667	3.22	20.67	1.29
2.750	1.40	8.750	2.90	14.750	3.22	20.75	1.29
2.833	1.40	8.833	2.90	14.833	3.22	20.83	1.29
2.917	1.40	8.917	2.90	14.917	3.22	20.92	1.29
3.000	1.40	9.000	2.90	15.000	3.22	21.00	1.29
3.083	1.40	9.083	3.44	15.083	3.22	21.08	1.29
3.167	1.40	9.167	3.44	15.167	3.22	21.17	1.29
3.250	1.40	9.250	3.44	15.250	3.22	21.25	1.29
3.333	1.40	9.333	3.44	15.333	3.22	21.33	1.29
3.417	1.40	9.417	3.44	15.417	3.22	21.42	1.29
3.500	1.40	9.500	3.44	15.500	3.22	21.50	1.29
3.583	1.40	9.583	3.87	15.583	3.22	21.58	1.29
3.667	1.40	9.667	3.87	15.667	3.22	21.67	1.29
3.750	1.40	9.750	3.87	15.750	3.22	21.75	1.29
3.833	1.40	9.833	3.87	15.833	3.22	21.83	1.29
3.917	1.40	9.917	3.87	15.917	3.22	21.92	1.29
4.000	1.40	10.000	3.87	16.000	3.22	22.00	1.29
4.083	1.72	10.083	4.94	16.083	1.94	22.08	1.29
4.167	1.72	10.167	4.95	16.167	1.93	22.17	1.29
4.250	1.72	10.250	4.95	16.250	1.93	22.25	1.29
4.333	1.72	10.333	4.94	16.333	1.94	22.33	1.29
4.417	1.72	10.417	4.95	16.417	1.93	22.42	1.29
4.500	1.72	10.500	4.95	16.500	1.93	22.50	1.29
4.583	1.72	10.583	6.66	16.583	1.94	22.58	1.29
4.667	1.72	10.667	6.66	16.667	1.93	22.67	1.29
4.750	1.72	10.750	6.66	16.750	1.93	22.75	1.29
4.833	1.72	10.833	6.66	16.833	1.94	22.83	1.29
4.917	1.72	10.917	6.66	16.917	1.93	22.92	1.29
5.000	1.72	11.000	6.66	17.000	1.93	23.00	1.29
5.083	1.72	11.083	10.32	17.083	1.94	23.08	1.29
5.167	1.72	11.167	10.32	17.167	1.93	23.17	1.29
5.250	1.72	11.250	10.32	17.250	1.93	23.25	1.29
5.333	1.72	11.333	10.32	17.333	1.94	23.33	1.29
5.417	1.72	11.417	10.32	17.417	1.93	23.42	1.29
5.500	1.72	11.500	10.32	17.500	1.93	23.50	1.29
5.583	1.72	11.583	44.72	17.583	1.94	23.58	1.29
5.667	1.72	11.667	44.72	17.667	1.93	23.67	1.29
5.750	1.72	11.750	44.72	17.750	1.93	23.75	1.29

5.833	1.72	11.833	118.67	17.833	1.94	23.83	1.29
5.917	1.72	11.917	118.68	17.917	1.93	23.92	1.29
6.000	1.72	12.000	118.68	18.000	1.93	24.00	1.29

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.031 (i)
 TIME TO PEAK (hrs)= 12.083
 RUNOFF VOLUME (mm)= 51.592
 TOTAL RAINFALL (mm)= 107.500
 RUNOFF COEFFICIENT = 0.480

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min

Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.08	6.083	2.15	12.083	15.49	18.08	1.94
0.167	1.08	6.167	2.15	12.167	15.48	18.17	1.93
0.250	1.08	6.250	2.15	12.250	15.48	18.25	1.93
0.333	1.08	6.333	2.15	12.333	15.48	18.33	1.94
0.417	1.08	6.417	2.15	12.417	15.48	18.42	1.93
0.500	1.08	6.500	2.15	12.500	15.48	18.50	1.93
0.583	1.08	6.583	2.15	12.583	7.96	18.58	1.94
0.667	1.08	6.667	2.15	12.667	7.95	18.67	1.93
0.750	1.08	6.750	2.15	12.750	7.95	18.75	1.93
0.833	1.07	6.833	2.15	12.833	7.95	18.83	1.94
0.917	1.08	6.917	2.15	12.917	7.95	18.92	1.93
1.000	1.08	7.000	2.15	13.000	7.95	19.00	1.93
1.083	1.07	7.083	2.15	13.083	1.51	19.08	1.94
1.167	1.08	7.167	2.15	13.167	1.50	19.17	1.93
1.250	1.08	7.250	2.15	13.250	1.50	19.25	1.93
1.333	1.08	7.333	2.15	13.333	1.50	19.33	1.94
1.417	1.08	7.417	2.15	13.417	1.50	19.42	1.93
1.500	1.08	7.500	2.15	13.500	1.50	19.50	1.94
1.583	1.08	7.583	2.15	13.583	8.81	19.58	1.93
1.667	1.08	7.667	2.15	13.667	8.81	19.67	1.93
1.750	1.08	7.750	2.15	13.750	8.81	19.75	1.94
1.833	1.93	7.833	2.15	13.833	8.81	19.83	1.93
1.917	1.93	7.917	2.15	13.917	8.81	19.92	1.93
2.000	1.93	8.000	2.15	14.000	8.81	20.00	1.93
2.083	1.40	8.083	2.90	14.083	3.23	20.08	1.29
2.167	1.40	8.167	2.90	14.167	3.22	20.17	1.29
2.250	1.40	8.250	2.90	14.250	3.22	20.25	1.29
2.333	1.40	8.333	2.90	14.333	3.22	20.33	1.29
2.417	1.40	8.417	2.90	14.417	3.22	20.42	1.29
2.500	1.40	8.500	2.90	14.500	3.22	20.50	1.29
2.583	1.40	8.583	2.90	14.583	3.22	20.58	1.29

2.667	1.40	8.667	2.90	14.667	3.22	20.67	1.29
2.750	1.40	8.750	2.90	14.750	3.22	20.75	1.29
2.833	1.40	8.833	2.90	14.833	3.22	20.83	1.29
2.917	1.40	8.917	2.90	14.917	3.22	20.92	1.29
3.000	1.40	9.000	2.90	15.000	3.22	21.00	1.29
3.083	1.40	9.083	3.44	15.083	3.22	21.08	1.29
3.167	1.40	9.167	3.44	15.167	3.22	21.17	1.29
3.250	1.40	9.250	3.44	15.250	3.22	21.25	1.29
3.333	1.40	9.333	3.44	15.333	3.22	21.33	1.29
3.417	1.40	9.417	3.44	15.417	3.22	21.42	1.29
3.500	1.40	9.500	3.44	15.500	3.22	21.50	1.29
3.583	1.40	9.583	3.87	15.583	3.22	21.58	1.29
3.667	1.40	9.667	3.87	15.667	3.22	21.67	1.29
3.750	1.40	9.750	3.87	15.750	3.22	21.75	1.29
3.833	1.40	9.833	3.87	15.833	3.22	21.83	1.29
3.917	1.40	9.917	3.87	15.917	3.22	21.92	1.29
4.000	1.40	10.000	3.87	16.000	3.22	22.00	1.29
4.083	1.72	10.083	4.94	16.083	1.94	22.08	1.29
4.167	1.72	10.167	4.95	16.167	1.93	22.17	1.29
4.250	1.72	10.250	4.95	16.250	1.93	22.25	1.29
4.333	1.72	10.333	4.94	16.333	1.94	22.33	1.29
4.417	1.72	10.417	4.95	16.417	1.93	22.42	1.29
4.500	1.72	10.500	4.95	16.500	1.93	22.50	1.29
4.583	1.72	10.583	6.66	16.583	1.94	22.58	1.29
4.667	1.72	10.667	6.66	16.667	1.93	22.67	1.29
4.750	1.72	10.750	6.66	16.750	1.93	22.75	1.29
4.833	1.72	10.833	6.66	16.833	1.94	22.83	1.29
4.917	1.72	10.917	6.66	16.917	1.93	22.92	1.29
5.000	1.72	11.000	6.66	17.000	1.93	23.00	1.29
5.083	1.72	11.083	10.32	17.083	1.94	23.08	1.29
5.167	1.72	11.167	10.32	17.167	1.93	23.17	1.29
5.250	1.72	11.250	10.32	17.250	1.93	23.25	1.29
5.333	1.72	11.333	10.32	17.333	1.94	23.33	1.29
5.417	1.72	11.417	10.32	17.417	1.93	23.42	1.29
5.500	1.72	11.500	10.32	17.500	1.93	23.50	1.29
5.583	1.72	11.583	44.72	17.583	1.94	23.58	1.29
5.667	1.72	11.667	44.72	17.667	1.93	23.67	1.29
5.750	1.72	11.750	44.72	17.750	1.93	23.75	1.29
5.833	1.72	11.833	118.67	17.833	1.94	23.83	1.29
5.917	1.72	11.917	118.68	17.917	1.93	23.92	1.29
6.000	1.72	12.000	118.68	18.000	1.93	24.00	1.29

Max.Eff.Inten.(mm/hr)=	118.68	65.33
over (min)	5.00	15.00
Storage Coeff. (min)=	4.17 (ii)	10.33 (ii)
Unit Hyd. Tpeak (min)=	5.00	15.00
Unit Hyd. peak (cms)=	0.24	0.09

TOTALS

PEAK FLOW (cms)=	0.66	0.94	1.494 (iii)
TIME TO PEAK (hrs)=	12.00	12.08	12.00
RUNOFF VOLUME (mm)=	106.50	48.50	60.68
TOTAL RAINFALL (mm)=	107.50	107.50	107.50
RUNOFF COEFFICIENT =	0.99	0.45	0.56

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

- (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 69.0 Ia = Dep. Storage (Above)
- (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
- (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

```

| RESERVOIR( 0300) |
| IN= 2---> OUT= 1 |
| DT= 5.0 min      |
|-----|

```

OVERFLOW IS OFF

OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
0.0000	0.0000	0.7200	0.1600
0.0500	0.0500	0.7300	0.1800
0.1500	0.0700	0.8600	0.1850
0.3000	0.0900	0.9500	0.1900
0.4200	0.1200	0.9900	0.1950
0.5500	0.1300	1.1900	0.2300
0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	1.494	12.00	60.68
OUTFLOW: ID= 1 (0300)	9.680	0.725	12.25	60.66

PEAK FLOW REDUCTION [Qout/Qin](%)= 48.52
 TIME SHIFT OF PEAK FLOW (min)= 15.00
 MAXIMUM STORAGE USED (ha.m.)= 0.1698

```

|-----|
| ADD HYD ( 0400) |
| 1 + 2 = 3       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.098	12.08	52.40
+ ID2= 2 (0202):	0.24	0.031	12.08	51.59
=====				
ID = 3 (0400):	1.05	0.129	12.08	52.21

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

```

|-----|
| ADD HYD ( 0400) |
| 3 + 2 = 1       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.129	12.08	52.21
+ ID2= 2 (0300):	9.68	0.725	12.25	60.66
=====				
ID = 1 (0400):	10.73	0.840	12.17	59.83

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\2a9b3116-c9ce-4ba0-9c4b-2c96328e57a8\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\2a9b3116-c9ce-4ba0-9c4b-2c96328e57a8\scen

DATE: 02-23-2024

TIME: 08:29:45

USER:

COMMENTS: _____

** SIMULATION : Run 11 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\9948bc8a
Ptotal=120.60 mm	Comments: 24hr 50year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	1.21	6.00	2.41	12.00	17.37	18.00	2.17
0.25	1.21	6.25	2.41	12.25	17.37	18.25	2.17
0.50	1.21	6.50	2.41	12.50	8.92	18.50	2.17
0.75	1.21	6.75	2.41	12.75	8.92	18.75	2.17
1.00	1.21	7.00	2.41	13.00	1.69	19.00	2.17
1.25	1.21	7.25	2.41	13.25	1.69	19.25	2.17
1.50	1.21	7.50	2.41	13.50	9.89	19.50	2.17
1.75	2.17	7.75	2.41	13.75	9.89	19.75	2.17
2.00	1.57	8.00	3.26	14.00	3.62	20.00	1.45
2.25	1.57	8.25	3.26	14.25	3.62	20.25	1.45
2.50	1.57	8.50	3.26	14.50	3.62	20.50	1.45
2.75	1.57	8.75	3.26	14.75	3.62	20.75	1.45

3.00	1.57	9.00	3.86	15.00	3.62	21.00	1.45
3.25	1.57	9.25	3.86	15.25	3.62	21.25	1.45
3.50	1.57	9.50	4.34	15.50	3.62	21.50	1.45
3.75	1.57	9.75	4.34	15.75	3.62	21.75	1.45
4.00	1.93	10.00	5.55	16.00	2.17	22.00	1.45
4.25	1.93	10.25	5.55	16.25	2.17	22.25	1.45
4.50	1.93	10.50	7.48	16.50	2.17	22.50	1.45
4.75	1.93	10.75	7.48	16.75	2.17	22.75	1.45
5.00	1.93	11.00	11.58	17.00	2.17	23.00	1.45
5.25	1.93	11.25	11.58	17.25	2.17	23.25	1.45
5.50	1.93	11.50	50.17	17.50	2.17	23.50	1.45
5.75	1.93	11.75	133.14	17.75	2.17	23.75	1.45

CALIB
 NASHYD (0201)
 ID= 1 DT= 5.0 min

Area (ha)= 0.81 Curve Number (CN)= 74.0
 Ia (mm)= 8.00 # of Linear Res.(N)= 3.00
 U.H. Tp(hrs)= 0.23

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.21	6.083	2.41	12.083	17.38	18.08	2.17
0.167	1.21	6.167	2.41	12.167	17.37	18.17	2.17
0.250	1.21	6.250	2.41	12.250	17.37	18.25	2.17
0.333	1.21	6.333	2.41	12.333	17.37	18.33	2.17
0.417	1.21	6.417	2.41	12.417	17.37	18.42	2.17
0.500	1.21	6.500	2.41	12.500	17.37	18.50	2.17
0.583	1.21	6.583	2.41	12.583	8.93	18.58	2.17
0.667	1.21	6.667	2.41	12.667	8.92	18.67	2.17
0.750	1.21	6.750	2.41	12.750	8.92	18.75	2.17
0.833	1.21	6.833	2.41	12.833	8.92	18.83	2.17
0.917	1.21	6.917	2.41	12.917	8.92	18.92	2.17
1.000	1.21	7.000	2.41	13.000	8.92	19.00	2.17
1.083	1.21	7.083	2.41	13.083	1.69	19.08	2.17
1.167	1.21	7.167	2.41	13.167	1.69	19.17	2.17
1.250	1.21	7.250	2.41	13.250	1.69	19.25	2.17
1.333	1.21	7.333	2.41	13.333	1.69	19.33	2.17
1.417	1.21	7.417	2.41	13.417	1.69	19.42	2.17
1.500	1.21	7.500	2.41	13.500	1.69	19.50	2.17
1.583	1.21	7.583	2.41	13.583	9.89	19.58	2.17
1.667	1.21	7.667	2.41	13.667	9.89	19.67	2.17
1.750	1.21	7.750	2.41	13.750	9.89	19.75	2.17
1.833	2.17	7.833	2.41	13.833	9.89	19.83	2.17
1.917	2.17	7.917	2.41	13.917	9.89	19.92	2.17
2.000	2.17	8.000	2.41	14.000	9.89	20.00	2.17
2.083	1.57	8.083	3.26	14.083	3.62	20.08	1.45
2.167	1.57	8.167	3.26	14.167	3.62	20.17	1.45
2.250	1.57	8.250	3.26	14.250	3.62	20.25	1.45
2.333	1.57	8.333	3.26	14.333	3.62	20.33	1.45
2.417	1.57	8.417	3.26	14.417	3.62	20.42	1.45
2.500	1.57	8.500	3.26	14.500	3.62	20.50	1.45
2.583	1.57	8.583	3.26	14.583	3.62	20.58	1.45
2.667	1.57	8.667	3.26	14.667	3.62	20.67	1.45
2.750	1.57	8.750	3.26	14.750	3.62	20.75	1.45
2.833	1.57	8.833	3.26	14.833	3.62	20.83	1.45
2.917	1.57	8.917	3.26	14.917	3.62	20.92	1.45
3.000	1.57	9.000	3.26	15.000	3.62	21.00	1.45
3.083	1.57	9.083	3.86	15.083	3.62	21.08	1.45

3.167	1.57	9.167	3.86	15.167	3.62	21.17	1.45
3.250	1.57	9.250	3.86	15.250	3.62	21.25	1.45
3.333	1.57	9.333	3.86	15.333	3.62	21.33	1.45
3.417	1.57	9.417	3.86	15.417	3.62	21.42	1.45
3.500	1.57	9.500	3.86	15.500	3.62	21.50	1.45
3.583	1.57	9.583	4.34	15.583	3.62	21.58	1.45
3.667	1.57	9.667	4.34	15.667	3.62	21.67	1.45
3.750	1.57	9.750	4.34	15.750	3.62	21.75	1.45
3.833	1.57	9.833	4.34	15.833	3.62	21.83	1.45
3.917	1.57	9.917	4.34	15.917	3.62	21.92	1.45
4.000	1.57	10.000	4.34	16.000	3.62	22.00	1.45
4.083	1.93	10.083	5.55	16.083	2.17	22.08	1.45
4.167	1.93	10.167	5.55	16.167	2.17	22.17	1.45
4.250	1.93	10.250	5.55	16.250	2.17	22.25	1.45
4.333	1.93	10.333	5.55	16.333	2.17	22.33	1.45
4.417	1.93	10.417	5.55	16.417	2.17	22.42	1.45
4.500	1.93	10.500	5.55	16.500	2.17	22.50	1.45
4.583	1.93	10.583	7.48	16.583	2.17	22.58	1.45
4.667	1.93	10.667	7.48	16.667	2.17	22.67	1.45
4.750	1.93	10.750	7.48	16.750	2.17	22.75	1.45
4.833	1.93	10.833	7.48	16.833	2.17	22.83	1.45
4.917	1.93	10.917	7.48	16.917	2.17	22.92	1.45
5.000	1.93	11.000	7.48	17.000	2.17	23.00	1.45
5.083	1.93	11.083	11.58	17.083	2.17	23.08	1.45
5.167	1.93	11.167	11.58	17.167	2.17	23.17	1.45
5.250	1.93	11.250	11.58	17.250	2.17	23.25	1.45
5.333	1.93	11.333	11.58	17.333	2.17	23.33	1.45
5.417	1.93	11.417	11.58	17.417	2.17	23.42	1.45
5.500	1.93	11.500	11.58	17.500	2.17	23.50	1.45
5.583	1.93	11.583	50.17	17.583	2.17	23.58	1.45
5.667	1.93	11.667	50.17	17.667	2.17	23.67	1.45
5.750	1.93	11.750	50.17	17.750	2.17	23.75	1.45
5.833	1.93	11.833	133.13	17.833	2.17	23.83	1.45
5.917	1.93	11.917	133.14	17.917	2.17	23.92	1.45
6.000	1.93	12.000	133.14	18.000	2.17	24.00	1.45

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.118 (i)
TIME TO PEAK (hrs)= 12.083
RUNOFF VOLUME (mm)= 62.745
TOTAL RAINFALL (mm)= 120.600
RUNOFF COEFFICIENT = 0.520

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
NASHYD (0202)
ID= 1 DT= 5.0 min

Area (ha)= 0.24 Curve Number (CN)= 73.0
Ia (mm)= 7.30 # of Linear Res.(N)= 3.00
U.H. Tp(hrs)= 0.19

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.21	6.083	2.41	12.083	17.38	18.08	2.17
0.167	1.21	6.167	2.41	12.167	17.37	18.17	2.17
0.250	1.21	6.250	2.41	12.250	17.37	18.25	2.17
0.333	1.21	6.333	2.41	12.333	17.37	18.33	2.17
0.417	1.21	6.417	2.41	12.417	17.37	18.42	2.17

0.500	1.21	6.500	2.41	12.500	17.37	18.50	2.17
0.583	1.21	6.583	2.41	12.583	8.93	18.58	2.17
0.667	1.21	6.667	2.41	12.667	8.92	18.67	2.17
0.750	1.21	6.750	2.41	12.750	8.92	18.75	2.17
0.833	1.21	6.833	2.41	12.833	8.92	18.83	2.17
0.917	1.21	6.917	2.41	12.917	8.92	18.92	2.17
1.000	1.21	7.000	2.41	13.000	8.92	19.00	2.17
1.083	1.21	7.083	2.41	13.083	1.69	19.08	2.17
1.167	1.21	7.167	2.41	13.167	1.69	19.17	2.17
1.250	1.21	7.250	2.41	13.250	1.69	19.25	2.17
1.333	1.21	7.333	2.41	13.333	1.69	19.33	2.17
1.417	1.21	7.417	2.41	13.417	1.69	19.42	2.17
1.500	1.21	7.500	2.41	13.500	1.69	19.50	2.17
1.583	1.21	7.583	2.41	13.583	9.89	19.58	2.17
1.667	1.21	7.667	2.41	13.667	9.89	19.67	2.17
1.750	1.21	7.750	2.41	13.750	9.89	19.75	2.17
1.833	2.17	7.833	2.41	13.833	9.89	19.83	2.17
1.917	2.17	7.917	2.41	13.917	9.89	19.92	2.17
2.000	2.17	8.000	2.41	14.000	9.89	20.00	2.17
2.083	1.57	8.083	3.26	14.083	3.62	20.08	1.45
2.167	1.57	8.167	3.26	14.167	3.62	20.17	1.45
2.250	1.57	8.250	3.26	14.250	3.62	20.25	1.45
2.333	1.57	8.333	3.26	14.333	3.62	20.33	1.45
2.417	1.57	8.417	3.26	14.417	3.62	20.42	1.45
2.500	1.57	8.500	3.26	14.500	3.62	20.50	1.45
2.583	1.57	8.583	3.26	14.583	3.62	20.58	1.45
2.667	1.57	8.667	3.26	14.667	3.62	20.67	1.45
2.750	1.57	8.750	3.26	14.750	3.62	20.75	1.45
2.833	1.57	8.833	3.26	14.833	3.62	20.83	1.45
2.917	1.57	8.917	3.26	14.917	3.62	20.92	1.45
3.000	1.57	9.000	3.26	15.000	3.62	21.00	1.45
3.083	1.57	9.083	3.86	15.083	3.62	21.08	1.45
3.167	1.57	9.167	3.86	15.167	3.62	21.17	1.45
3.250	1.57	9.250	3.86	15.250	3.62	21.25	1.45
3.333	1.57	9.333	3.86	15.333	3.62	21.33	1.45
3.417	1.57	9.417	3.86	15.417	3.62	21.42	1.45
3.500	1.57	9.500	3.86	15.500	3.62	21.50	1.45
3.583	1.57	9.583	4.34	15.583	3.62	21.58	1.45
3.667	1.57	9.667	4.34	15.667	3.62	21.67	1.45
3.750	1.57	9.750	4.34	15.750	3.62	21.75	1.45
3.833	1.57	9.833	4.34	15.833	3.62	21.83	1.45
3.917	1.57	9.917	4.34	15.917	3.62	21.92	1.45
4.000	1.57	10.000	4.34	16.000	3.62	22.00	1.45
4.083	1.93	10.083	5.55	16.083	2.17	22.08	1.45
4.167	1.93	10.167	5.55	16.167	2.17	22.17	1.45
4.250	1.93	10.250	5.55	16.250	2.17	22.25	1.45
4.333	1.93	10.333	5.55	16.333	2.17	22.33	1.45
4.417	1.93	10.417	5.55	16.417	2.17	22.42	1.45
4.500	1.93	10.500	5.55	16.500	2.17	22.50	1.45
4.583	1.93	10.583	7.48	16.583	2.17	22.58	1.45
4.667	1.93	10.667	7.48	16.667	2.17	22.67	1.45
4.750	1.93	10.750	7.48	16.750	2.17	22.75	1.45
4.833	1.93	10.833	7.48	16.833	2.17	22.83	1.45
4.917	1.93	10.917	7.48	16.917	2.17	22.92	1.45
5.000	1.93	11.000	7.48	17.000	2.17	23.00	1.45
5.083	1.93	11.083	11.58	17.083	2.17	23.08	1.45
5.167	1.93	11.167	11.58	17.167	2.17	23.17	1.45
5.250	1.93	11.250	11.58	17.250	2.17	23.25	1.45
5.333	1.93	11.333	11.58	17.333	2.17	23.33	1.45
5.417	1.93	11.417	11.58	17.417	2.17	23.42	1.45
5.500	1.93	11.500	11.58	17.500	2.17	23.50	1.45
5.583	1.93	11.583	50.17	17.583	2.17	23.58	1.45
5.667	1.93	11.667	50.17	17.667	2.17	23.67	1.45
5.750	1.93	11.750	50.17	17.750	2.17	23.75	1.45

5.833	1.93	11.833	133.13	17.833	2.17	23.83	1.45
5.917	1.93	11.917	133.14	17.917	2.17	23.92	1.45
6.000	1.93	12.000	133.14	18.000	2.17	24.00	1.45

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.038 (i)
 TIME TO PEAK (hrs)= 12.083
 RUNOFF VOLUME (mm)= 61.795
 TOTAL RAINFALL (mm)= 120.600
 RUNOFF COEFFICIENT = 0.512

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min

Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.21	6.083	2.41	12.083	17.38	18.08	2.17
0.167	1.21	6.167	2.41	12.167	17.37	18.17	2.17
0.250	1.21	6.250	2.41	12.250	17.37	18.25	2.17
0.333	1.21	6.333	2.41	12.333	17.37	18.33	2.17
0.417	1.21	6.417	2.41	12.417	17.37	18.42	2.17
0.500	1.21	6.500	2.41	12.500	17.37	18.50	2.17
0.583	1.21	6.583	2.41	12.583	8.93	18.58	2.17
0.667	1.21	6.667	2.41	12.667	8.92	18.67	2.17
0.750	1.21	6.750	2.41	12.750	8.92	18.75	2.17
0.833	1.21	6.833	2.41	12.833	8.92	18.83	2.17
0.917	1.21	6.917	2.41	12.917	8.92	18.92	2.17
1.000	1.21	7.000	2.41	13.000	8.92	19.00	2.17
1.083	1.21	7.083	2.41	13.083	1.69	19.08	2.17
1.167	1.21	7.167	2.41	13.167	1.69	19.17	2.17
1.250	1.21	7.250	2.41	13.250	1.69	19.25	2.17
1.333	1.21	7.333	2.41	13.333	1.69	19.33	2.17
1.417	1.21	7.417	2.41	13.417	1.69	19.42	2.17
1.500	1.21	7.500	2.41	13.500	1.69	19.50	2.17
1.583	1.21	7.583	2.41	13.583	9.89	19.58	2.17
1.667	1.21	7.667	2.41	13.667	9.89	19.67	2.17
1.750	1.21	7.750	2.41	13.750	9.89	19.75	2.17
1.833	2.17	7.833	2.41	13.833	9.89	19.83	2.17
1.917	2.17	7.917	2.41	13.917	9.89	19.92	2.17
2.000	2.17	8.000	2.41	14.000	9.89	20.00	2.17
2.083	1.57	8.083	3.26	14.083	3.62	20.08	1.45
2.167	1.57	8.167	3.26	14.167	3.62	20.17	1.45
2.250	1.57	8.250	3.26	14.250	3.62	20.25	1.45
2.333	1.57	8.333	3.26	14.333	3.62	20.33	1.45
2.417	1.57	8.417	3.26	14.417	3.62	20.42	1.45
2.500	1.57	8.500	3.26	14.500	3.62	20.50	1.45
2.583	1.57	8.583	3.26	14.583	3.62	20.58	1.45

2.667	1.57	8.667	3.26	14.667	3.62	20.67	1.45
2.750	1.57	8.750	3.26	14.750	3.62	20.75	1.45
2.833	1.57	8.833	3.26	14.833	3.62	20.83	1.45
2.917	1.57	8.917	3.26	14.917	3.62	20.92	1.45
3.000	1.57	9.000	3.26	15.000	3.62	21.00	1.45
3.083	1.57	9.083	3.86	15.083	3.62	21.08	1.45
3.167	1.57	9.167	3.86	15.167	3.62	21.17	1.45
3.250	1.57	9.250	3.86	15.250	3.62	21.25	1.45
3.333	1.57	9.333	3.86	15.333	3.62	21.33	1.45
3.417	1.57	9.417	3.86	15.417	3.62	21.42	1.45
3.500	1.57	9.500	3.86	15.500	3.62	21.50	1.45
3.583	1.57	9.583	4.34	15.583	3.62	21.58	1.45
3.667	1.57	9.667	4.34	15.667	3.62	21.67	1.45
3.750	1.57	9.750	4.34	15.750	3.62	21.75	1.45
3.833	1.57	9.833	4.34	15.833	3.62	21.83	1.45
3.917	1.57	9.917	4.34	15.917	3.62	21.92	1.45
4.000	1.57	10.000	4.34	16.000	3.62	22.00	1.45
4.083	1.93	10.083	5.55	16.083	2.17	22.08	1.45
4.167	1.93	10.167	5.55	16.167	2.17	22.17	1.45
4.250	1.93	10.250	5.55	16.250	2.17	22.25	1.45
4.333	1.93	10.333	5.55	16.333	2.17	22.33	1.45
4.417	1.93	10.417	5.55	16.417	2.17	22.42	1.45
4.500	1.93	10.500	5.55	16.500	2.17	22.50	1.45
4.583	1.93	10.583	7.48	16.583	2.17	22.58	1.45
4.667	1.93	10.667	7.48	16.667	2.17	22.67	1.45
4.750	1.93	10.750	7.48	16.750	2.17	22.75	1.45
4.833	1.93	10.833	7.48	16.833	2.17	22.83	1.45
4.917	1.93	10.917	7.48	16.917	2.17	22.92	1.45
5.000	1.93	11.000	7.48	17.000	2.17	23.00	1.45
5.083	1.93	11.083	11.58	17.083	2.17	23.08	1.45
5.167	1.93	11.167	11.58	17.167	2.17	23.17	1.45
5.250	1.93	11.250	11.58	17.250	2.17	23.25	1.45
5.333	1.93	11.333	11.58	17.333	2.17	23.33	1.45
5.417	1.93	11.417	11.58	17.417	2.17	23.42	1.45
5.500	1.93	11.500	11.58	17.500	2.17	23.50	1.45
5.583	1.93	11.583	50.17	17.583	2.17	23.58	1.45
5.667	1.93	11.667	50.17	17.667	2.17	23.67	1.45
5.750	1.93	11.750	50.17	17.750	2.17	23.75	1.45
5.833	1.93	11.833	133.13	17.833	2.17	23.83	1.45
5.917	1.93	11.917	133.14	17.917	2.17	23.92	1.45
6.000	1.93	12.000	133.14	18.000	2.17	24.00	1.45

Max.Eff.Inten.(mm/hr)=	133.14	78.19
over (min)	5.00	10.00
Storage Coeff. (min)=	3.99 (ii)	9.72 (ii)
Unit Hyd. Tpeak (min)=	5.00	10.00
Unit Hyd. peak (cms)=	0.24	0.11

TOTALS

PEAK FLOW (cms)=	0.74	1.22	1.957 (iii)
TIME TO PEAK (hrs)=	12.00	12.00	12.00
RUNOFF VOLUME (mm)=	119.60	58.17	71.07
TOTAL RAINFALL (mm)=	120.60	120.60	120.60
RUNOFF COEFFICIENT =	0.99	0.48	0.59

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

- (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 69.0 Ia = Dep. Storage (Above)
- (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
- (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

```

| RESERVOIR( 0300) |
| IN= 2---> OUT= 1 |
| DT= 5.0 min      |
|-----|

```

OVERFLOW IS OFF

OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
0.0000	0.0000	0.7200	0.1600
0.0500	0.0500	0.7300	0.1800
0.1500	0.0700	0.8600	0.1850
0.3000	0.0900	0.9500	0.1900
0.4200	0.1200	0.9900	0.1950
0.5500	0.1300	1.1900	0.2300
0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	1.957	12.00	71.07
OUTFLOW: ID= 1 (0300)	9.680	0.997	12.17	71.05

PEAK FLOW REDUCTION [Qout/Qin](%)= 50.94
 TIME SHIFT OF PEAK FLOW (min)= 10.00
 MAXIMUM STORAGE USED (ha.m.)= 0.1970

```

|-----|
| ADD HYD ( 0400) |
| 1 + 2 = 3       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.118	12.08	62.74
+ ID2= 2 (0202):	0.24	0.038	12.08	61.79
=====				
ID = 3 (0400):	1.05	0.155	12.08	62.53

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

```

|-----|
| ADD HYD ( 0400) |
| 3 + 2 = 1       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.155	12.08	62.53
+ ID2= 2 (0300):	9.68	0.997	12.17	71.05
=====				
ID = 1 (0400):	10.73	1.137	12.17	70.21

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\75c47d97-4a76-445a-a2e5-88dbddcd5c06\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\75c47d97-4a76-445a-a2e5-88dbddcd5c06\scen

DATE: 02-23-2024

TIME: 08:29:45

USER:

COMMENTS: _____

** SIMULATION : Run 12 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\6d480168
Ptotal=133.60 mm	Comments: 24hr 100year SCS STORM - CITY OF BARRIE

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.00	1.34	6.00	2.67	12.00	19.24	18.00	2.40
0.25	1.34	6.25	2.67	12.25	19.24	18.25	2.40
0.50	1.34	6.50	2.67	12.50	9.89	18.50	2.40
0.75	1.34	6.75	2.67	12.75	9.89	18.75	2.40
1.00	1.34	7.00	2.67	13.00	1.87	19.00	2.40
1.25	1.34	7.25	2.67	13.25	1.87	19.25	2.40
1.50	1.34	7.50	2.67	13.50	10.96	19.50	2.40
1.75	2.40	7.75	2.67	13.75	10.96	19.75	2.40
2.00	1.74	8.00	3.61	14.00	4.01	20.00	1.60
2.25	1.74	8.25	3.61	14.25	4.01	20.25	1.60
2.50	1.74	8.50	3.61	14.50	4.01	20.50	1.60
2.75	1.74	8.75	3.61	14.75	4.01	20.75	1.60

3.00	1.74	9.00	4.28	15.00	4.01	21.00	1.60
3.25	1.74	9.25	4.28	15.25	4.01	21.25	1.60
3.50	1.74	9.50	4.81	15.50	4.01	21.50	1.60
3.75	1.74	9.75	4.81	15.75	4.01	21.75	1.60
4.00	2.14	10.00	6.15	16.00	2.40	22.00	1.60
4.25	2.14	10.25	6.15	16.25	2.40	22.25	1.60
4.50	2.14	10.50	8.28	16.50	2.40	22.50	1.60
4.75	2.14	10.75	8.28	16.75	2.40	22.75	1.60
5.00	2.14	11.00	12.83	17.00	2.40	23.00	1.60
5.25	2.14	11.25	12.83	17.25	2.40	23.25	1.60
5.50	2.14	11.50	55.58	17.50	2.40	23.50	1.60
5.75	2.14	11.75	147.49	17.75	2.40	23.75	1.60

CALIB							
NASHYD	(0201)	Area	(ha)= 0.81	Curve Number	(CN)= 74.0		
ID= 1	DT= 5.0 min	Ia	(mm)= 8.00	# of Linear Res.(N)= 3.00			
		U.H. Tp(hrs)=	0.23				

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.34	6.083	2.67	12.083	19.25	18.08	2.40
0.167	1.34	6.167	2.67	12.167	19.24	18.17	2.40
0.250	1.34	6.250	2.67	12.250	19.24	18.25	2.40
0.333	1.34	6.333	2.67	12.333	19.24	18.33	2.40
0.417	1.34	6.417	2.67	12.417	19.24	18.42	2.40
0.500	1.34	6.500	2.67	12.500	19.24	18.50	2.40
0.583	1.34	6.583	2.67	12.583	9.89	18.58	2.40
0.667	1.34	6.667	2.67	12.667	9.89	18.67	2.40
0.750	1.34	6.750	2.67	12.750	9.89	18.75	2.40
0.833	1.34	6.833	2.67	12.833	9.89	18.83	2.40
0.917	1.34	6.917	2.67	12.917	9.89	18.92	2.40
1.000	1.34	7.000	2.67	13.000	9.89	19.00	2.40
1.083	1.34	7.083	2.67	13.083	1.87	19.08	2.40
1.167	1.34	7.167	2.67	13.167	1.87	19.17	2.40
1.250	1.34	7.250	2.67	13.250	1.87	19.25	2.40
1.333	1.34	7.333	2.67	13.333	1.87	19.33	2.40
1.417	1.34	7.417	2.67	13.417	1.87	19.42	2.40
1.500	1.34	7.500	2.67	13.500	1.87	19.50	2.40
1.583	1.34	7.583	2.67	13.583	10.95	19.58	2.40
1.667	1.34	7.667	2.67	13.667	10.96	19.67	2.40
1.750	1.34	7.750	2.67	13.750	10.96	19.75	2.40
1.833	2.40	7.833	2.67	13.833	10.96	19.83	2.40
1.917	2.40	7.917	2.67	13.917	10.96	19.92	2.40
2.000	2.40	8.000	2.67	14.000	10.96	20.00	2.40
2.083	1.74	8.083	3.61	14.083	4.01	20.08	1.60
2.167	1.74	8.167	3.61	14.167	4.01	20.17	1.60
2.250	1.74	8.250	3.61	14.250	4.01	20.25	1.60
2.333	1.74	8.333	3.61	14.333	4.01	20.33	1.60
2.417	1.74	8.417	3.61	14.417	4.01	20.42	1.60
2.500	1.74	8.500	3.61	14.500	4.01	20.50	1.60
2.583	1.74	8.583	3.61	14.583	4.01	20.58	1.60
2.667	1.74	8.667	3.61	14.667	4.01	20.67	1.60
2.750	1.74	8.750	3.61	14.750	4.01	20.75	1.60
2.833	1.74	8.833	3.61	14.833	4.01	20.83	1.60
2.917	1.74	8.917	3.61	14.917	4.01	20.92	1.60
3.000	1.74	9.000	3.61	15.000	4.01	21.00	1.60
3.083	1.74	9.083	4.28	15.083	4.01	21.08	1.60

3.167	1.74	9.167	4.28	15.167	4.01	21.17	1.60
3.250	1.74	9.250	4.28	15.250	4.01	21.25	1.60
3.333	1.74	9.333	4.28	15.333	4.01	21.33	1.60
3.417	1.74	9.417	4.28	15.417	4.01	21.42	1.60
3.500	1.74	9.500	4.28	15.500	4.01	21.50	1.60
3.583	1.74	9.583	4.81	15.583	4.01	21.58	1.60
3.667	1.74	9.667	4.81	15.667	4.01	21.67	1.60
3.750	1.74	9.750	4.81	15.750	4.01	21.75	1.60
3.833	1.74	9.833	4.81	15.833	4.01	21.83	1.60
3.917	1.74	9.917	4.81	15.917	4.01	21.92	1.60
4.000	1.74	10.000	4.81	16.000	4.01	22.00	1.60
4.083	2.14	10.083	6.15	16.083	2.41	22.08	1.60
4.167	2.14	10.167	6.15	16.167	2.40	22.17	1.60
4.250	2.14	10.250	6.15	16.250	2.40	22.25	1.60
4.333	2.14	10.333	6.15	16.333	2.40	22.33	1.60
4.417	2.14	10.417	6.15	16.417	2.40	22.42	1.60
4.500	2.14	10.500	6.15	16.500	2.40	22.50	1.60
4.583	2.14	10.583	8.28	16.583	2.40	22.58	1.60
4.667	2.14	10.667	8.28	16.667	2.40	22.67	1.60
4.750	2.14	10.750	8.28	16.750	2.40	22.75	1.60
4.833	2.14	10.833	8.28	16.833	2.40	22.83	1.60
4.917	2.14	10.917	8.28	16.917	2.40	22.92	1.60
5.000	2.14	11.000	8.28	17.000	2.40	23.00	1.60
5.083	2.14	11.083	12.83	17.083	2.40	23.08	1.60
5.167	2.14	11.167	12.83	17.167	2.40	23.17	1.60
5.250	2.14	11.250	12.83	17.250	2.40	23.25	1.60
5.333	2.14	11.333	12.83	17.333	2.40	23.33	1.60
5.417	2.14	11.417	12.83	17.417	2.40	23.42	1.60
5.500	2.14	11.500	12.83	17.500	2.40	23.50	1.60
5.583	2.14	11.583	55.57	17.583	2.40	23.58	1.60
5.667	2.14	11.667	55.58	17.667	2.40	23.67	1.60
5.750	2.14	11.750	55.58	17.750	2.40	23.75	1.60
5.833	2.14	11.833	147.48	17.833	2.40	23.83	1.60
5.917	2.14	11.917	147.49	17.917	2.40	23.92	1.60
6.000	2.14	12.000	147.49	18.000	2.40	24.00	1.60

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.138 (i)
TIME TO PEAK (hrs)= 12.083
RUNOFF VOLUME (mm)= 73.346
TOTAL RAINFALL (mm)= 133.600
RUNOFF COEFFICIENT = 0.549

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
NASHYD (0202)
ID= 1 DT= 5.0 min

Area (ha)= 0.24 Curve Number (CN)= 73.0
Ia (mm)= 7.30 # of Linear Res.(N)= 3.00
U.H. Tp(hrs)= 0.19

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.34	6.083	2.67	12.083	19.25	18.08	2.40
0.167	1.34	6.167	2.67	12.167	19.24	18.17	2.40
0.250	1.34	6.250	2.67	12.250	19.24	18.25	2.40
0.333	1.34	6.333	2.67	12.333	19.24	18.33	2.40
0.417	1.34	6.417	2.67	12.417	19.24	18.42	2.40

0.500	1.34	6.500	2.67	12.500	19.24	18.50	2.40
0.583	1.34	6.583	2.67	12.583	9.89	18.58	2.40
0.667	1.34	6.667	2.67	12.667	9.89	18.67	2.40
0.750	1.34	6.750	2.67	12.750	9.89	18.75	2.40
0.833	1.34	6.833	2.67	12.833	9.89	18.83	2.40
0.917	1.34	6.917	2.67	12.917	9.89	18.92	2.40
1.000	1.34	7.000	2.67	13.000	9.89	19.00	2.40
1.083	1.34	7.083	2.67	13.083	1.87	19.08	2.40
1.167	1.34	7.167	2.67	13.167	1.87	19.17	2.40
1.250	1.34	7.250	2.67	13.250	1.87	19.25	2.40
1.333	1.34	7.333	2.67	13.333	1.87	19.33	2.40
1.417	1.34	7.417	2.67	13.417	1.87	19.42	2.40
1.500	1.34	7.500	2.67	13.500	1.87	19.50	2.40
1.583	1.34	7.583	2.67	13.583	10.95	19.58	2.40
1.667	1.34	7.667	2.67	13.667	10.96	19.67	2.40
1.750	1.34	7.750	2.67	13.750	10.96	19.75	2.40
1.833	2.40	7.833	2.67	13.833	10.96	19.83	2.40
1.917	2.40	7.917	2.67	13.917	10.96	19.92	2.40
2.000	2.40	8.000	2.67	14.000	10.96	20.00	2.40
2.083	1.74	8.083	3.61	14.083	4.01	20.08	1.60
2.167	1.74	8.167	3.61	14.167	4.01	20.17	1.60
2.250	1.74	8.250	3.61	14.250	4.01	20.25	1.60
2.333	1.74	8.333	3.61	14.333	4.01	20.33	1.60
2.417	1.74	8.417	3.61	14.417	4.01	20.42	1.60
2.500	1.74	8.500	3.61	14.500	4.01	20.50	1.60
2.583	1.74	8.583	3.61	14.583	4.01	20.58	1.60
2.667	1.74	8.667	3.61	14.667	4.01	20.67	1.60
2.750	1.74	8.750	3.61	14.750	4.01	20.75	1.60
2.833	1.74	8.833	3.61	14.833	4.01	20.83	1.60
2.917	1.74	8.917	3.61	14.917	4.01	20.92	1.60
3.000	1.74	9.000	3.61	15.000	4.01	21.00	1.60
3.083	1.74	9.083	4.28	15.083	4.01	21.08	1.60
3.167	1.74	9.167	4.28	15.167	4.01	21.17	1.60
3.250	1.74	9.250	4.28	15.250	4.01	21.25	1.60
3.333	1.74	9.333	4.28	15.333	4.01	21.33	1.60
3.417	1.74	9.417	4.28	15.417	4.01	21.42	1.60
3.500	1.74	9.500	4.28	15.500	4.01	21.50	1.60
3.583	1.74	9.583	4.81	15.583	4.01	21.58	1.60
3.667	1.74	9.667	4.81	15.667	4.01	21.67	1.60
3.750	1.74	9.750	4.81	15.750	4.01	21.75	1.60
3.833	1.74	9.833	4.81	15.833	4.01	21.83	1.60
3.917	1.74	9.917	4.81	15.917	4.01	21.92	1.60
4.000	1.74	10.000	4.81	16.000	4.01	22.00	1.60
4.083	2.14	10.083	6.15	16.083	2.41	22.08	1.60
4.167	2.14	10.167	6.15	16.167	2.40	22.17	1.60
4.250	2.14	10.250	6.15	16.250	2.40	22.25	1.60
4.333	2.14	10.333	6.15	16.333	2.40	22.33	1.60
4.417	2.14	10.417	6.15	16.417	2.40	22.42	1.60
4.500	2.14	10.500	6.15	16.500	2.40	22.50	1.60
4.583	2.14	10.583	8.28	16.583	2.40	22.58	1.60
4.667	2.14	10.667	8.28	16.667	2.40	22.67	1.60
4.750	2.14	10.750	8.28	16.750	2.40	22.75	1.60
4.833	2.14	10.833	8.28	16.833	2.40	22.83	1.60
4.917	2.14	10.917	8.28	16.917	2.40	22.92	1.60
5.000	2.14	11.000	8.28	17.000	2.40	23.00	1.60
5.083	2.14	11.083	12.83	17.083	2.40	23.08	1.60
5.167	2.14	11.167	12.83	17.167	2.40	23.17	1.60
5.250	2.14	11.250	12.83	17.250	2.40	23.25	1.60
5.333	2.14	11.333	12.83	17.333	2.40	23.33	1.60
5.417	2.14	11.417	12.83	17.417	2.40	23.42	1.60
5.500	2.14	11.500	12.83	17.500	2.40	23.50	1.60
5.583	2.14	11.583	55.57	17.583	2.40	23.58	1.60
5.667	2.14	11.667	55.58	17.667	2.40	23.67	1.60
5.750	2.14	11.750	55.58	17.750	2.40	23.75	1.60

5.833	2.14	11.833	147.48	17.833	2.40	23.83	1.60
5.917	2.14	11.917	147.49	17.917	2.40	23.92	1.60
6.000	2.14	12.000	147.49	18.000	2.40	24.00	1.60

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.044 (i)
 TIME TO PEAK (hrs)= 12.083
 RUNOFF VOLUME (mm)= 72.257
 TOTAL RAINFALL (mm)= 133.600
 RUNOFF COEFFICIENT = 0.541

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
 STANDHYD (0200)
 ID= 1 DT= 5.0 min

Area (ha)= 9.68
 Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	1.34	6.083	2.67	12.083	19.25	18.08	2.40
0.167	1.34	6.167	2.67	12.167	19.24	18.17	2.40
0.250	1.34	6.250	2.67	12.250	19.24	18.25	2.40
0.333	1.34	6.333	2.67	12.333	19.24	18.33	2.40
0.417	1.34	6.417	2.67	12.417	19.24	18.42	2.40
0.500	1.34	6.500	2.67	12.500	19.24	18.50	2.40
0.583	1.34	6.583	2.67	12.583	9.89	18.58	2.40
0.667	1.34	6.667	2.67	12.667	9.89	18.67	2.40
0.750	1.34	6.750	2.67	12.750	9.89	18.75	2.40
0.833	1.34	6.833	2.67	12.833	9.89	18.83	2.40
0.917	1.34	6.917	2.67	12.917	9.89	18.92	2.40
1.000	1.34	7.000	2.67	13.000	9.89	19.00	2.40
1.083	1.34	7.083	2.67	13.083	1.87	19.08	2.40
1.167	1.34	7.167	2.67	13.167	1.87	19.17	2.40
1.250	1.34	7.250	2.67	13.250	1.87	19.25	2.40
1.333	1.34	7.333	2.67	13.333	1.87	19.33	2.40
1.417	1.34	7.417	2.67	13.417	1.87	19.42	2.40
1.500	1.34	7.500	2.67	13.500	1.87	19.50	2.40
1.583	1.34	7.583	2.67	13.583	10.95	19.58	2.40
1.667	1.34	7.667	2.67	13.667	10.96	19.67	2.40
1.750	1.34	7.750	2.67	13.750	10.96	19.75	2.40
1.833	2.40	7.833	2.67	13.833	10.96	19.83	2.40
1.917	2.40	7.917	2.67	13.917	10.96	19.92	2.40
2.000	2.40	8.000	2.67	14.000	10.96	20.00	2.40
2.083	1.74	8.083	3.61	14.083	4.01	20.08	1.60
2.167	1.74	8.167	3.61	14.167	4.01	20.17	1.60
2.250	1.74	8.250	3.61	14.250	4.01	20.25	1.60
2.333	1.74	8.333	3.61	14.333	4.01	20.33	1.60
2.417	1.74	8.417	3.61	14.417	4.01	20.42	1.60
2.500	1.74	8.500	3.61	14.500	4.01	20.50	1.60
2.583	1.74	8.583	3.61	14.583	4.01	20.58	1.60

2.667	1.74	8.667	3.61	14.667	4.01	20.67	1.60
2.750	1.74	8.750	3.61	14.750	4.01	20.75	1.60
2.833	1.74	8.833	3.61	14.833	4.01	20.83	1.60
2.917	1.74	8.917	3.61	14.917	4.01	20.92	1.60
3.000	1.74	9.000	3.61	15.000	4.01	21.00	1.60
3.083	1.74	9.083	4.28	15.083	4.01	21.08	1.60
3.167	1.74	9.167	4.28	15.167	4.01	21.17	1.60
3.250	1.74	9.250	4.28	15.250	4.01	21.25	1.60
3.333	1.74	9.333	4.28	15.333	4.01	21.33	1.60
3.417	1.74	9.417	4.28	15.417	4.01	21.42	1.60
3.500	1.74	9.500	4.28	15.500	4.01	21.50	1.60
3.583	1.74	9.583	4.81	15.583	4.01	21.58	1.60
3.667	1.74	9.667	4.81	15.667	4.01	21.67	1.60
3.750	1.74	9.750	4.81	15.750	4.01	21.75	1.60
3.833	1.74	9.833	4.81	15.833	4.01	21.83	1.60
3.917	1.74	9.917	4.81	15.917	4.01	21.92	1.60
4.000	1.74	10.000	4.81	16.000	4.01	22.00	1.60
4.083	2.14	10.083	6.15	16.083	2.41	22.08	1.60
4.167	2.14	10.167	6.15	16.167	2.40	22.17	1.60
4.250	2.14	10.250	6.15	16.250	2.40	22.25	1.60
4.333	2.14	10.333	6.15	16.333	2.40	22.33	1.60
4.417	2.14	10.417	6.15	16.417	2.40	22.42	1.60
4.500	2.14	10.500	6.15	16.500	2.40	22.50	1.60
4.583	2.14	10.583	8.28	16.583	2.40	22.58	1.60
4.667	2.14	10.667	8.28	16.667	2.40	22.67	1.60
4.750	2.14	10.750	8.28	16.750	2.40	22.75	1.60
4.833	2.14	10.833	8.28	16.833	2.40	22.83	1.60
4.917	2.14	10.917	8.28	16.917	2.40	22.92	1.60
5.000	2.14	11.000	8.28	17.000	2.40	23.00	1.60
5.083	2.14	11.083	12.83	17.083	2.40	23.08	1.60
5.167	2.14	11.167	12.83	17.167	2.40	23.17	1.60
5.250	2.14	11.250	12.83	17.250	2.40	23.25	1.60
5.333	2.14	11.333	12.83	17.333	2.40	23.33	1.60
5.417	2.14	11.417	12.83	17.417	2.40	23.42	1.60
5.500	2.14	11.500	12.83	17.500	2.40	23.50	1.60
5.583	2.14	11.583	55.57	17.583	2.40	23.58	1.60
5.667	2.14	11.667	55.58	17.667	2.40	23.67	1.60
5.750	2.14	11.750	55.58	17.750	2.40	23.75	1.60
5.833	2.14	11.833	147.48	17.833	2.40	23.83	1.60
5.917	2.14	11.917	147.49	17.917	2.40	23.92	1.60
6.000	2.14	12.000	147.49	18.000	2.40	24.00	1.60

Max.Eff.Inten.(mm/hr)=	147.49	91.37
over (min)	5.00	10.00
Storage Coeff. (min)=	3.83 (ii)	9.21 (ii)
Unit Hyd. Tpeak (min)=	5.00	10.00
Unit Hyd. peak (cms)=	0.25	0.12

TOTALS

PEAK FLOW (cms)=	0.82	1.46	2.280 (iii)
TIME TO PEAK (hrs)=	12.00	12.00	12.00
RUNOFF VOLUME (mm)=	132.60	68.14	81.67
TOTAL RAINFALL (mm)=	133.60	133.60	133.60
RUNOFF COEFFICIENT =	0.99	0.51	0.61

***** WARNING: STORAGE COEFF. IS SMALLER THAN TIME STEP!

- (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 69.0 Ia = Dep. Storage (Above)
- (ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
- (iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

```

| RESERVOIR( 0300) |
| IN= 2---> OUT= 1 |
| DT= 5.0 min      |
|-----|

```

OVERFLOW IS OFF

OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
0.0000	0.0000	0.7200	0.1600
0.0500	0.0500	0.7300	0.1800
0.1500	0.0700	0.8600	0.1850
0.3000	0.0900	0.9500	0.1900
0.4200	0.1200	0.9900	0.1950
0.5500	0.1300	1.1900	0.2300
0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	2.280	12.00	81.67
OUTFLOW: ID= 1 (0300)	9.680	1.152	12.17	81.65

PEAK FLOW REDUCTION [Qout/Qin](%)= 50.51
 TIME SHIFT OF PEAK FLOW (min)= 10.00
 MAXIMUM STORAGE USED (ha.m.)= 0.2243

```

|-----|
| ADD HYD ( 0400) |
| 1 + 2 = 3       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.138	12.08	73.35
+ ID2= 2 (0202):	0.24	0.044	12.08	72.26
=====				
ID = 3 (0400):	1.05	0.182	12.08	73.10

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

```

|-----|
| ADD HYD ( 0400) |
| 3 + 2 = 1       |
|-----|

```

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.182	12.08	73.10
+ ID2= 2 (0300):	9.68	1.152	12.17	81.65
=====				
ID = 1 (0400):	10.73	1.316	12.17	80.81

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

V V I SSSSS U U A L (v 6.2.2015)
V V I SS U U A A L
V V I SS U U AAAAA L
V V I SS U U A A L
VV I SSSSS UUUUU A A LLLLL

000 TTTTT TTTTT H H Y Y M M 000 TM
O O T T H H Y Y MM MM O O
O O T T H H Y M M O O
000 T T H H Y M M 000

Developed and Distributed by Smart City Water Inc
Copyright 2007 - 2022 Smart City Water Inc
All rights reserved.

***** D E T A I L E D O U T P U T *****

Input filename: C:\Program Files (x86)\Visual OTTHYMO 6.2\VO2\voin.dat
Output filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\5a76a84d-15ab-44ca-8e16-455bd150b21d\scen
Summary filename: C:\Users\nparmar\AppData\Local\Civica\XH5\eaed411-b099-4108-b6b0-cc0fca6dc942\5a76a84d-15ab-44ca-8e16-455bd150b21d\scen

DATE: 02-23-2024

TIME: 08:29:45

USER:

COMMENTS: _____

** SIMULATION : Run 13 **

READ STORM	Filename: C:\Users\nparmar\AppData\Local\Temp\123993b6-6ef8-4a48-a7fe-3c00e668a813\b0a73a8f
Ptotal=193.00 mm	Comments: REGIONAL STORM TIMMINS - 12 hour storm

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
0.00	15.00	3.00	3.00	6.00	43.00	9.00	13.00
1.00	20.00	4.00	5.00	7.00	20.00	10.00	13.00
2.00	10.00	5.00	20.00	8.00	23.00	11.00	8.00

CALIB	Area (ha)=	0.81	Curve Number (CN)=	74.0
NASHYD (0201)	Ia (mm)=	8.00	# of Linear Res.(N)=	3.00
ID= 1 DT= 5.0 min	U.H. Tp(hrs)=	0.23		

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----							
TIME	RAIN	TIME	RAIN	TIME	RAIN	TIME	RAIN
hrs	mm/hr	hrs	mm/hr	hrs	mm/hr	hrs	mm/hr
0.083	15.00	3.083	3.00	6.083	43.00	9.08	13.00
0.167	15.00	3.167	3.00	6.167	43.00	9.17	13.00
0.250	15.00	3.250	3.00	6.250	43.00	9.25	13.00
0.333	15.00	3.333	3.00	6.333	43.00	9.33	13.00
0.417	15.00	3.417	3.00	6.417	43.00	9.42	13.00
0.500	15.00	3.500	3.00	6.500	43.00	9.50	13.00
0.583	15.00	3.583	3.00	6.583	43.00	9.58	13.00
0.667	15.00	3.667	3.00	6.667	43.00	9.67	13.00
0.750	15.00	3.750	3.00	6.750	43.00	9.75	13.00
0.833	15.00	3.833	3.00	6.833	43.00	9.83	13.00
0.917	15.00	3.917	3.00	6.917	43.00	9.92	13.00
1.000	15.00	4.000	3.00	7.000	43.00	10.00	13.00
1.083	20.00	4.083	5.00	7.083	20.00	10.08	13.00
1.167	20.00	4.167	5.00	7.167	20.00	10.17	13.00
1.250	20.00	4.250	5.00	7.250	20.00	10.25	13.00
1.333	20.00	4.333	5.00	7.333	20.00	10.33	13.00
1.417	20.00	4.417	5.00	7.417	20.00	10.42	13.00
1.500	20.00	4.500	5.00	7.500	20.00	10.50	13.00
1.583	20.00	4.583	5.00	7.583	20.00	10.58	13.00
1.667	20.00	4.667	5.00	7.667	20.00	10.67	13.00
1.750	20.00	4.750	5.00	7.750	20.00	10.75	13.00
1.833	20.00	4.833	5.00	7.833	20.00	10.83	13.00
1.917	20.00	4.917	5.00	7.917	20.00	10.92	13.00
2.000	20.00	5.000	5.00	8.000	20.00	11.00	13.00
2.083	10.00	5.083	20.00	8.083	23.00	11.08	8.00
2.167	10.00	5.167	20.00	8.167	23.00	11.17	8.00
2.250	10.00	5.250	20.00	8.250	23.00	11.25	8.00
2.333	10.00	5.333	20.00	8.333	23.00	11.33	8.00
2.417	10.00	5.417	20.00	8.417	23.00	11.42	8.00
2.500	10.00	5.500	20.00	8.500	23.00	11.50	8.00
2.583	10.00	5.583	20.00	8.583	23.00	11.58	8.00
2.667	10.00	5.667	20.00	8.667	23.00	11.67	8.00
2.750	10.00	5.750	20.00	8.750	23.00	11.75	8.00
2.833	10.00	5.833	20.00	8.833	23.00	11.83	8.00
2.917	10.00	5.917	20.00	8.917	23.00	11.92	8.00
3.000	10.00	6.000	20.00	9.000	23.00	12.00	8.00

Unit Hyd Qpeak (cms)= 0.135

PEAK FLOW (cms)= 0.074 (i)

TIME TO PEAK (hrs)= 7.000

RUNOFF VOLUME (mm)= 124.660

TOTAL RAINFALL (mm)= 193.000

RUNOFF COEFFICIENT = 0.646

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB			
NASHYD (0202)	Area (ha)=	0.24	Curve Number (CN)= 73.0
ID= 1 DT= 5.0 min	Ia (mm)=	7.30	# of Linear Res.(N)= 3.00
	U.H. Tp(hrs)=	0.19	

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
0.083	15.00	3.083	3.00	6.083	43.00	9.08	13.00
0.167	15.00	3.167	3.00	6.167	43.00	9.17	13.00
0.250	15.00	3.250	3.00	6.250	43.00	9.25	13.00
0.333	15.00	3.333	3.00	6.333	43.00	9.33	13.00
0.417	15.00	3.417	3.00	6.417	43.00	9.42	13.00
0.500	15.00	3.500	3.00	6.500	43.00	9.50	13.00
0.583	15.00	3.583	3.00	6.583	43.00	9.58	13.00
0.667	15.00	3.667	3.00	6.667	43.00	9.67	13.00
0.750	15.00	3.750	3.00	6.750	43.00	9.75	13.00
0.833	15.00	3.833	3.00	6.833	43.00	9.83	13.00
0.917	15.00	3.917	3.00	6.917	43.00	9.92	13.00
1.000	15.00	4.000	3.00	7.000	43.00	10.00	13.00
1.083	20.00	4.083	5.00	7.083	20.00	10.08	13.00
1.167	20.00	4.167	5.00	7.167	20.00	10.17	13.00
1.250	20.00	4.250	5.00	7.250	20.00	10.25	13.00
1.333	20.00	4.333	5.00	7.333	20.00	10.33	13.00
1.417	20.00	4.417	5.00	7.417	20.00	10.42	13.00
1.500	20.00	4.500	5.00	7.500	20.00	10.50	13.00
1.583	20.00	4.583	5.00	7.583	20.00	10.58	13.00
1.667	20.00	4.667	5.00	7.667	20.00	10.67	13.00
1.750	20.00	4.750	5.00	7.750	20.00	10.75	13.00
1.833	20.00	4.833	5.00	7.833	20.00	10.83	13.00
1.917	20.00	4.917	5.00	7.917	20.00	10.92	13.00
2.000	20.00	5.000	5.00	8.000	20.00	11.00	13.00
2.083	10.00	5.083	20.00	8.083	23.00	11.08	8.00
2.167	10.00	5.167	20.00	8.167	23.00	11.17	8.00
2.250	10.00	5.250	20.00	8.250	23.00	11.25	8.00
2.333	10.00	5.333	20.00	8.333	23.00	11.33	8.00
2.417	10.00	5.417	20.00	8.417	23.00	11.42	8.00
2.500	10.00	5.500	20.00	8.500	23.00	11.50	8.00
2.583	10.00	5.583	20.00	8.583	23.00	11.58	8.00
2.667	10.00	5.667	20.00	8.667	23.00	11.67	8.00
2.750	10.00	5.750	20.00	8.750	23.00	11.75	8.00
2.833	10.00	5.833	20.00	8.833	23.00	11.83	8.00
2.917	10.00	5.917	20.00	8.917	23.00	11.92	8.00
3.000	10.00	6.000	20.00	9.000	23.00	12.00	8.00

Unit Hyd Qpeak (cms)= 0.048

PEAK FLOW (cms)= 0.022 (i)

TIME TO PEAK (hrs)= 7.000

RUNOFF VOLUME (mm)= 123.027

TOTAL RAINFALL (mm)= 193.000

RUNOFF COEFFICIENT = 0.637

(i) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

CALIB
STANDHYD (0200)
ID= 1 DT= 5.0 min

Area (ha)= 9.68
Total Imp(%)= 21.00 Dir. Conn.(%)= 21.00

		IMPERVIOUS	PERVIOUS (i)
Surface Area	(ha)=	2.03	7.65
Dep. Storage	(mm)=	1.00	5.00
Average Slope	(%)=	1.00	2.00
Length	(m)=	254.03	40.00
Mannings n	=	0.013	0.150

NOTE: RAINFALL WAS TRANSFORMED TO 5.0 MIN. TIME STEP.

----- TRANSFORMED HYETOGRAPH -----

TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr	TIME hrs	RAIN mm/hr
0.083	15.00	3.083	3.00	6.083	43.00	9.08	13.00
0.167	15.00	3.167	3.00	6.167	43.00	9.17	13.00
0.250	15.00	3.250	3.00	6.250	43.00	9.25	13.00
0.333	15.00	3.333	3.00	6.333	43.00	9.33	13.00
0.417	15.00	3.417	3.00	6.417	43.00	9.42	13.00
0.500	15.00	3.500	3.00	6.500	43.00	9.50	13.00
0.583	15.00	3.583	3.00	6.583	43.00	9.58	13.00
0.667	15.00	3.667	3.00	6.667	43.00	9.67	13.00
0.750	15.00	3.750	3.00	6.750	43.00	9.75	13.00
0.833	15.00	3.833	3.00	6.833	43.00	9.83	13.00
0.917	15.00	3.917	3.00	6.917	43.00	9.92	13.00
1.000	15.00	4.000	3.00	7.000	43.00	10.00	13.00
1.083	20.00	4.083	5.00	7.083	20.00	10.08	13.00
1.167	20.00	4.167	5.00	7.167	20.00	10.17	13.00
1.250	20.00	4.250	5.00	7.250	20.00	10.25	13.00
1.333	20.00	4.333	5.00	7.333	20.00	10.33	13.00
1.417	20.00	4.417	5.00	7.417	20.00	10.42	13.00
1.500	20.00	4.500	5.00	7.500	20.00	10.50	13.00
1.583	20.00	4.583	5.00	7.583	20.00	10.58	13.00
1.667	20.00	4.667	5.00	7.667	20.00	10.67	13.00
1.750	20.00	4.750	5.00	7.750	20.00	10.75	13.00
1.833	20.00	4.833	5.00	7.833	20.00	10.83	13.00
1.917	20.00	4.917	5.00	7.917	20.00	10.92	13.00
2.000	20.00	5.000	5.00	8.000	20.00	11.00	13.00
2.083	10.00	5.083	20.00	8.083	23.00	11.08	8.00
2.167	10.00	5.167	20.00	8.167	23.00	11.17	8.00
2.250	10.00	5.250	20.00	8.250	23.00	11.25	8.00
2.333	10.00	5.333	20.00	8.333	23.00	11.33	8.00
2.417	10.00	5.417	20.00	8.417	23.00	11.42	8.00
2.500	10.00	5.500	20.00	8.500	23.00	11.50	8.00
2.583	10.00	5.583	20.00	8.583	23.00	11.58	8.00
2.667	10.00	5.667	20.00	8.667	23.00	11.67	8.00
2.750	10.00	5.750	20.00	8.750	23.00	11.75	8.00
2.833	10.00	5.833	20.00	8.833	23.00	11.83	8.00
2.917	10.00	5.917	20.00	8.917	23.00	11.92	8.00
3.000	10.00	6.000	20.00	9.000	23.00	12.00	8.00

Max.Eff.Inten.(mm/hr)= 43.00 31.59
over (min) 5.00 15.00
Storage Coeff. (min)= 6.26 (ii) 14.50 (ii)
Unit Hyd. Tpeak (min)= 5.00 15.00
Unit Hyd. peak (cms)= 0.19 0.08

PEAK FLOW (cms)= 0.24 0.64
TIME TO PEAK (hrs)= 7.00 7.00
RUNOFF VOLUME (mm)= 192.00 116.99
TOTAL RAINFALL (mm)= 193.00 193.00
RUNOFF COEFFICIENT = 0.99 0.61

TOTALS
0.879 (iii)

- (i) CN PROCEDURE SELECTED FOR PERVIOUS LOSSES:
CN* = 69.0 Ia = Dep. Storage (Above)
(ii) TIME STEP (DT) SHOULD BE SMALLER OR EQUAL
THAN THE STORAGE COEFFICIENT.
(iii) PEAK FLOW DOES NOT INCLUDE BASEFLOW IF ANY.

| RESERVOIR(0300) |
| IN= 2---> OUT= 1 |

OVERFLOW IS OFF

DT= 5.0 min	OUTFLOW (cms)	STORAGE (ha.m.)	OUTFLOW (cms)	STORAGE (ha.m.)
	0.0000	0.0000	0.7200	0.1600
	0.0500	0.0500	0.7300	0.1800
	0.1500	0.0700	0.8600	0.1850
	0.3000	0.0900	0.9500	0.1900
	0.4200	0.1200	0.9900	0.1950
	0.5500	0.1300	1.1900	0.2300
	0.5900	0.1500	1.4000	0.2550

	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
INFLOW : ID= 2 (0200)	9.680	0.879	7.00	132.74
OUTFLOW: ID= 1 (0300)	9.680	0.725	7.17	132.71

PEAK FLOW REDUCTION [Qout/Qin](%)= 82.51
 TIME SHIFT OF PEAK FLOW (min)= 10.00
 MAXIMUM STORAGE USED (ha.m.)= 0.1705

ADD HYD (0400) 1 + 2 = 3	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 1 (0201):	0.81	0.074	7.00	124.66
+ ID2= 2 (0202):	0.24	0.022	7.00	123.03
=====				
ID = 3 (0400):	1.05	0.095	7.00	124.29

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.

ADD HYD (0400) 3 + 2 = 1	AREA (ha)	QPEAK (cms)	TPEAK (hrs)	R.V. (mm)
ID1= 3 (0400):	1.05	0.095	7.00	124.29
+ ID2= 2 (0300):	9.68	0.725	7.17	132.71
=====				
ID = 1 (0400):	10.73	0.818	7.00	131.89

NOTE: PEAK FLOWS DO NOT INCLUDE BASEFLOWS IF ANY.



APPENDIX E

PHOSPHOROUS BUDGET CALCULATIONS

Development Export Summary

Development :23008 - GSP Horning's Mill

Updated : Sept 2014

Pre-Development Phosphorus Export

DEVELOPMENT : 23008 - GSP Horning's Mill			
Landuse	Area (ha)	P coeff (kg/ha)	Pload (kg/yr)
Natural Heritage			
Forest	1.00	0.06	0.06
Hay/Pasture	9.17	0.08	0.73
Natural Heritage Land use Class Total :		10.17	0.79
Development Total :		10.17	0.79

2/22/2024

Page 1 of 1

Updated : Sept 2014

Cropland Site Sediment & Phosphorus Pre-Development Export

DEVELOPMENT : 23008 - GSP Horning's Mill			
COLOUR KEY :	Site Specific Input	Constant / Lookup	Calculation
SubArea :			

Slope Area (ha)	R (rainfall / runoff for Lake Simcoe)
Surface Slope Gradient (%)	K (soil erodability factor)
Length of Slope (m)	NN (determined by slope)
Cropt Type Factor)	LS (slope length gradient factor)
Tillage Type Factor	C (crop management factor)
	P (prevention + capture)
	Soil Loss (kg/year)
	Phosphorus export (kg/ha/yr)
	Phosphorus load (kg/yr)

PRE Developed Area (ha) :

Phosphorus export (kg/ha/yr) :

Phosphorus load (kg/yr) :

2/22/2024

Page 1 of 1

Post-Development Phosphorus Export

DEVELOPMENT : 23008 - GSP Horning's Mill

Landuse	Area (ha)	P coeff (kg/ha)	Pload (kg/yr)
Natural Heritage			
Hay/Pasture	0.82	0.08	0.07
Natural Heritage Land use Class Total :		0.82	0.07
Urban			
Residential	0.23	0.41	0.05
Residential	0.83	0.41	1.09
Residential	8.29	0.41	1.99
Urban Land use Class Total :		9.35	3.13
Development Total :		10.17	3.20

2/22/2024

Page 1 of 1

Updated : Sept 2014

Cropland Site Sediment & Phosphorus Post-Development Export

DEVELOPMENT : 23008 - GSP Horning's Mill

COLOUR KEY :	Site Specific Input	Constant / Lookup	Calculation
SubArea :			

Slope Area (ha)	R (rainfall / runoff for Lake Simcoe)
Surface Slope Gradient (%)	K (soil erodability factor)
Length of Slope (m)	NN (determined by slope)
Cropt Type Factor)	LS (slope length gradient factor)
Tillage Type Factor	C (crop management factor)
	P (prevention + capture)
	Soil Loss (kg/year)
	Phosphorus export (kg/ha/yr)
	Phosphorus load (kg/yr)

PRE Developed Area (ha) :

Phosphorus export (kg/ha/yr) :

Phosphorus load (kg/yr) :

2/22/2024

Page 1 of 1

GSP Inc., Horning's Mill Phosphorus Budget

Pre-Development Condition

Total Pre-Development P (kg/yr)	0.79	(Taken from NVCA Phosphorous Tool)
---------------------------------	------	------------------------------------

Post-Development Condition (Uncontrolled):

Total Uncontrolled Post-Development (kg/yr):	3.20	(Taken from NVCA Phosphorous Tool)
--	------	------------------------------------

Post Development Condition (Controlled)

Without Treatment

Total (kg/yr):	0.12	
----------------	------	--

RooftopArea Draining to Soakaway Pits

Total P (kg/yr):	1.09	
Soakaway Pits Proficiency (%):	71	
P Removed (kg/yr):	0.77	
P Remaining (kg/yr):	0.32	

Area Draining to Dry Pond

Total P (kg/yr):	=	1.99 + 0.32	(Taken from NVCA Phosphorous Tool ID 15534)
Total P (kg/yr):		2.31	
Dry Pond Proficiency (%):		10	
P Removed (kg/yr):		0.23	
P Remaining (kg/yr):		2.08	

Area Draining to OGS

Total P (kg):	2.08	
OGS Proficiency (%):	20	
P Removed (kg):	0.42	
P Remaining (kg):	1.66	

Total Site P (kg):	1.78	
--------------------	------	--



APPENDIX F

WATER BALANCE CALCULATIONS

GSP Inc., Horning's Mill Water Balance Calculations

Pre-Development Recharge:

Precipitation data taken from Environment Canada information for the Town of Orangeville

$$\text{Yearly Precipitation} = 901.5 \text{ mm}$$

Using Table 3.1 of the MOE's SWM Planning & Design Manual, the infiltration amount is approximately 29.1% of the precipitation value for Mature Forest and 25.6% of the Moderately Rooted Crops for Fine Sandy Loam. Using site specific rainfall data, the infiltration can be calculated.

$$\begin{aligned} \text{Mature Forest} &= 1.01 \text{ ha} \\ \text{Cultivated Area} &= 10.24 \text{ ha} \\ \text{Annual Site Area Recharge Volume} &= (1.01 \times 0.29 + 10.08 \times 0.26) \times 901.5 \\ &= 26,294 \text{ m}^3 \end{aligned}$$

Therefore, 26,294 m³ per year of recharge volume is required for the proposed project.

Post-Development Recharge:

Using Table 3.1 of the MOE's SWM Planning & Design Manual, the infiltration amount is approximately 24.3% of the precipitation value for Urban Lawn and approximately 25.6% of Moderately Rooted Crops was considered.

$$\begin{aligned} \text{Grassed Area} &= 8.68 \text{ ha} \\ \text{Cultivated Area} &= 1.04 \text{ ha} \\ \text{Annual Site Area Recharge Volume} &= (8.66 \times 0.24 + 0.89 \times 0.26) \times 901.5 \\ &= 21,207 \text{ m}^3 \end{aligned}$$

Therefore, post-development infiltration deficit is as follows:

$$\begin{aligned} \text{Deficit Volume} &= \text{Pre Development} - \text{Post Development} \\ &= 26,294 - 21,207 \\ &= 5,088 \text{ m}^3 \end{aligned}$$

Roof Top Infiltration:

Find the depth of annual rainfall required to infiltrate 5088 m³ from the rooftops into the ground.

$$\begin{aligned} \text{Area Contributing to the Infiltration Locations} &= 8,320 \text{ m}^2 \\ \text{Infiltration Deficit} &= 5,088 \text{ m}^3 \end{aligned}$$

Annual Precipitation Depth Required

$$\begin{aligned} \text{Required Precipitation Depth} &= \frac{5,088 \text{ m}^3}{8,320 \text{ m}^2} \\ &= 611.5 \text{ mm} \end{aligned}$$

The runoff coefficient for the contributing area is 0.95, the precipitation depth required to get 611.5 mm of runoff is:

$$\begin{aligned} \text{Precipitation Depth} &= \frac{611.5 \text{ mm}}{0.95} \\ &= 643.7 \text{ mm} \end{aligned}$$

Find Percent of Annual Precipitation that Required Precipitation Depth represents:

$$\begin{array}{rcl}
 \text{Annual Precipitation for Study Area} & = & 901.5 \text{ mm} \\
 \text{\% Annual Rainfall} & = & \frac{643.7}{901.5} \text{ mm} \\
 & = & 71\%
 \end{array}$$

From MOE Figure C-2, 71% of annual rainfall occurs for storm events of 10 mm or less.

$$\begin{array}{rcl}
 \text{Contributing Area} & = & 8,320 \text{ m}^2 \\
 \text{Precipitation Depth} & = & 10 \text{ mm} \\
 \text{Storage Volume Required} & = & A \times D \\
 & = & 8,320 \times 10 \\
 & = & 83 \text{ m}^3
 \end{array}$$

The site will require a minimum infiltration volume of 83 m³ and will be provided using soakaway pits.



**GSP Inc., Horning's Mill
Soakaway Pit Infiltration Calculations**

Storage Volume Required Using 10 mm Storm Event as per Water Balance Calculations:

$$\begin{aligned}\text{Roof Area (A)} &= 8,320 \text{ m}^2 \\ \text{Storm Event (D)} &= 10 \text{ mm} \\ \text{Total Volume Required (V)} &= A \times D \\ &= 8,320 \times 10 \\ \text{Total Volume Required (V)} &= 83 \text{ m}^3\end{aligned}$$

Storage Volume Provided Using 25 mm Storm Event as per Water Balance Calculations:

$$\begin{aligned}\text{Number of Houses} &= 26 \text{ lots} \\ \text{Average Roof Area per Soakaway Pit} &= 320 \text{ m}^2 \\ \text{Soakaway Pit Volume Required (V)} &= A \times D \\ &= 320 \times 10 \\ &= 3.20 \text{ m}^3 \\ \text{Soakaway Pit Volume Provided (V)} &= 3.80 \text{ m}^3 \\ \text{Total Volume Provided (V)} &= 98.8 \text{ m}^3\end{aligned}$$

MECP Maximum Allowable Soakaway Pit Depth:

$$\begin{aligned}\text{Percolation (P)} &= 22 \text{ mm/hr} \\ \text{Drawdown Time (T)} &= 36 \text{ hr} \\ \text{Maximum Depth (d)} &= \frac{PT}{1,000} \\ &= 0.79 \text{ m}\end{aligned}$$

(Average Estimated Percolation Rate Based on the Hydrogeological Assessment Grain Size Analysis)

MECP Required Soakaway Pit Bottom Area:

$$\begin{aligned}\text{Percolation (P)} &= 22 \text{ mm/hr} \\ \text{Porosity Of The Storage Material (n)} &= 0.40 \text{ (for Clear Stone)} \\ \text{Runoff Volume to be Infiltrated (V)} &= 83 \text{ m}^3 \\ \text{Retention Time (\Delta t)} &= 48 \text{ hr} \\ \text{Soakaway Pit Bottom Area Required (A)} &= \frac{1000V}{Pn\Delta t} \\ &= 197 \text{ m}^2 \\ \text{Total Soakaway Pit Bottom Area Provided} &= 198 \text{ m}^2\end{aligned}$$



APPENDIX G

GEOTECHNICAL INVESTIGATION REPORT, CAMBIUM INC., MARCH 11TH, 2024



Geotechnical Investigation Report - 537086 Main Street, Horning's Mills, Ontario

March 11, 2024

Prepared for:
Angelo Carnevale

Cambium Reference: 17217-001

CAMBIUM INC.

866.217.7900

cambium-inc.com

Peterborough | Barrie | Oshawa | Kingston



Table of Contents

1.0	Introduction.....	1
1.1	Reviewed Documents	1
1.2	Standards and Guidelines	1
2.0	Site and Project Description	2
2.1	Site Description	2
2.2	Project Description	2
3.0	Methodology	3
3.1	Borehole Investigation	3
3.2	Site Survey	3
3.3	Physical Laboratory Testing	4
4.0	Subsurface Conditions	5
4.1	Regional Geology	5
4.2	Surficial Soils	6
4.3	Non-Cohesive Deposits	7
4.4	Cohesive Deposits	8
4.5	Bedrock	8
4.6	Groundwater	8
4.7	Percolation Rates	9
5.0	Slope Stability and Karst Assessments	11
5.1	Slope Stability Assessment	11
5.2	Karst Assessment	13
6.0	Geotechnical Considerations	17
6.1	Site Preparation	17
6.2	Frost Penetration	18
6.3	Excavations	18
6.4	Groundwater Control and Dewatering	19



6.5	Foundation Design	20
6.5.1	Conventional Shallow Footings	20
6.5.2	Floor Slabs	21
6.6	Backfill and Compaction	22
6.6.1	Engineered Fill	23
6.7	Subdrainage	24
6.8	Buried Utilities	24
6.9	Lateral Earth Pressure	24
6.10	Pavement Design	25
7.0	Report Limitations	27
7.1	Design Review and Inspections	27
7.2	Changes in Site and Project Scope	27
8.0	Closing	28

List of Embedded Figures

Embedded Figure 1: Quaternary geologic mapping	6
Embedded Figure 2: Karst mapping	14
Embedded Figure 3: Drift thickness mapping	15

List of Appended Figures

Figure 1	Site Location Plan
Figure 2	Borehole Location Plan

List of Tables

Table 1	Particle Size Distribution – Non-Cohesive Deposits
Table 2	Particle Size Distribution – Cohesive Deposits
Table 3	Groundwater Observations During Monitoring Events
Table 4	Estimated Percolation Rates
Table 5	Slope Stability Rating Chart – Results



Table 6 Lateral Earth Pressure Coefficients

Table 7 Minimum Pavement Structure

List of Appendices

Appendix A Borehole Logs

Appendix B Physical Laboratory Testing Results

Appendix C Slope Stability Rating Charts

Appendix D Site Photographs



1.0 Introduction

Cambium Inc. (Cambium) was retained by Angelo Carnevale (Client) to complete a geotechnical investigation in support of a proposed residential development located at 537086 Main Street in Horning's Mills, Township of Melancthon, Ontario (Site).

This report presents and summarizes the methodology and findings of the geotechnical investigation conducted by Cambium at the Site. Based on the results of the investigation, geotechnical engineering recommendations relevant to the proposed development are provided. In addition, the results of visual slope stability and karst assessments conducted by Cambium at the Site are presented in this report.

1.1 Reviewed Documents

The following project documents were received and reviewed during the drafting of this report:

[1] GSP Group Inc. – Kitchener, Ontario

Development Concept – 537080 Main Street, Horning's Mills; 1:2000; Project No. 22028; February 2, 2022.

[2] Van Harten Surveying Inc. – Orangeville, Ontario

Lot 13, Concession 2 – Preliminary Topo (32159-23) UTM 2010; received by email on May 4, 2023.

1.2 Standards and Guidelines

Applicable standards, guidelines and other normative documents utilized in preparing geotechnical engineering recommendations for this report are provided below.

[3] Canadian Foundation Engineering Manual – 4th Edition; Canadian Geotechnical Society; 2006.

[4] Technical Guide – River & Stream Systems: Erosion Hazard Limit; Ontario Ministry of Natural Resources; 2002.



2.0 Site and Project Description

2.1 Site Description

The Site covers an area of approximately 10.2 acres and is bordered by Dufferin County Road 124 to the west, Main Street to the east, and on all other sides by both vacant and residentially developed properties. The current parcel is vacant and used for agricultural purposes. The adjoining parcel on the eastern side of the property with the civic address 537080 Main Street is developed with a residential dwelling and a barn structure.

The ground elevation at the Site generally falls from west to east, from a maximum elevation of around 482 m above sea level (mASL) along the western property line bordering County Road 124 to elevations around 458 mASL along the eastern property line bordering Main Street. The ground elevation predominantly falls at shallow inclinations (approximately 20H:1V) throughout the property, at times steepening to inclinations of about 10H:1V.

Two defined slope areas exist within the Site, with one slope area along the eastern property line bordering Main Street (height difference of about 4 m to 5 m between the top and bottom of bank based on [2], and maximum inclination approximately 6H:1V) and the second slope area intersecting the southeastern corner of the property (height difference of up to about 4 m, and maximum inclination approximately 5H:1V). Both of the slope areas are regulated by the Nottawasaga Valley Conservation Authority (NVCA) under O.Reg. 172/06 in conjunction with Horning's Mills Creek.

A Site Location Plan is provided as Figure 1 of this report for reference.

2.2 Project Description

Based on the concept plan provided to Cambium [1], the proposed development will consist of 19 separate residential lots, accessed from Main Street by two new roadways. In the southeastern corner of the Site, near Horning's Mills Creek, parkland is currently proposed.

It is understood that the lots will be privately serviced.



3.0 Methodology

3.1 Borehole Investigation

Seven boreholes were advanced throughout the Site on May 11 and 12, 2023, at predetermined locations confirmed with the Client and staked by Cambium during a site visit conducted on May 9, 2023. The boreholes were designated as BH101-23 to BH107-23 and were terminated at depths ranging from 4.5 m below ground surface (mbgs) to 5.2 mbgs.

BH101-23, BH104-23 and BH106-23 were outfitted with monitoring wells to allow for subsequent groundwater level monitoring at the Site.

Borehole drilling and sampling were completed using a track-mounted drill rig operating under the supervision of a Cambium geotechnical analyst. The boreholes were advanced to the sampling depths by means of continuous flight hollow and solid stem augers with 50 mm O.D. split spoon samplers.

Standard Penetration Test (SPT) N values were recorded for the sampled intervals as the number of blows required to drive a split spoon sampler 305 mm into the soil, using a 63.5 kg drop hammer falling 750 mm, as per ASTM D1586 procedures. The SPT N values are used in this report to assess the consistency of cohesive soils and relative density of non-cohesive materials. Soil samples were collected at approximately 0.75 m intervals in the upper 3.0 mbgs and at 1.5 m intervals below that depth.

The encountered soil units were logged in the field using visual and tactile methods, and samples were placed in labelled plastic bags for transport, future reference, laboratory testing, and storage. Borehole logs are provided in Appendix A.

3.2 Site Survey

The borehole coordinates were obtained during the geotechnical investigation using a handheld GPS-enabled device. The approximate borehole elevations were determined by interpolating between 0.25 m contour lines provided on a topographic survey of the property conducted by others [2].



3.3 Physical Laboratory Testing

Physical laboratory testing, including five particle size distribution analyses (LS-702, 705), was completed on selected soil samples to confirm textural classification and to assess geotechnical parameters. Natural moisture content testing (LS-701) was completed on all retrieved soil samples. The physical laboratory testing results are presented in Appendix B and are discussed in Section 4.0.



4.0 Subsurface Conditions


The stratigraphy encountered in the boreholes is indicated on the attached borehole logs in Appendix A. It is noted that the conditions indicated on the borehole logs are for specific locations only and can vary between and beyond the borehole locations. The soil boundaries indicated on the borehole logs are inferred from non-continuous sampling and observations during drilling. These boundaries are intended to reflect approximate transition zones and should not be interpreted as exact planes of geological change. In addition, the descriptions provided in the borehole logs are inferred from a variety of factors, including visual observations of the soil samples retrieved, laboratory testing, measurements prior to and after drilling, and the drilling process itself (drilling speed, shaking/grinding of the augers, etc.).

In general, the encountered subsurface conditions consist of surficial topsoil and silty sand containing organics, primarily underlain by non-cohesive soil deposits.

4.1 Regional Geology

Ontario Geological Survey (OGS) quaternary geologic mapping indicates that the Site is projected to fall within a formation of glaciofluvial ice-contact deposits, including gravel and sand minor till including esker, kame, end moraine, ice-marginal delta and subaqueous fan deposits.

Embedded Figure 1 shows the site (outlined in red) and surrounding quaternary geologic formations.



Embedded Figure 1: Quaternary geologic mapping

4.2 Surficial Soils

A surficial layer of topsoil containing organics was encountered in all boreholes advanced at the Site. The recorded thickness of the topsoil layer varied between 125 mm and 150 mm.

Below the topsoil, a layer of brown silty sand, predominantly containing organics, was encountered in all boreholes. The silty sand containing organics extended to a depth of about 0.8 mbgs and contained trace amounts of gravel and clay.

SPT N values recorded for the surficial soils ranged between 5 and 18, indicating loose to compact relative density. Natural moisture contents determined by laboratory testing ranged between 8.4% and 25.4%.

Assessments of organic matter content or other topsoil quality tests were beyond the scope of this study.



4.3 Non-Cohesive Deposits

Below the surficial soils described above, non-cohesive soil deposits inferred to be native were generally encountered to the termination depths of the boreholes. The composition of the non-cohesive deposits ranged significantly from finer-grained non-cohesive soils (sand and silt, silty sand, sand with some silt) to coarser-grained non-cohesive soils (gravel and sand, gravelly sand, to gravelly silty sand). The soils were predominantly brown in colour.

SPT N values within the non-cohesive deposits generally ranged between 8 and 25 up to a depth of 1.5 mbgs, indicating loose to compact relative density. Below a depth of 1.5 mbgs, the recorded SPT N values generally ranged between 33 and 100, indicating dense to very dense relative density. At varying locations and depths within this formation, auger advancement was noted as being difficult and split spoon refusal was noted, at times leading to minimal sample recovery, which is often indicative of cobbles/boulders being present within the investigated soils. Organics were noted within the non-cohesive soils between 1.5 mbgs and 2.3 mbgs in BH102-23, however it is unclear whether the encountered organics are present within the deposit or represent caved material due to the drilling method (i.e., use of solid stem augers).

Natural moisture contents in the non-cohesive deposits ranged between 3.2% and 17.2% based on laboratory testing. Particle size distribution analysis was completed on four samples collected from the non-cohesive deposits. The testing results are provided in Appendix B and summarized in Table 1.

Table 1 Particle Size Distribution – Non-Cohesive Deposits

Sample ID	Depth (mbgs)	Description	% Gravel	% Sand	% Silt	% Clay	% Moisture Content
BH102-23-SS4	2.3 – 2.9	Silty Gravel and Sand trace Clay	36	36	21	7	4.4
BH103-23-SS3	1.5 – 2.1	Sand and Silt trace Gravel trace Clay	9	44	40	7	12.5
BH105-23-SS2	0.8 – 1.4	Sand and Gravel some Silt trace Clay	35	44	18	3	6.2
BH107-23-SS2	0.8 – 1.4	Silty Sand trace Gravel trace Clay	7	68	20	5	6.6



4.4 Cohesive Deposits

A layer of predominantly cohesive soil was encountered in BH101-23 between depths of 1.5 mbgs and 2.3 mbgs.

The soil was classified as a brown silt with some clay and some sand, and a trace amount of gravel. The recorded SPT N value of 36 indicated hard consistency. Table 2 summarizes the results of the particle size distribution analysis and natural moisture content testing completed on the retrieved sample.

Table 2 Particle Size Distribution – Cohesive Deposits

Sample ID	Depth (mbgs)	Description	% Gravel	% Sand	% Silt	% Clay	% Moisture Content
BH101-23-SS3	1.5 – 2.1	Silt some Clay some Sand trace Gravel	1	11	74	14	22.3

4.5 Bedrock

Bedrock was not confirmed in any of the boreholes advanced by Cambium at the Site. The boreholes were terminated at depths ranging between 4.5 mbgs and 5.2 mbgs, corresponding to absolute elevations between 459.5 mASL and 475.8 mASL.

In BH103-23, BH105-23, BH106-23 and BH107-23, split spoon refusal (i.e., split spoon bouncing on a probable hard surface) was encountered within the final sampling interval prior to reaching the proposed termination depth, and the boreholes were terminated between depths of 4.5 mbgs and 5.1 mbgs. To determine whether the early termination depths are indicative of a bedrock surface at the Site, further confirmation would be required using methods outside of the current scope of work (i.e., coring or other methods such as geophysical surveys or test pit works). A drift thickness map showing approximate projected drift thicknesses in the project area is provided in Section 5.0 below.

4.6 Groundwater

The soils were predominantly described as being dry to moist throughout the borehole investigation. Wet soils were encountered at a depth of approximately 4.6 mbgs in BH104-23,



which was advanced near the lowest ground elevations at the Site. BH102-23 and BH103-23 were observed to be open and dry upon completion of drilling. In BH105-23 and BH107-23, caving occurred to depths of 3.6 mbgs and 3.9 mbgs respectively (about 0.9 m to 1.2 m above the borehole termination depth), and no water was observed in the boreholes upon completion. Monitoring wells were installed in BH101-23, BH104-23 and BH106-23 to allow for subsequent groundwater level monitoring at the Site. The water levels measured in the installed wells following the investigation are summarized in Table 3.

Table 3 Groundwater Observations During Monitoring Events

Date	Borehole	Ground Elevation (mASL)	Water Level in Monitoring Well (mbgs)	Water Level Elevation (mASL)	Bottom of Well Elevation (mASL)
June 6, 2023	BH101-23	480.25	Dry	-	475.7
	BH104-23	464.45	4.3	460.15	459.9
	BH106-23	474.35	Dry	-	469.9
August 8, 2023	BH101-23	480.25	Dry	-	475.7
	BH104-23	464.45	4.5	459.95	459.9
	BH106-23	474.35	Dry	-	469.9

During the monitoring event conducted on June 6, 2023, water was solely encountered in BH104-23, at a depth of 4.3 mbgs (absolute elevation of approximately 460.15 mASL).

It is noted that the encountered and measured groundwater levels reflect the groundwater conditions in the boreholes at the time of the borehole investigation and subsequent monitoring events between May and August 2023. Groundwater levels at the Site may be anticipated to vary between and beyond the borehole locations and to fluctuate with seasonal variations in precipitation and snowmelt.

4.7 Percolation Rates

Percolation rates were estimated for each of the soil samples submitted for particle size distribution testing, with the results summarized in Table 4.

**Table 4 Estimated Percolation Rates**

Sample ID	Depth	Description	Estimated Percolation Rate [min/cm]
BH101-23-SS3	1.5 – 2.1	Silt some Clay some Sand trace Gravel	30
BH102-23-SS4	2.3 – 2.9	Silty Gravel and Sand trace Clay	12
BH103-23-SS3	1.5 – 2.1	Sand and Silt trace Gravel trace Clay	20
BH105-23-SS2	0.8 – 1.4	Sand and Gravel some Silt trace Clay	10
BH107-23-SS2	0.8 – 1.4	Silty Sand trace Gravel trace Clay	18



5.0 Slope Stability and Karst Assessments

On May 9, 2023, a Site visit was conducted by Cambium personnel to conduct visual slope stability assessments of relevant slope areas within the property boundaries (slope area to the east along Main Street, and in the southeastern corner of the property near Horning's Mills Creek). In addition, a visual karst assessment was completed to fulfil project-specific permitting requirements communicated to Cambium by the Client. The results of these assessments are documented in this Section of the report.

5.1 Slope Stability Assessment

A visual slope stability assessment was conducted separately for two distinct slope areas at the Site (one slope area parallel to Main Street along the eastern property line, and an additional slope area intersecting the southeastern corner of the property near Horning's Mills Creek).

During the slope stability assessment, the top of bank of both slope areas was inferred and staked by Cambium, with coordinates for the inferred top of bank obtained at each stake location using a handheld GPS-enabled device. The inferred top of bank is provided for both slope areas on the Borehole Location Plan appended as Figure 2 of this report.

The visual slope stability assessment was conducted for both slope areas according to the criteria defined in the Ontario MNRF Technical Guide [4]. The Slope Stability Rating Chart per Table 4.2 of the Technical Guide was completed for both slope areas, with the results summarized in Table 5, including commentary and explanations for the selected rating values. The completed rating charts can be found in Appendix C of this report, and photographs taken during the inspection are included in Appendix D.



Table 5 Slope Stability Rating Chart – Results

Criterion	Slope area adjacent to Main Street (eastern property line) <i>Photographs 1 to 8 in Appendix D</i>	Slope area near Horning's Mills Creek (southeastern corner of property) <i>Photographs 9 to 16 in Appendix D</i>
Slope Inclination	Maximum inclination approx. 6H:1V based on [2], giving a rating of 0 .	Maximum inclination of approx. 5H:1V based on [2], giving a rating of 0 .
Soil Stratigraphy	Predominantly non-cohesive sands and gravels based on the geotechnical investigation. Based on quaternary geologic mapping, the encountered materials could potentially represent glacial till formations, therefore a recommended rating of 6 to 9 applies.	
Seepage from Slope Face	None observed, giving a rating of 0 .	
Slope Height	Maximum 5 m based on [2], giving a rating of 2 .	Maximum 4 m based on [2], giving a rating of 2 .
Vegetation Cover on Slope Face	Forested with mature trees, giving a rating of 0 .	Vegetation ranges from grass to low-lying shrubs, to mature trees, giving a rating of 0 to 4 .
Table Land Drainage	The table land is gently sloped towards the slope area, which may result in minor drainage occurring over the slope, giving a rating of 2 .	
Proximity of Watercourse to Slope Toe	No regulated watercourse exists adjacent to the slope toe. A ditch exists between the western road edge of Main Street and the slope toe area and was directing water on the inspection date. While not expected to cause significant and continual erosion of the slope toe, a conservative rating of 6 is applied.	Horning's Mills Creek is located within 15 m of the slope toe area based on available NVCA mapping. Based on the NVCA mapping, the creek source is located approximately 150 m south of the southern property line, and the creek was not directing water on the inspection date. A conservative rating of 6 is applied.
Previous Landslide Activity	No evidence of previous landslide activity was noted, giving a rating of 0 .	

Based on the slope stability rating chart results, a rating between **16 and 19** would apply for the eastern slope area adjacent to Main Street, and a rating between **16 and 23** would apply for the southeastern slope area near Horning's Mills Creek.

The rating values indicate that both slopes can be classified as having a **low potential for slope instability** (rating value less than 24). For low potential slopes, the minimum investigation requirements per the Technical Guide consist of a visual site inspection and letter report. The fieldwork completed by Cambium and the current report are considered to fulfil the investigation requirements for low potential slopes.



From a geotechnical perspective and given the low potential for slope instability, the permitting authority can consider permitting the development at a distance of at least 6 m (erosion access allowance) from the top of bank, however, it is noted a site-specific setback/erosion access allowance will be stipulated by the NVCA or the local municipality.

5.2 Karst Assessment

As part of Cambium's scope of work, a karst assessment including a desktop review and field inspection was completed for the Site. The field inspection for evidence of karst conditions was completed concurrently with the visual slope assessment described above.

The following available information was reviewed by Cambium prior to conducting the visual inspection:

- Karst mapping:
Brunton, F.R. and Dodge, J.E.P.; Karst of Southern Ontario and Manitoulin Island; Ontario Geological Survey, Groundwater Resources Study 5; 2008.
- Drift thickness mapping:
Gwyn, Q.H.J. and Frazer, J.Z.; Drift Thickness of the Dundalk Area, Southern Ontario; Ontario Div. Mines, Prelim. Map P.1023, Drift Thickness Ser., Scale 1:50,000. Geological compilation; 1975.


Based on the desktop review of available karst mapping, the Site is located at the eastern edge of a **potential karst area** (yellow area shown on Embedded Figure 2 below), which indicates areas of carbonate rock units identified as most susceptible to karst processes. The nearest **known karst areas** (red areas shown on Embedded Figure 2 below) are located between approximately 12 km and 14 km to the northwest, north and southeast of the Site. Known karst areas indicate areas where karst features have been confirmed by visual observation, measured field data or data from published reports.

Further to the karst mapping, available drift thickness mapping for the project area indicates that the drift thickness (i.e., depth of bedrock from the ground surface) is projected to be




between approximately 15 m and 23 m in the project area. The bedrock drift thickness mapping is shown on Embedded Figure 3.

Given that the Site is located at the edge of a potential karst area, with no inferred or known karst areas in the immediate vicinity of the Site, the desktop review indicated a low probability of karst conditions being present at the Site. Further, the projected drift thickness (> 15 m) indicates that karst conditions, if present at the Site, will likely be difficult/impossible to observe from the surface during the visual assessment.



Embedded Figure 2: Karst mapping



Embedded Figure 3: Drift thickness mapping

During the visual inspection, no bedrock outcropping was confirmed and therefore, no karstification or features such as voids in bedrock were observed from the surface.

Water was observed in the ditch area along Main Street but was not disappearing into the ground surface at any location along the ditch alignment. A pond containing standing water was observed on the neighbouring property on the east side of Main Street (see Photograph 8 in Appendix D). No sinkholes, conical depressions, pinnaced surfaces, etc., were observed during the inspection.

In summary, ***no conditions indicating the presence of karst were observed during the visual inspection.*** As noted above, given the projected depth of bedrock (> 15 m), visual observations of the bedrock surface were unlikely to be made from the surface during the inspection, and any physical exposure of bedrock using methods such as a test pit investigation would likely be impractical. Early refusal was encountered in some boreholes



around a depth of approximately 5 mbgs, which could indicate a higher bedrock surface at the Site than anticipated based on drift thickness mapping. It should be noted that the early refusal depths encountered in some boreholes could also be indicative of larger cobbles and boulders present within the investigated soils, and therefore should not be taken as definitively confirming a bedrock surface at the Site.

Should further confirmation of the existence of karst conditions be required at certain locations throughout the Site, it may be cost effective to consider geophysical investigation methods (georadar) to effectively map bedrock and any cavities (should they exist).

It is understood that test well installations for water supply will be conducted at the Site. It is recommended to document bedrock observations during the well installations (i.e., drift thickness at well location, and type and composition of bedrock), and to report any relevant observations encountered during well installation and subsequent testing to Cambium.



6.0 Geotechnical Considerations

This section of the report provides engineering information on, and recommendations for, the geotechnical design aspects of the project based on our interpretation of the borehole information, the laboratory test data, and our understanding of the project requirements. The information in this portion of the report is provided for planning and design purposes for the guidance of the design engineers and architects. Where comments are made on construction, they are provided only to highlight aspects of construction which could affect the design of the project. Contractors bidding on or undertaking any work at the Site should examine the factual results of the investigation, satisfy themselves as to the adequacy of the information for construction and make their own independent interpretation of the factual data as it affects their proposed construction techniques, schedule, equipment capabilities, costs, sequencing and the like. Cambium will not assume any responsibility for construction-related decisions made by contractors on the basis of this report.

6.1 Site Preparation

Existing topsoil and organic material, any loose reworked/disturbed native materials and any deleterious material (i.e., construction debris, fibrous material, asphalt, brick fragments, etc.) encountered should be excavated and removed beneath proposed development areas prior to construction. Additionally, this material should be excavated and removed to a minimum distance of 3 m around the building footprint. Any topsoil and materials with significant quantities of organics and deleterious materials are not appropriate for use as fill.

The exposed subgrade should be proof-rolled and inspected by a qualified geotechnical engineer prior to placement of any granular fill or foundations. Any loose/soft soils identified at the time of the proof-rolling that are unable to uniformly be compacted should be sub-excavated and removed.

The excavations created through the removal of these materials should be backfilled with approved engineered fill consistent with the recommendations provided below.



The near surface soils can become unstable if wet or saturated. Such conditions are common in the spring and late fall. Under these conditions, temporary use of granular fill, and possible separating/reinforcing geotextiles, may be required to prevent severe rutting on construction access routes.

6.2 Frost Penetration

Based on climate data and design charts, the maximum frost penetration depth below the surface at the Site is estimated at 1.6 mbgs. Exterior footings for the proposed structure should be situated at or below this depth for frost penetration or should be appropriately protected. Any services should be located below this depth or be sufficiently insulated.

6.3 Excavations

Excavations will be required at the Site to construct footings for the proposed structures, which are currently assumed to be single detached dwellings. It is currently not known whether the structures will be constructed with basements, however, for the purposes of these recommendations it is assumed that excavation depths below the current ground surface will range between 1.6 mbgs and 3 mbgs.

Where sufficient space is available between the proposed building lines and property boundaries, unsupported excavations can be carried out and must be completed in accordance with Occupation Health and Safety (OHSA) requirements, as detailed below.

For practical purposes, the overburden soils at the Site above the groundwater table and within continually dewatered depths can be considered Type 3 soils, as such, excavation side slopes should be no steeper than 1H:1V. Soils below the groundwater table are to be considered Type 4 soils in accordance with OHSA, and excavation side slopes are to be limited to 3H:1V.

It is noted that a workspace allowance of approximately 0.5 m should be maintained between building lines and the toe of the adjacent temporary excavation slopes (applies for slopes with a maximum inclination of 1H:1V).



Excavation slopes should be protected during construction from precipitation, runoff, or snow/ice melt and should be inspected regularly for signs of instability. If localized instability is noted during excavation or if wet conditions are encountered, the side slopes should be flattened as required to maintain safe working conditions or the excavation sidewalls must be fully supported (shored).

The crest area of unsupported excavation slopes is to be held free of any loading (i.e., by heavy machinery, stockpiled construction materials, etc.).

6.4 Groundwater Control and Dewatering

During the water level monitoring events conducted in June and August 2023, two of the installed monitoring wells were dry and the water level in BH104-23, located in the eastern portion of the property, was at or lower than approximately 4.3 mbgs.

Though the extent of the dewatering methods will be dependent on actual excavation depths, it is not anticipated that excavations required to construct proposed dwellings will encounter significant groundwater seepage. It is generally recommended to conduct further water level monitoring events during high groundwater seasons (i.e., during the spring following snowmelt and significant precipitation events) to confirm seasonal high groundwater levels. The recommendations provided in this section should be revisited and revised as necessary if significantly higher groundwater levels are measured in the monitoring wells.

Based on currently available information, infiltrating surface water or groundwater should be manageable using filtered sumps and pumps. It is generally recommended to conduct excavation and foundation construction works during drier seasons to minimize or mitigate potential groundwater-related issues.

Should dewatering methods be deemed necessary for any excavations at the Site, any dewatering methods employed at the Site must ensure that the water table is maintained at least 1 m below the excavation base for the duration of construction. The Contractor is responsible for selecting and designing an appropriate dewatering method to meet project requirements.



6.5 Foundation Design

6.5.1 Conventional Shallow Footings

From a geotechnical perspective, conventional shallow footings placed on competent native soils may be used to transfer loads from the proposed structures to the soils below. In general, the dense to very dense non-cohesive soils and hard cohesive soils encountered below a depth of 1.5 mbgs throughout the Site are considered competent to directly support loads from shallow footings.

Should incompetent (loose, soft and/or deleterious) soils be encountered at the proposed footing depths following excavation, these soils are to be sub-excavated down to competent soils under the guidance of a qualified geotechnical engineer and replaced with competent engineered fill as detailed in Section 6.6. The recommendations and bearing capacities provided in this report assume that any incompetent materials encountered at underside of footing depths will be sub-excavated and replaced in this manner.

Further, any large cobbles or boulders encountered at footing subgrade elevations are to be removed and replaced with engineered fill or other material approved by a geotechnical engineer.

Provided that footings are constructed according to the recommendations provided above, bearing directly on competent native soils with any localized incompetent soils removed and replaced with competent engineered fill material, the following bearing capacities can be provided:

- Serviceability Limit State (SLS): 150 kPa
- Ultimate Limit State (ULS): 225 kPa

The bearing capacities given above apply for strip foundations with a width of 0.5 to 1 m, and for spread footings with dimensions between 1 m x 1 m and 2 m x 2 m, with all footings having at least 1.6 m of adjacent earth cover satisfying frost penetration depth requirements. It is noted that the provided SLS bearing capacity represents the allowable bearing capacity value as calculated according to the methodology in [3], and is to be compared with unfactored load



values. The provided ULS bearing capacity represents the factored bearing resistance calculated according to the methodology in [3] and is to be compared with load values increased by load factors according to applicable standards/building codes. If any proposed structures are subject to stringent settlement requirements (i.e., such that estimated settlement in the order of 20 mm to 25 mm is not tolerable), it is recommended that a geotechnical engineer be retained to conduct a detailed settlement analysis, to ensure that project-specific requirements are met.

Cambium should be contacted to review final site grading plans and foundation dimensions and elevations, in order to confirm the bearing capacities provided in this report. A qualified geotechnical engineer should be retained to confirm bearing capacities onsite, following excavation to the proposed footing subgrade elevations, or to develop further recommendations such as the required depth of engineered fill pads.

6.5.2 Floor Slabs

To create a stable working surface, to distribute loadings, and for drainage purposes, an allowance should be made to provide at least 200 mm of OPSS.MUNI 1010 Granular A compacted to 98% of Standard Proctor Maximum Dry Density (SPMDD) beneath all floor slabs. It is recommended that all floor slabs are situated at least 500 mm above the seasonal high groundwater elevation.

Within any interior areas that may be exposed to freezing conditions for extended periods of time, the floor slab may be susceptible to frost heaving, depending on the composition of the subgrade. The subgrade underlying these areas should be adequately insulated to prevent frost penetration.

Any basement floor slabs (if applicable) should be underlain by a 300 mm thick layer of 19 mm diameter crushed clear stone wrapped in a geotextile (Terrafix 270R or equivalent) and hydraulically connected to perimeter subdrains. The clear stone material should be nominally compacted to a dense state.



6.6 Backfill and Compaction

Engineered fill, if required for foundations, should consist of free-draining granular material meeting the specifications of OPSS 1010 Granular B or an approved equivalent and should be placed in maximum 200 mm thick lifts compacted to 100% of SPMDD, as confirmed by nuclear densometer testing.

Imported material for engineered fill should consist of clean, no-organic, soils, free of chemical contamination or deleterious material. The moisture content of the engineered fill will need to be close enough to optimum at the time of placement to allow for adequate compaction.

Foundation wall and any buried utility backfill material should consist of free draining imported granular material. Excavated sand and gravel materials at the Site may be suitable for re-use as backfill for foundation walls and for grading purposes. Geotechnical testing of the material will be required to confirm suitability and compaction parameters (i.e., Proctor testing to confirm optimum moisture content). The fines (silt and clay) content of materials utilized as backfill for foundation walls/grading should not exceed 35%, which will need to be confirmed by sampling from stockpiled material and conducting confirmatory grain size analyses. The fines content of the samples collected during the borehole investigation and subsequently selected for particle size distribution testing generally ranged between 21% and 28%, however higher fines contents between 47% and 88% were also determined for samples collected from the Site.

Typically, backfill should be placed in maximum 300 mm thick lifts and should be compacted to a minimum of 98% of SPMDD. Backfill adjacent to the structural elements (i.e., foundation walls) should be compacted to 95% of SPMDD taking care not to damage the adjacent structures. The backfill material in the upper 300 mm below the pavement subgrade elevation should be compacted to 100% of SPMDD in all areas.

All existing vegetation, topsoil, organic and non-organic fills, and any loose soils shall be removed down to a competent base. Backfill areas must be approved by a qualified geotechnical engineer prior to placement of any new fill, to ensure the suitability of subgrade conditions.



6.6.1 Engineered Fill

Where the existing fill is treated as an engineered fill to support structural elements such as foundations and/or floor slabs the following is recommended for the construction of engineered fill:

- I. Remove any and all existing vegetation, surficial topsoil / organics, organic fills or fills and any loose/disturbed soils to a competent subgrade for a suitable envelope.
- II. The area of the engineered fill should extend horizontally 1 m beyond the outside edge of the foundations then extend downward at an imaginary 1H:1V slope to the competent approved native soil. The exposed edges of the engineered fill should be sloped at a maximum of 3H:1V to avoid weakening of the engineered fill edges due to slope movement. If fill is required adjacent to sloped banks (i.e., slope steeper than 3H:1V), the fill shall be placed in stepped planes to avoid a plane weakness.
- III. The subgrade or base of the engineered fill area must be approved by Cambium prior to placement of any new fill, to ensure that suitability of subgrade condition.
- IV. Place approved OPSS 1010.MUNI SSM or Granular 'B' Type I material at a moisture content at or near optimum moisture in suitable maximum 200 mm thick lifts, compacted to 100% of SPMDD. If native soils from the site are not used as engineered fill, imported material for engineered fill should consist of clean, non-organic soils, free of chemical contamination or deleterious material. Any frost penetration into the fill material must be removed prior to placement of subsequent lifts of fill and reviewed by Cambium.
- V. The engineered fill should be placed at least 600 mm above the elevation of the proposed underside of footing.
- VI. Due to the potential negative effects of differential settlement between the engineered fill and the native soils, in any block where footings are to be placed partly on engineered fill and partly on native soils, reinforcing steel bars should be included and placed within the footings and the top of the foundation walls. All tie reinforcing steel bars should be included and placed within the top of the foundation walls. All tie



reinforcing steel bars should have at least 600 mm of overlap. The actual steel reinforcement design should be confirmed / designed by the project structural engineer.

- VII. Full time testing and inspection of the engineered fill will be required for it to be used as a founding material, as outlined in Section 4.2.2.2 of the Ontario Building Code.

6.7 Subdrainage

The exterior grade around any buildings should be sloped from the walls to direct surface runoff away from the building. In order to deal with seasonal perched water and/or the water table, perimeter subdrains consisting of geotextile-wrapped perforated pipe subdrains set in a trench of clear stone and connected to a sump or other frost-free positive outlet are recommended.

Subsurface walls should be adequately damp proofed above the water table and waterproofed below the water table.

6.8 Buried Utilities

Bedding and cover material for any buried utilities should consist of OPSS 1010 Granular A or B Type II, placed in accordance with pertinent Ontario Provincial Standard Drawings (OPSD 802.013). The bedding and cover material shall be placed in maximum 200 mm thick lifts and should be compacted to at least 98% of SPMDD.

The cover material shall be a minimum of 300 mm over the top of the pipe and compacted to 98% of SPMDD, taking care not to damage the utility pipes during compaction.

6.9 Lateral Earth Pressure

Lateral earth pressure coefficients (K) are shown in Table 6 and may be used for the preliminary design of temporary and permanent structures at the Site. It is assumed that potential lateral loads will result from cohesion less, frictional materials, such as granular backfill and the encountered near surface native sand.

**Table 6 Lateral Earth Pressure Coefficients**

Stratum/Parameter	γ / γ' [kN/m ³]	Φ [°]	c [kN/m ²]	K_o [-]	K_a [-]	K_p [-]
Non-Cohesive Soils (Sand and Gravel) <i>compact to dense</i>	19.5 / 10.5	30	0	0.50	0.33	3.00
Engineered Fill (per recommendations provided above)	20.5 / 11.5	32	0	0.47	0.31	3.25

Where:

- γ = bulk unit weight of soil (kN/m³)
- γ' = submerged (effective) unit weight of soil (kN/m³)
- ϕ = internal angle of friction (degrees)
- c = soil cohesion (kN/m²)
- K_a = Rankine active earth pressure coefficient (dimensionless)
- K_o = Rankine at-rest earth pressure coefficient (dimensionless)
- K_p = Rankine passive earth pressure coefficient (dimensionless)

The coefficients provided in Table 6 assume that the surface of the granular backfill is horizontal against any proposed retaining wall, and the wall is vertical and smooth. Cambium should be contacted to provide updated lateral earth pressure coefficients should the assumptions differ to those noted.

6.10 Pavement Design

The performance of pavement is dependent on proper subgrade preparation. All topsoil and organic materials should be removed and backfilled with approved engineered fill or native material (if tested and approved for use by a qualified geotechnical/pavement engineer), compacted to 98% of SPMDD. The subgrade should be proof rolled and inspected by a geotechnical engineer. Any areas where boulders, rutting, or appreciable deflection is noted should be sub-excavated and replaced with suitable fill. The fill should be compacted to at least 100% of SPMDD.

The recommended pavement structure should meet relevant standards, if prescribed by the local municipality. A preliminary minimum pavement structure is provided in Table 7.

**Table 7 Minimum Pavement Structure**

Pavement Layer	Compaction Requirements	Minimum Thickness and Material Requirements
Surface Course Asphalt	92% - 96.5% MRD (OPSS 310)	40 mm HL3
Binder Course Asphalt	92% - 96.5% MRD (OPSS 310)	50 mm HL8
Granular Base	100% SPMDD (ASTM-D698)	150 mm OPSS 1010 Granular A
Granular Subbase	100% SPMDD (ASTM-D698)	300 mm OPSS 1010 Granular B Type I

Final material and thickness requirements, and any material/thickness substitutions must be approved by the Design Engineer.

The thickness of the subbase layer could be increased at the discretion of the Engineer, to accommodate site conditions at the time of construction, including any soft or weak subgrade soil replacement.

Compaction of the subgrade should be verified by the Engineer prior to placing the granular fill. Granular layers should be placed in 200 mm maximum loose lifts and compacted to at least 100% of SPMDD. The granular materials specified should conform to OPSS standards, as confirmed by appropriate materials testing. Asphalt materials should be rolled and compacted as per OPSS 310.

The final asphalt surface should be sloped at a minimum of 2% to shed runoff. Abutting pavements should be saw cut to provide clean vertical joints with new pavement areas.



7.0 Report Limitations

7.1 Design Review and Inspections

Cambium should be contacted to review and approve design drawings, prior to tendering or commencing construction, to ensure that all pertinent geotechnical-related factors have been addressed. It is important that onsite geotechnical supervision be provided at this site for excavation and backfill procedures, deleterious soil removal, subgrade inspections and compaction testing.

7.2 Changes in Site and Project Scope

This geotechnical engineering report is intended for planning and design purposes only.

Subsurface conditions can be altered by the passage of sufficient time, natural occurrences, and human intervention. In particular, consideration should be given to contractual responsibilities as they relate to control of groundwater seepage, disturbance of soils, and frost protection.

The design parameters provided, and the engineering advice offered in this report are intended for use by the owner and its retained design consultants. If there are changes to the project scope and development features, these interpretations made of the subsurface information, for geotechnical design parameters, advice, and comments relating to constructability issues and quality control may not be complete for the project. Cambium should be retained to conduct further review to interpret the implications of such changes with respect to this report.



8.0 Closing

We trust that the information contained in this report meets your current requirements. If you have questions or comments regarding this document, please do not hesitate to contact the undersigned at (705) 719-0700.

Respectfully submitted,

Cambium Inc.

DocuSigned by:

D29A94473BBC4E1...

Josef Schweighofer, B.Sc., M.Sc.
Project Coordinator - Geotechnical

DocuSigned by:

E2EEE82F32D347D...

Rob Gethin, P.Eng.
Group Manager – Geotechnical

DS

DocuSigned by:

0B68D45279A94B7...

Stuart Baird, M.Eng., P.Eng.
General Manager - Geotechnical



2024-03-12

SEB/RG/js

\\cambiumincstorage.file.core.windows.net\projects\17200 to 17299\17217-001 Carnevale - GEO & HYD - 537080 Main St, Horning's Mills\Deliverables\REPORT - GEO\Final\2024-03-11
GEO RPT 537086 Main St, Horning's Mills, ON.docx



Standard Limitations

Limited Warranty

In performing work on behalf of a client, Cambium relies on its client to provide instructions on the scope of its retainer, and, on that basis, Cambium determines the precise nature of the work to be performed. Cambium undertakes all work in accordance with applicable accepted industry practices and standards. Unless required under local laws, other than as expressly stated herein, no other warranties or conditions, either expressed or implied, are made regarding the services, work or reports provided.

Reliance on Materials and Information

The findings and results presented in reports prepared by Cambium are based on the materials and information provided by the client to Cambium and on the facts, conditions and circumstances encountered by Cambium during the performance of the work requested by the client. In formulating its findings and results into a report, Cambium assumes that the information and materials provided by the client or obtained by Cambium from the client or otherwise are factual, accurate and represent a true depiction of the circumstances that exist. Cambium relies on its client to inform Cambium if there are changes to any such information and materials. Cambium does not review, analyze, or attempt to verify the accuracy or completeness of the information or materials provided, or circumstances encountered, other than in accordance with applicable accepted industry practice. Cambium will not be responsible for matters arising from incomplete, incorrect, or misleading information or from facts or circumstances that are not fully disclosed to or that are concealed from Cambium during the provision of services, work or reports.

Facts, conditions, information, and circumstances may vary with time and locations and Cambium's work is based on a review of such matters as they existed at the particular time and location indicated in its reports. No assurance is made by Cambium that the facts, conditions, information, circumstances, or any underlying assumptions made by Cambium in connection with the work performed will not change after the work is completed and a report is submitted. If any such changes occur or additional information is obtained, Cambium should be advised and requested to consider if the changes or additional information affect its findings or results.

When preparing reports, Cambium considers applicable legislation, regulations, governmental guidelines, and policies to the extent they are within its knowledge, but Cambium is not qualified to advise with respect to legal matters. The presentation of information regarding applicable legislation, regulations, governmental guidelines, and policies is for information only and is not intended to and should not be interpreted as constituting a legal opinion concerning the work completed or conditions outlined in a report. All legal matters should be reviewed and considered by an appropriately qualified legal practitioner.

Site Assessments

A site assessment is created using data and information collected during the investigation of a site and based on conditions encountered at the time and particular locations at which fieldwork is conducted. The information, sample results and data collected represent the conditions only at the specific times at which and at those specific locations from which the information, samples and data were obtained and the information, sample results and data may vary at other locations and times. To the extent that Cambium's work or report considers any locations or times other than those from which information, sample results and data was specifically received, the work or report is based on a reasonable extrapolation from such information, sample results and data but the actual conditions encountered may vary from those extrapolations.

Only conditions at the site and locations chosen for study by the client are evaluated; no adjacent or other properties are evaluated unless specifically requested by the client. Any physical or other aspects of the site chosen for study by the client, or any other matter not specifically addressed in a report prepared by Cambium, are beyond the scope of the work performed by Cambium and such matters have not been investigated or addressed.

Reliance

Cambium's services, work and reports may be relied on by the client and its corporate directors and officers, employees, and professional advisors. Cambium is not responsible for the use of its work or reports by any other party, or for the reliance on, or for any decision which is made by any party using the services or work performed by or a report prepared by Cambium without Cambium's express written consent. Any party that relies on services or work performed by Cambium or a report prepared by Cambium without Cambium's express written consent, does so at its own risk. No report of Cambium may be disclosed or referred to in any public document without Cambium's express prior written consent. Cambium specifically disclaims any liability or responsibility to any such party for any loss, damage, expense, fine, penalty or other such thing which may arise or result from the use of any information, recommendation or other matter arising from the services, work or reports provided by Cambium.

Limitation of Liability


Potential liability to the client arising out of the report is limited to the amount of Cambium's professional liability insurance coverage. Cambium shall only be liable for direct damages to the extent caused by Cambium's negligence and/or breach of contract. Cambium shall not be liable for consequential damages.

Personal Liability

The client expressly agrees that Cambium employees shall have no personal liability to the client with respect to a claim, whether in contract, tort and/or other cause of action in law. Furthermore, the client agrees that it will bring no proceedings nor take any action in any court of law against Cambium employees in their personal capacity.



Appended Figures



**GEOTECHNICAL
INVESTIGATION**
ANGELO CARNEVALE
537080 Main Street,
Hornings Mills, Ontario

LEGEND

- Highway
- Major Road
- Minor Road
- Watercourse
- Provincial Park
- Water Area
- Wooded Area
- Built Up Area

Notes:
- Base mapping features are © King's Printer of Ontario, 2022 (this does not constitute an endorsement by the Ministry of Natural Resources or the Ontario Government).
- Distances on this plan are in metres and can be converted to feet by dividing by 0.3048.
- Cambium Inc. makes every effort to ensure this map is free from errors but cannot be held responsible for any damages due to error or omissions. This map should not be used for navigation or legal purposes. It is intended for general reference use only.



194 Sophia Street
Peterborough, Ontario, K9H 1E5
Tel: (705) 742.7900 Fax: (705) 742.7907
www.cambium-inc.com

SITE LOCATION PLAN

Project No.: 17217-001	Date: May 2023
Scale: 1:100,000	Projection: NAD 1983 UTM Zone 17N
Created by: MAT	Checked by: RG
Figure: 1	



GEOTECHNICAL INVESTIGATION

ANGELO CARNEVALE
537080 Main Street,
Hornings Mills, Ontario

LEGEND

-  Borehole
-  Monitoring Well
-  Inferred Top of Bank (Cambium, May 2023)
-  Site (approximate)

Notes:

- Base mapping features are © King's Printer of Ontario, 2022 (this does not constitute an endorsement by the Ministry of Natural Resources or the Ontario Government).
- Distances on this plan are in metres and can be converted to feet by dividing by 0.3048.
- Cambium Inc. makes every effort to ensure this map is free from errors but cannot be held responsible for any damages due to error or omissions. This map should not be used for navigation or legal purposes. It is intended for general reference use only.



194 Sophia Street
Peterborough, Ontario, K9H 1E5
Tel: (705) 742.7900 Fax: (705) 742.7907
www.cambium-inc.com

BOREHOLE LOCATION PLAN

Project No.:	17217-001	Date:	June 2023
Scale:	1:3,000	Rev.:	
Created by:	MAT	Projection:	NAD 1983 UTM Zone 17N
Checked by:	RG	Figure:	2




Appendix A
Borehole Logs



Client: Angelo Carnevale
Contractor: Walker Drilling
Project No.: 17217-001
Location: 537090 Main Street

Project Name: 537090 Main Street, Horning's Mills, ON
Method: Track Mounted Hollow Stem Auger
Elevation: 480.25 mASL
UTM: 17 T N: 4888586 E: 563201

Log of Borehole: BH101-23
Page: 1 of 1
Date Completed: May 11, 2023



Logged By: WA

Input By: WA

Peterborough, Barrie, Oshawa, Kingston, Ottawa

Log of Borehole: BH102-23
Page: 1 of 1
Date Completed: May 11, 2023

Peterborough, Barrie, Oshawa, Kingston, Ottawa

Log of Borehole: BH103-23
Page: 1 of 1
Date Completed: May 11, 2023


Peterborough, Barrie, Oshawa, Kingston, Ottawa



Client: Angelo Carnevale
Contractor: Walker Drilling
Project No.: 17217-001
Location: 537090 Main Street

Project Name: 537090 Main Street, Horning's Mills, ON
Method: Track Mounted Solid Stem Auger
Elevation: 464.45 mASL
UTM: 17 T N: 4888732 E: 563621

Log of Borehole: BH104-23
Page: 1 of 1
Date Completed: May 11, 2023



Logged By: WA

Input By: WA

Peterborough, Barrie, Oshawa, Kingston, Ottawa

Log of Borehole: BH105-23
Page: 1 of 1
Date Completed: May 12, 2023


Peterborough, Barrie, Oshawa, Kingston, Ottawa



Client: Angelo Carnevale
Contractor: Walker Drilling
Project No.: 17217-001
Location: 537090 Main Street

Project Name: 537090 Main Street, Horning's Mills, ON
Method: Track Mounted Solid Stem Auger
Elevation: 474.35 mASL
UTM: 17 T N: 4888425 E: 563458

Log of Borehole: BH106-23
Page: 1 of 1
Date Completed: May 12, 2023



Logged By: WA

Input By: WA

Peterborough, Barrie, Oshawa, Kingston, Ottawa



Client: Angelo Carnevale
Contractor: Walker Drilling
Project No.: 17217-001
Location: 537090 Main Street

Project Name: 537090 Main Street, Horning's Mills, ON
Method: Track Mounted Solid Stem Auger
Elevation: 480.9 mASL
UTM: 17 T N: 4888538 E: 563305

Log of Borehole: BH107-23
Page: 1 of 1
Date Completed: May 12, 2023

SUBSURFACE PROFILE					SAMPLE													
Elevation (m)	Depth	Lithology	Description	Elevation Depth	Number	Type	% Recovery	SPT (N)	Atterberg Limits (%)			Shear Strength Cu, kPa			Well Installation	Log Notes		
									LL	PL	PI	nat V. rem V.	20	40			60	80
									25	50	75	20	40	60	80			
480.9	0		TOPSOIL: (~125mm thick)	480.77	1A	SS						25.4%						
			(SM) SILTY SAND: trace organic matter; brown; non-cohesive, moist, compact	0.13	1B	SS	50	13				19.3%		13				
480.4	0.5			480.14														
			(SM) SILTY SAND: trace gravel, trace clay; brown; non-cohesive, moist, compact	0.76	2	SS	80	25				6.6%		25				
479.9	1																	
479.4	1.5		- very dense			3	SS	50	100				6.5%			100		
478.9	2			478.61														
			(SW) SAND: some gravel, some silt, brown; non-cohesive, moist to dry, very dense	2.29	4	SS	70	89				3.6%			89			
478.4	2.5																	
477.9	3					5	SS	60	50				4.7%		50			
477.4	3.5																	
476.9	4																	
476.4	4.5				6	SS	70	65				3.2%			65			
475.9	5			475.85														
			Borehole terminated @ 5.1 mbgs due to SPT refusal encountered.	5.05														
475.4	5.5																	
474.9	6																	
474.4	6.5																	
473.9	7																	
473.4																		
GRAINSIZE DISTRIBUTION																		
SAMPLE GRAVEL SAND SILT CLAY																		
2 7 68 20 5																		

1m = 24 units

Logged By: WA

Input By: WA

Peterborough, Barrie, Oshawa, Kingston, Ottawa



Geotechnical Investigation Report - 537086 Main Street, Horning's Mills, Ontario
Angelo Carnevale
Cambium Reference: 17217-001
March 11, 2024

Appendix B


Physical Laboratory Testing Results



Grain Size Distribution Chart

Project Number: 17217-001 **Client:** Angelo Carnevale
Project Name: 537090 Main Street Horning's Mills
Sample Date: May 11-12, 2023 **Sampled By:** Waleed El-Taweel - Cambium Inc.
Location: BH 101-23 SS 3 **Depth:** 1.5 m to 2.1 m **Lab Sample No:** S-23-0825

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT		FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE
			SAND			GRAVEL		
								BOULDERS

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
BH 101-23	SS 3	1.5 m to 2.1 m	1	11	74	14	22.3
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Silt some Clay some Sand trace Gravel		ML	0.0240	0.0059	-	-	-

Additional information available upon request

Issued By:
 (Senior Project Manager)

Date Issued: May 24, 2023


Cambium Inc. (Laboratory)
 866.217.7900 | cambium-inc.com
 194 Sophia St. | Peterborough | ON | K9H 1E5

Form: L6V.2 - Grad.Hydo



Grain Size Distribution Chart

Project Number: 17217-001 **Client:** Angelo Carnevale
Project Name: 537090 Main Street Horning's Mills
Sample Date: May 11-12, 2023 **Sampled By:** Waleed El-Taweel - Cambium Inc.
Location: BH 102-23 SS 4 **Depth:** 2.3 m to 2.9 m **Lab Sample No:** S-23-0826



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
BH 102-23	SS 4	2.3 m to 2.9 m	36	36	21	7	4.4
Description	Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c	
Silty Gravel and Sand trace Clay	SM	3.7000	0.1300	0.0042	880.95	1.09	

Additional information available upon request

Issued By:
 (Senior Project Manager)


Date Issued: May 24, 2023



Grain Size Distribution Chart

Project Number: 17217-001 **Client:** Angelo Carnevale
Project Name: 537090 Main Street Horning's Mills
Sample Date: May 11-12, 2023 **Sampled By:** Waleed El-Taweel - Cambium Inc.
Location: BH 103-23 SS 3 **Depth:** 1.5 m to 2.1 m **Lab Sample No:** S-23-0827

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDER
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
BH 103-23	SS 3	1.5 m to 2.1 m	9	44	40	7	12.5
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Sand and Silt trace Gravel trace Clay		SM	0.1300	0.0370	0.0038	34.21	2.77

Additional information available upon request

Issued By: 
 (Senior Project Manager)


Date Issued: May 24, 2023



Grain Size Distribution Chart

Project Number: 17217-001 **Client:** Angelo Carnevale
Project Name: 537090 Main Street Horning's Mills
Sample Date: May 11-12, 2023 **Sampled By:** Waleed El-Taweel - Cambium Inc.
Location: BH 105-23 SS 2 **Depth:** 0.8 m to 1.4 m **Lab Sample No:** S-23-0828

UNIFIED SOIL CLASSIFICATION SYSTEM					
CLAY & SILT (<0.075 mm)	SAND (<4.75 mm to 0.075 mm)			GRAVEL (>4.75 mm)	
	FINE	MEDIUM	COARSE	FINE	COARSE



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDER
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
BH 105-23	SS 2	0.8 m to 1.4 m	35	44	18	3	6.2
Description		Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c
Sand and Gravel some Silt trace Clay		SM	2.700	0.145	0.030	90.00	0.26

Additional information available upon request


Issued By: 
 (Senior Project Manager)

Date Issued: May 24, 2023



Grain Size Distribution Chart

Project Number: 17217-001 **Client:** Angelo Carnevale
Project Name: 537090 Main Street Horning's Mills
Sample Date: May 11-12, 2023 **Sampled By:** Waleed El-Taweel - Cambium Inc.
Location: BH 107-23 SS 2 **Depth:** 0.8 m to 1.4 m **Lab Sample No:** S-23-0829



MIT SOIL CLASSIFICATION SYSTEM								
CLAY	SILT	FINE	MEDIUM	COARSE	FINE	MEDIUM	COARSE	BOULDERS
		SAND			GRAVEL			

Borehole No.	Sample No.	Depth	Gravel	Sand	Silt	Clay	Moisture
BH 107-23	SS 2	0.8 m to 1.4 m	7	68	20	5	6.6
Description	Classification	D ₆₀	D ₃₀	D ₁₀	C _u	C _c	
Silty Sand trace Gravel trace Clay	SM	0.6400	0.1250	0.0068	94.12	3.59	

Additional information available upon request

Issued By:
 (Senior Project Manager)

Date Issued: May 24, 2023



Moisture Content



Project Number: 17217-001
Project Name: 537090 Main St, Horning's Mills
Client: Angelo Carnevale
Date Taken: 2023-05-11

Lab Number: S-23-0824
Date Tested: 2023-05-16
Tested By: D. Rock

Borehole Number	Sample Number	Sample Depth (m)	Water Weight (g)	Water Content (%)	Additional Observations
101	1A	0.00-0.13	15.2	18.6	NR,1
101	1B	0.13-0.61	14.4	18.0	NR,1
101	2	0.76-1.37	25.9	9.7	NR
101	3	1.52-2.13	81.1	22.3	NR
101	4	2.29-2.90	11.2	3.4	NR
101	5	3.05-3.20	6.3	3.8	NR
101	6	4.57-5.18	11.5	3.5	NR
102	1A	0.00-0.20	26.5	24.0	NR,1
102	1B	0.15-0.61	27.5	10.6	NR,1
102	2	0.76-1.37	15.2	5.4	
102	3	1.52-2.13	21.2	5.8	NR
102	4	2.29-2.90	20.5	4.4	NR
102	5	3.05-3.51	11.5	5.2	NR
102	6	4.57-5.03	8.6	4.0	
103	1A	0.00-0.13	30.2	21.0	NR,1
103	1B	0.13-0.61	28.5	15.3	NR
103	2	0.76-1.37	38.4	17.2	
103	3	1.52-2.13	53.2	12.5	NR
103	4	2.29-2.59	23.9	7.6	NR
103	5	3.05-3.35	11.5	4.3	NR
103	6	4.57-4.72	9.5	5.5	NR
104	1A	0.00-0.13	31.8	23.3	NR,1
104	1B	0.13-0.61	8.5	8.4	NR
104	2	0.76-1.37	13.4	4.7	NR
104	3	1.52-1.98	24.9	8.9	
104	4	2.29-2.59	18.9	7.1	NR
104	5	3.05-3.66	23.7	8.0	NR

1 – Contains organics
 2 – Contains rubble
 3 – Hydrocarbon Odour
 4 – Unknown Chemical Odour
 5 – Saturated – free water visible

6 – Very moist – near optimum moisture content
 7 – Moist – below optimum moisture
 8 – Dry – dry texture – powdery
 9 – Very small – caution may not be representative
 10 – Hold sample for gradation analysis



Moisture Content



Project Number: 17217-001
Project Name: 537090 Main St, Horning's Mills
Client: Angelo Carnevale
Date Taken: 2023-05-11

Lab Number: S-23-0824
Date Tested: 2023-05-16
Tested By: D. Rock

Borehole Number	Sample Number	Sample Depth (m)	Water Weight (g)	Water Content (%)	Additional Observations
104	6	4.57-5.03	35.8	10.3	
105	1A	0.00-0.15	14.2	22.2	NR,1
105	1B	0.15-0.61	36.7	21.1	NR,1
105	2	0.76-1.37	34.2	6.2	NR
105	3	1.52-1.98	19.4	5.6	NR
105	4	2.29-2.59	12.2	7.2	NR
105	5	3.05-3.35	18.7	5.7	NR
105	6	4.57-4.65	6.4	4.7	NR
106	1A	0.00-0.13	23.7	25.4	NR,1
106	1B	0.13-0.61	17.1	18.4	NR,1
106	2	0.76-1.37	42.5	15.6	
106	3	1.52-2.13	30.7	8.8	NR
106	4A	2.29-2.59	7.5	4.2	NR
106	4B	2.44-2.74	5.9	2.8	NR
106	5	3.05-3.35	15.7	6.1	
107	1A	0.00-0.13	30.4	25.4	NR,1
107	1B	0.13-0.61	44.0	19.3	NR
107	2	0.76-1.37	53.2	6.6	NR
107	3	1.52-1.98	14.0	6.5	
107	4	2.29-2.74	14.0	3.6	NR
107	5	3.05-3.25	16.0	4.7	NR
107	6	4.57-5.03	9.4	3.2	

- | | |
|------------------------------------|--|
| 1 – Contains organics | 6 – Very moist – near optimum moisture content |
| 2 – Contains rubble | 7 – Moist – below optimum moisture |
| 3 – Hydrocarbon Odour | 8 – Dry – dry texture – powdery |
| 4 – Unknown Chemical Odour | 9 – Very small – caution may not be representative |
| 5 – Saturated – free water visible | 10 – Hold sample for gradation analysis |



Appendix C
Slope Stability Rating Charts

SLOPE STABILITY RATING CHART

Site Location:	537080 Main St. - <i>Eastern Slope Area (Main St.)</i>	File No.	17217-001		
Property Owner:	Angelo Carnevale	Inspection Date:	2023-05-09		
Inspected By:	JS/RG	Weather:	partly cloudy		
Inspection Task		Rating Value			
1. SLOPE INCLINATION					
Degrees	Horizontal:Vertical				
a) 18 or less	3:1 or flatter	0			
b) 18 to 26	2:1 to more than 3:1	6			
c) more than 26	Steeper than 2:1	16			
2. SOIL STRATIGRAPHY					
a) Shale, Limestone, Granite (Bedrock)		0			
b) Sand, Gravel		6			
c) Glacial Till		9			
d) Clay, Silt		12			
e) Fill		16			
f) Leda Clay		24			
3. SEEPAGE FROM SLOPE FACE					
a) None or near bottom only		0			
b) Near mid-slope only		6			
c) Near crest only or from several levels		12			
4. SLOPE HEIGHT					
a) 2 m or less		0			
b) 2.1 to 5 m		2			
c) 5.1 to 10 m		4			
d) more than 10 m		8			
5. VEGETATION COVER ON SLOPE FACE					
a) Well vegetated, heavy shrubs or forested with mature trees		0			
b) Light Vegetation; Mostly grass, weeds, occasional trees, shrubs		4			
c) No vegetation, bare		8			
6. TABLE LAND DRAINAGE					
a) Table land flat, no apparent drainage over slope		0			
b) Minor drainage over slope, no active erosion		2			
c) Drainage over slope, active erosion, gullies		4			
7. PROXIMITY OF WATERCOURSE TO SLOPE TOE					
a) 15 m or more from slope toe		0			
b) Less than 15 m from slope toe		6			
8. PREVIOUS LANDSLIDE ACTIVITY					
a) No		0			
b) Yes		6			
RATING VALUES TOTAL		16...19			
SLOPE INSTABILITY RATING		INVESTIGATION REQUIREMENTS			
1. Low Potential	<24	Site inspection only, confirmation, report letter			
2. Slight Potential	25 - 35	Site inspection and surveying, preliminary study, detailed report			
3. Moderate Potential	>35	Boreholes, piezometers, lab tests, surveying detailed report			
Notes:					
a) Choose only one rating value from each category; compare total rating value with above requirements					
b) If there is a waterbody (stream, creek, river, pond, bay, lake) at the slope toe, the potential for toe erosion and undercutting should be evaluated in detail and protection provided if required.					
c) For leda clay and rock slopes, additional evaluation must be carried out					

SLOPE STABILITY RATING CHART

Site Location:	537080 Main St. - <i>SE Slope Area (Creek)</i>	File No.	17217-001		
Property Owner:	Angelo Carnevale	Inspection Date:	2023-05-09		
Inspected By:	JS/RG	Weather:	partly cloudy		
Inspection Task		Rating Value			
1. SLOPE INCLINATION					
Degrees	Horizontal:Vertical				
a) 18 or less	3:1 or flatter	0			
b) 18 to 26	2:1 to more than 3:1	6			
c) more than 26	Steeper than 2:1	16			
2. SOIL STRATIGRAPHY					
a) Shale, Limestone, Granite (Bedrock)		0			
b) Sand, Gravel		6			
c) Glacial Till		9			
d) Clay, Silt		12			
e) Fill		16			
f) Leda Clay		24			
3. SEEPAGE FROM SLOPE FACE					
a) None or near bottom only		0			
b) Near mid-slope only		6			
c) Near crest only or from several levels		12			
4. SLOPE HEIGHT					
a) 2 m or less		0			
b) 2.1 to 5 m		2			
c) 5.1 to 10 m		4			
d) more than 10 m		8			
5. VEGETATION COVER ON SLOPE FACE					
a) Well vegetated, heavy shrubs or forested with mature trees		0			
b) Light Vegetation; Mostly grass, weeds, occasional trees, shrubs		4			
c) No vegetation, bare		8			
6. TABLE LAND DRAINAGE					
a) Table land flat, no apparent drainage over slope		0			
b) Minor drainage over slope, no active erosion		2			
c) Drainage over slope, active erosion, gullies		4			
7. PROXIMITY OF WATERCOURSE TO SLOPE TOE					
a) 15 m or more from slope toe		0			
b) Less than 15 m from slope toe		6			
8. PREVIOUS LANDSLIDE ACTIVITY					
a) No		0			
b) Yes		6			
RATING VALUES TOTAL			16...23		
SLOPE INSTABILITY RATING		INVESTIGATION REQUIREMENTS			
1. Low Potential	<24	Site inspection only, confirmation, report letter			
2. Slight Potential	25 - 35	Site inspection and surveying, preliminary study, detailed report			
3. Moderate Potential	>35	Boreholes, piezometers, lab tests, surveying detailed report			
Notes:					
a) Choose only one rating value from each category; compare total rating value with above requirements					
b) If there is a waterbody (stream, creek, river, pond, bay, lake) at the slope toe, the potential for toe erosion and undercutting should be evaluated in detail and protection provided if required.					
c) For leda clay and rock slopes, additional evaluation must be carried out					



Appendix D
Site Photographs



Eastern Slope Area bordering Main Street



Photograph 1: Views of table land, with stakes indicating inferred top of bank



Photograph 2: View of stake inferring top of bank, with existing dwelling visible



Photograph 3: View downslope, with mature trees on slope and Main Street visible



Photograph 4: Alternate view of slope, looking north



Photograph 5: View of bench area in slope, looking north



Photograph 6: View of ditch area and Main Street, looking north



Photograph 7: View of ditch area and Main Street, looking south



Photograph 8: View looking east across Main Street, with pond on neighbouring property



Southeastern Slope Area near Horning's Mills Creek



Photograph 9: View of table land



Photograph 10: View looking down (L) and up (R) slope area with grass vegetation



Photograph 11: View of slope with vegetation, and top of bank visible



Photograph 12: Alternative view of slope with grass vegetation, from top of bank



Photograph 13: View of slope with mature trees



Photograph 14: View of toe area of slope with vegetation



Photograph 15: Alternate view of toe area of slope




Photograph 16: View towards Main Street from toe area of slope



APPENDIX H

PEARSON ENGINEERING DRAWINGS

C:\Users\viparman\AppData\Local\Temp\Asdubation_2872\23008 - BASE - GRADING - FSR.dwg Layout:SSG-1 Plotted Mar 22, 2024 @ 9:37am by nparmar © PEARSON ENGINEERING LTD.



KEYMAP
N.T.S.

LEGEND

- PROPOSED ELEVATION
- EXISTING ELEVATION
- PROPOSED DIRECTION AND
- NVCA REGULATED AREA LINE
- PROPOSED RIPRAP
- PROPOSED SOAKAWAY PITS
- PROPERTY LINE
- PROP. WELL
- DRIVEWAY LOCATION
SUBJECT TO CHANGE AT PLOT
PLAN STAGE
- PROP. SEPTIC BED (400m² TYPICAL)
- HOUSE ENVELOPE
(320 m²)
- EXISTING/PROPOSED FLOODLINE

NOTE: SEE SEPTIC BED SIZING
IN FSR REPORT

NO.	REVISION NOTE	DATE	BY

BENCHMARK
ELEVATIONS ARE BASED ON GPS OBSERVATION TO PERMANENT REFERENCE
STATION IN THE NAD83(CRS-2010) COORDINATE SYSTEM AND HAVE BEEN
CORRECTED TO ORTHOMETRIC ELEVATION ON THE CGVD28 DATUM (1978
ADJUSTMENT) WITH GEOID MODEL HTv2.0, AS SUPPLIED BY NATURAL
RESOURCES CANADA.

TBM1, SPIKE IN HYDRO POLE, 458.51m.





CARNEVALE'S
537086 MAIN ST., HORNING'S MILLS
TOWNSHIP OF MELANCTHON

PRELIMINARY SITE SERVICING &
GRADING PLAN

		PEARSON ENGINEERING PEARSONENG.COM PH. 705.719.4785			
DESIGNED BY	AMC/IR	HORIZ SCALE	1:1000	PROJECT #	23008
DRAWN BY	NP/IR	VERT SCALE	N/A	DRAWING #	SSG-1
CHECKED BY	MWD/GMP	DATE	APRIL 2023	REVISION #	0

C:\Users\viparmar\AppData\Local\Temp\Aefubian_2872\23008 -- BASE -- GRADING -- ESR.dwg Layout:PND-1 Plotted Mar 22, 2024 @ 9:37am by nparmar @ PEARSON ENGINEERING LTD.



- KEYMAP**
N.T.S.
- LEGEND**
- PROPOSED ELEVATION
 - EXISTING ELEVATION
 - PROPOSED DIRECTION AND GRADE
 - MH
 - STORM MANHOLE
 - HIGH POINT
 - NVCA REGULATED AREA LINE
 - PROPOSED RIPRAP
 - EXISTING WELL
 - PROPERTY LINE
 - EXISTING/PROPOSED FLOODLINE

NO.	REVISION NOTE	DATE	BY

BENCHMARK
ELEVATIONS ARE BASED ON GPS OBSERVATION TO PERMANENT REFERENCE
STATION IN THE NAD83(CSRs-2010) COORDINATE SYSTEM AND HAVE BEEN
CORRECTED TO ORTHOMETRIC ELEVATION ON THE CGVD28 DATUM (1978
ADJUSTMENT) WITH GEOD MODEL HTv2.0, AS SUPPLIED BY NATURAL
RESOURCES CANADA.

TBM1, SPIKE IN HYDRO POLE, 458.51m.



CARNEVALE'S
537086 MAIN ST., HORNING'S MILLS
TOWNSHIP OF MELANCTHON

STORMWATER MANAGEMENT POND



DESIGNED BY	AMC/IR	HORIZ SCALE	1:250	PROJECT #	23008
DRAWN BY	NP/IR	VERT SCALE	N/A	DRAWING #	PND-1
CHECKED BY	MWD/GMP	DATE	APRIL 2023	REVISION #	0

C:\Users\viparma\AppData\Local\Temp\Aepubiah_2872\23008 -- BASE -- STORM DESIGN.dwg Layout:STM-1 Plotted Mar 22, 2024 @ 9:38am by viparma @ PEARSON ENGINEERING LTD.



				BENCHMARK ELEVATIONS ARE BASED ON GPS OBSERVATION TO PERMANENT REFERENCE STATION IN THE NAD83(CRS-2010) COORDINATE SYSTEM AND HAVE BEEN CORRECTED TO ORTHOMETRIC ELEVATION ON THE CGVD28 DATUM (1978 ADJUSTMENT) WITH GEOD MODEL HTv2.0, AS SUPPLIED BY NATURAL RESOURCES CANADA.					CARNEVALE'S 537086 MAIN ST., HORNING'S MILLS TOWNSHIP OF MELANCTHON		 PEARSON ENGINEERING PEARSONENG.COM PH. 705.719.4785		
				TBM1, SPIKE IN HYDRO POLE, 458.51m.									
NO.		REVISION NOTE		DATE		BY		PRE-DEVELOPMENT STORM CATCHMENT PLAN					
								DESIGNED BY AMC/IR				HORIZ SCALE 1:1000	PROJECT # 23008
								DRAWN BY NP/IR				VERT SCALE N/A	DRAWING # STM-1
								CHECKED BY MWD/GMP				DATE APRIL 2023	REVISION # 0

C:\Users\viparma\AppData\Local\Temp\Aspubliah_2872\23008 - BASE - STORM DESIGN.dwg Layout:STM-2 Plotted Mar 22, 2024 @ 9:35am by nparmar © PEARSON ENGINEERING LTD.



KEYMAP
N.T.S

LEGEND

- OVERLAND FLOW DIRECTION
- CATCHMENT AREA: 1 (0.75) ON NUMBER OR IMPERVIOUSNESS, 1.00 ha, AREA IN HECTARES
- CATCHMENT BOUNDARY
- NVCA REGULATED AREA LINE
- PROPOSED RIPRAP
- PROPOSED SOAKAWAY PITS
- EXISTING FLOODLINE
- PROPERTY LINE

BENCHMARK
ELEVATIONS ARE BASED ON GPS OBSERVATION TO PERMANENT REFERENCE
STATION IN THE NAD83(CSRS-2010) COORDINATE SYSTEM AND HAVE BEEN
CORRECTED TO ORTHOMETRIC ELEVATION ON THE CGVD28 DATUM (1978
ADJUSTMENT) WITH GEOD MODEL HTv2.0, AS SUPPLIED BY NATURAL
RESOURCES CANADA.

TBM1, SPIKE IN HYDRO POLE, 458.51m.



CARNEVALE'S
537086 MAIN ST., HORNING'S MILLS
TOWNSHIP OF MELANCTHON

POST-DEVELOPMENT STORM
CATCHMENT PLAN

		DESIGNED BY	AMC/IR	HORIZ SCALE	1:1000	PROJECT #	23008
		DRAWN BY	NP/IR	VERT SCALE	N/A	DRAWING #	STM-2
		CHECKED BY	MWD/GMP	DATE	APRIL 2023	REVISION #	0